



ROOM FINISH SCHEDULE

NO.	NAME	WALLS	WALLS SF	FLOOR	FLOOR SF	CEILING	CEILING SF	COMMENTS
2C-01	COM. HALL	GWB	-	VCT	61.30	2x2 ACOUSTIC CEILING TILE	61.30	INSPECT WALL HEATER
2C-02	E.E. STAIR	GWB	-	WOOD	59.60	2x2 ACOUSTIC CEILING TILE	59.60	
2C-03	PLUMB. CL.	UNKNOWN	-	UNKNOWN	6.00	UNKNOWN	6.00	
2A-01	KITCHEN	GWB/PANELING	-	VCT	117.80	2x2 ACOUSTIC CEILING TILE	117.80	REPLACE KITCHEN COOK HOOD & VENT TO OUTSIDE W/ SMOOTH WALL METAL DUCT, ADJUST AND RE-CAULK WINDOW 2A, REPLACE LIGHT FIXTURE ABOVE SINK
2A-02	BATH RM.	GWB	-	12x12 ADHESIVE BACKED VINYL	45.40	2x2 ACOUSTIC CEILING TILE	45.40	REPLACE BATHROOM FAN & VENT TO OUTSIDE W/ SMOOTH WALL METAL DUCT, REPLACE GFI OUTLET, REPLACE EXISTING VANITY W/ NEW 30" VANITY, REPLACE EXG. MEDICINE CABINET, STRIP AND RE-CAULK TUB, INSTALL NEW TRANSITION STRIP @ TUB BASE & RESEAL, & REPLACE DOOR
2A-03	CLOSET 1	GWB	-	VCT	4.70	2x2 ACOUSTIC CEILING TILE	4.70	
2A-04	LIVING ROOM	GWB/PANELING	-	VCT	179.90	2x2 ACOUSTIC CEILING TILE	179.90	REMOVE AND REPLACE VCT FLOORING
2A-05	BED RM.	GWB/PANELING	-	VCT	169.00	2x2 ACOUSTIC CEILING TILE	169.00	REMOVE AND REPLACE VCT FLOORING
2A-06	CLOSET 2	GWB	-	VCT	6.50	2x2 ACOUSTIC CEILING TILE	6.50	
2A-07	CLOSET 3	GWB	-	VCT	16.00	2x2 ACOUSTIC CEILING TILE	16.00	
2B-01	HALL	GWB	-	VCT	36.60	2x2 ACOUSTIC CEILING TILE	36.60	SEE NOTES ON DRAWING
2B-02	BED RM. 1	GWB/PANELING	-	VCT	163.80	2x2 ACOUSTIC CEILING TILE	163.80	INSTALL NEW HOLLOW CORE SLIDING DOOR
2B-03	CLOSET 1	GWB	-	VCT	13.40	2x2 ACOUSTIC CEILING TILE	13.40	
2B-04	CLOSET 2	GWB	-	VCT	6.80	2x2 ACOUSTIC CEILING TILE	6.80	
2B-05	BED RM. 2	PANELING	-	VCT	138.90	2x2 ACOUSTIC CEILING TILE	138.90	
2B-06	LIVING RM.	PANELING	-	VCT	170.70	2x2 ACOUSTIC CEILING TILE	170.70	
2B-07	KITCHEN	PANELING	-	VCT	171.60	2x2 ACOUSTIC CEILING TILE	171.60	REPLACE KITCHEN COOK HOOD & VENT TO OUTSIDE W/ SMOOTH WALL METAL DUCT, REPLACE CABINETS COMPLETE, REPLACE 7/8" RADIANT HEAT BASEBOARD, REPLACE LIGHT FIXTURE ABOVE SINK
2B-08	BATH RM.	GWB	-	LENOLEUM	43.40	2x2 ACOUSTIC CEILING TILE	43.40	REPLACE BATHROOM FAN & VENT TO OUTSIDE W/ SMOOTH WALL METAL DUCT, REPLACE GFI OUTLET, REPLACE TOILET, REPLACE EXISTING VANITY W/ NEW 30" VANITY, REPLACE EXG. MEDICINE CABINET, STRIP AND RE-CAULK TUB, INSTALL NEW TRANSITION STRIP @ TUB BASE & RESEAL, & REPLACE DOOR

- NOTES:
- PATCH AND PAINT ALL WALLS
 - STRIP, CLEAN, SEAL, WAX AND BUFF ALL EXG. VCT FLOORS
 - ALL SQUAR FOOT AMOUNTS ARE APPROXIMATE
 - INSTALL 1/2" GYP @ ALL CEILINGS ABOVE ACT WHERE GYP IS DAMAGED BEYOND REPAIR
 - Ⓢ = THERMOSTAT
 - ALL EXG. VCT STAIR LANDINGS AND TREADS TO BE REMOVED AND REPLACED W/ RUBBER TREADS AND LANDINGS.
 - REPLACE ALL APT. ENTRY DOORS W/ NEW STEEL DOORS, AND FRAMES.

ASSOCIATED DESIGN PARTNERS INC.
 Office: (207) 878-1751
 80 Leighton Road
 Falmouth, Maine 04105
 Fax: (207) 878-1788
 E-Mail: adp@adpengineering.com

THIS DRAWING, DESIGN AND ELECTRONIC FILE ARE THE PROPERTY OF ASSOCIATED DESIGN PARTNERS, INC. THE REPRODUCTION, COPYING OR ANY OTHER USE OF THIS DOCUMENT WITHOUT WRITTEN CONSENT IS PROHIBITED.

PROJECT: **22 PARK ST. PORTLAND, MAINE**
 SHEET TITLE: **EXG. SECOND FLOOR PLAN ISSUED FOR PERMITTING**

REVISIONS	DATE	DESCRIPTION
1	2-9-09	JAT
2	2-9-09	REVISED FROM WALK THRU ON 2-6-09
3	3-23-09	JAT
4		JAT
5		JAT
6		JAT
7		JAT

DATE : 2-6-09
 SCALE : AS NOTED
 DESIGN BY: JAT
 DRAWN BY: RSC
 PROJECT NUMBER:
08275
 SHEET NO:
A102