



ROOM FINISH SCHEDULE

NO.	NAME	WALLS	WALL SF	FLOOR	FLOOR SF	CEILING	CEILING SF	COMMENTS
3C-01	COM. HALL	GWB	-	VCT	91.50	2x2 ACOUSTIC CEILING TILE	91.50	
3C-02	E.E. STAIR	GWB	-	WOOD	51.20	2x2 ACOUSTIC CEILING TILE	51.20	
3C-03	PLUMB. CL.	UNKNOWN	-	VCT	6.00	2x2 ACOUSTIC CEILING TILE	6.00	
3A-01	KITCHEN	GWB/PANELING	-	VCT	117.80	2x2 ACOUSTIC CEILING TILE	117.80	REPLACE KITCHEN COOK HOOD & VENT TO OUTSIDE w/ SMOOTH WALL METAL DUCT, REPLACE LIGHT FIXTURE ABOVE SINK
3A-02	BATH RM.	GWB	-	VCT	45.40	2x2 ACOUSTIC CEILING TILE	45.40	REPLACE BATHROOM FAN & VENT TO OUTSIDE w/ SMOOTH WALL METAL DUCT, REPLACE GFI OUTLET, REPLACE EXISTING VANITY w/ NEW 30" VANITY, REPLACE EXG. MEDICINE CABINET, STRIP AND RE-CAULK TUB, INSTALL NEW TRANSITION STRIP @ TUB BASE & RESEAL, REMOVE EXG. FLOORING & REPLACE w/ LENOLEUM
3A-03	CLOSET 1	GWB	-	VCT	4.70	2x2 ACOUSTIC CEILING TILE	4.70	
3A-04	LIVING ROOM	GWB/PANELING	-	VCT	179.90	2x2 ACOUSTIC CEILING TILE	179.90	REMOVE & REPLACE VCT FLOORING
3A-05	BED RM.	GWB/PANELING	-	VCT	169.00	2x2 ACOUSTIC CEILING TILE	169.00	
3A-06	CLOSET 2	GWB	-	VCT	6.50	2x2 ACOUSTIC CEILING TILE	6.50	
3A-07	CLOSET 3	GWB	-	VCT	16.00	2x2 ACOUSTIC CEILING TILE	16.00	
3B-01	HALL	PANELING	-	VCT	36.60	2x2 ACOUSTIC CEILING TILE	36.60	ADD CLOSER TO ENTRY DOOR C7
3B-02	BED RM. 1	GWB/PANELING	-	VCT	163.80	2x2 ACOUSTIC CEILING TILE	163.80	
3B-03	CLOSET 1	GWB	-	VCT	13.40	2x2 ACOUSTIC CEILING TILE	13.40	REMOVE AND REPLACE SLIDING HOLLOW CORE CLOSET DOOR
3B-04	CLOSET 2	GWB	-	VCT	6.80	2x2 ACOUSTIC CEILING TILE	6.80	
3B-05	BED RM. 2	PANELING	-	VCT	138.90	2x2 ACOUSTIC CEILING TILE	138.90	
3B-06	LIVING RM.	PANELING	-	VCT	170.70	2x2 ACOUSTIC CEILING TILE	170.70	REMOVE & REPLACE VCT FLOORING, REPLACE HEAD TRIM @ CASSED OPENING
3B-07	KITCHEN	PANELING	-	VCT	171.60	2x2 ACOUSTIC CEILING TILE	171.60	REPLACE KITCHEN COOK HOOD & VENT TO OUTSIDE w/ SMOOTH WALL METAL DUCT, REPLACE BROKEN CABINET DOOR ABOVE STOVE, REPLACE KITCHEN SINK, FAUCET, REPLACE LIGHT FIXTURE ABOVE SINK
3B-08	CLOSET 3	GWB	-	VCT	4.40	2x2 ACOUSTIC CEILING TILE	4.40	
3B-09	BATH RM.	GWB	-	LENOLEUM	43.40	2x2 ACOUSTIC CEILING TILE	43.40	REPLACE BATHROOM FAN & VENT TO OUTSIDE w/ SMOOTH WALL METAL DUCT, REPLACE GFI OUTLET, REPLACE EXISTING VANITY w/ NEW 30" VANITY, REPLACE EXG. MEDICINE CABINET, STRIP AND RE-CAULK TUB, INSTALL NEW TRANSITION STRIP @ TUB BASE & RESEAL, & REPLACE DOOR C15

- NOTES:
1. PATCH AND PAINT ALL WALLS
 2. STRIP, CLEAN, SEAL, WAX AND BUFF ALL EXG. VCT FLOORS
 3. ALL SQUAR FOOT AMOUNTS ARE APPROXIMATE
 4. INSTALL 1/2" GYP @ ALL CEILINGS ABOVE ACT
 5. (T) HERE GYP IS DAMAGED BEYOND REPAIR
 6. = THERMOSTAT
 7. ALL EXG. VCT STAIR LANDINGS AND TREADS TO BE REMOVED AND REPLACED w/ RUBBER TREADS AND LANDINGS.
 8. REPLACE ALL ART. ENTRY DOORS w/ NEW STEEL DOORS, AND FRAMES.

ASSOCIATED DESIGN PARTNERS INC.
 Office: (207) 878-1751
 80 Leighton Road
 Falmouth, Maine 04105
 Fax: (207) 878-1788
 E-Mail: adp@adpengineering.com

THIS DRAWING, DESIGN AND ELECTRONIC FILE ARE THE PROPERTY OF ASSOCIATED DESIGN PARTNERS, INC. THE REPRODUCTION, COPYING OR ANY OTHER USE OF THIS DOCUMENT WITHOUT WRITTEN CONSENT IS PROHIBITED.

PROJECT: **22 PARK ST. PORTLAND, MAINE**
 SHEET TITLE: **EXG. THIRD FLOOR PLAN ISSUED FOR PERMITTING**

NO.	BY	DATE	DESCRIPTION
1	JAT	2-9-09	REVISED FROM WALK THRU ON 2-6-09
2	JAT	3-23-09	ISSUED FOR PERMITTING

DATE : 2-6-09
 SCALE : AS NOTED
 DESIGN BY: JAT
 DRAWN BY: RSC
 FILE #: 08275-A101.DWG
 PROJECT NUMBER:
08275
 SHEET NO:
A103