



ALTERNATE NO. 1:
 THE CONTRACTOR IS ASKED TO PROVIDE TEXTURED CEILING FINISHES WITHIN ALL SPACES OF ALL LIVING UNITS AS PART OF THE BASE BID. ALTERNATE NO.1 ASKES THAT THE CONTRACTOR PROVIDE 7/8" FLURRING AT 16" O.C. WITH 5/8" GYPSUM WALLBOARD SURFACING WITHIN ALL SPACES OF ALL THE LIVING UNITS THAT DO NOT CURRENTLY INDICATE GMB CEILING CONDITIONS. THE CONTRACTOR IS ASKED TO PROVIDE FINISHES WITHIN ALL LIVING UNITS. EXCEPTED PAINT APPLICATIONS THROUGHOUT THE UNITS AS PART OF THIS ALTERNATE PRICING.