

SECTION 12511

WINDOW TREATMENT

1 PART 1 GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of Contract including General and Supplementary Conditions and Division 1 specification sections apply to Work of this section.

1.2 SECTION INCLUDES

- A. Curtain rods.
- B. Roll-up shades.

1.3 SUBMITTALS

- A. Product Data: Provide data indicating physical and dimensional characteristics and operating features.
- B. Samples: Submit samples for selection of color and finish of shades.

2 PART 2 PRODUCTS

2.1 CURTAIN RODS

- A. Manufacturers:
  - 1. Bali-Graber Contract.
  - 2. Kirsch.
- B. Curtain Rods: Steel C shaped track system with nylon carriers, ball bearing pulleys and polyester cord traverse operation.
- C. Accessory Hardware: Type recommended by manufacturer.

2.2 ROLL-UP SHADES

- A. Shades: Vertical roll-up fabric window blind, with manual control to raise or lower by cord attached to stiffened lower blind edge.
  - 1. Fabric Sheeting: Vinyl treated cloth or 4 ply room-darkening.
  - 2. Pull Cord: Braided nylon.
  - 3. Color: As selected
- B. Roller: Wood or steel.
- C. Roller Mechanism: Internally fitted with hardware for blind operation.

- D. Attachment Hardware: Type recommended by blind manufacturer.

### 2.3 FABRICATION

- A. Fabricate blinds to fit within openings with uniform edge clearance of 1/2 inch.
- B. At openings requiring multiple blind units, provide separate blind assemblies with space of 1/2 inch between assemblies, occurring at window mullion centers.

## 3 PART 3 EXECUTION

### 3.1 EXAMINATION

- A. Verify that openings are ready to receive the work.

### 3.2 INSTALLATION

- A. Install blinds in accordance with manufacturer's instructions.
- B. Secure in place with flush countersunk fasteners.
- C. Adjust blinds for smooth operation.

...END OF SECTION