# CAST-IN-PLACE CONCRETE

### PART 1 - GENERAL

# 1.01 GENERAL REQUIREMENTS

- A. Related Documents: Drawings and general provisions of Contract.
- B. Examine all other sections of the Specifications for requirements which affect work of this Section whether or not such work is specifically mentioned in this Section.
- C. Coordinate work with that of all trades affecting or affected by work of this Section. Cooperate with such trades to assure the steady progress of all work under the Contract.

### 1.02 DESCRIPTION OF WORK:

### A. Work included:

Provide labor, materials, and equipment necessary to complete the work of this Section and, without limiting the generality thereof, furnish and include the following:

- The extent of cast-in-place concrete work is shown on drawings and includes (but not by way of limitation) formwork, reinforcing, cast-in-place concrete, accessories, and casting in of items specified under other Sections of the Specifications or furnished by Owner that are required to be built-in with the concrete.
- Equipment support pads indicated on mechanical drawings to be installed by the Building Contractor.

# 1.03 RELATED WORK:

- A. Miscellaneous Metal: Section 05500
  - 1. Expansion Anchors Section 05500
  - 2. Embedded Items Section 05500
- B. Anchor Bolts: Section 05120
- C. Joint Sealants: Section 07900

# CAST-IN-PLACE-CONCRETE

# 1.04 QUALITY ASSURANCE:

- A. Codes and Standards: Comply with provisions of the following except where more stringent requirements are shown or specified:
  - 1. ACI 213R-Latest Edition "Guide for Structural Lightweight Aggregate Concrete."
  - 2. ACI 211.1-Latest Edition "Recommended Practice for Selecting Proportions for Normal Heavyweight and Mass Concrete."
  - 3. ACI 212.2 Latest Edition "Guide for Use of Admixtures in Concrete."
  - 4. ACI 301-Latest Edition "Specifications for Structural Concrete for Buildings."
  - 5. ACI 302.1 Latest Edition "Guide for Concrete Floor and Slab Construction."
  - 6. ACI 304-Latest Edition "Recommended Practice for Measuring, Mixing, Transporting and Placing Concrete."
  - 7. ACI 304-2 Latest Edition "Placing Concrete by Pumping Methods."
  - 8. ACI 306 Latest Edition "Cold Weather Concreting."
  - 9. ACI 308-Latest Edition "Standard Practice for Curing Concrete."
  - 10. ACI 309-Latest Edition "Recommended Practice for Consolidation of Concrete."
  - 11. ACI 315-Latest Edition "Details and Detailing of Concrete Reinforcement."
  - 12. ACI 318-Latest Edition "Building Code Requirements for Reinforced Concrete."
  - 13. ACI 347-Latest Edition "Recommended Practice for Concrete Formwork."
  - 14. Concrete Reinforcing Steel Institute, "Placing Reinforcing Bars, 1976.

# CAST-IN-PLACE CONCRETE

- 15. ACI 211.2-Latest Edition "Standard Practice for Selecting Proportions for Structural Lightweight Concrete."
- B. Materials and installed work may require testing and retesting, as directed by the Architect, at any time during progress of work. Allow free access to material stockpiles and facilities. Tests not specifically indicated shall be done at Owner's expense. Retesting of rejected materials and installed work, shall be done at Contractor's expense.

# 1.05 SUBMITTALS:

A. Product Data: Submit manufacturer's product data with application and installation instructions for proprietary materials and items, including reinforcement and forming accessories, polypropylene fiber admixtures, patching compounds, non-shrink grout, water stops, joint systems, curing compounds, and others as requested by Architect.

# B. Shop Drawings:

- 1. Reinforcement: Submit shop drawings for fabrication, bending and placement of concrete reinforcement. Comply with ACI 315, showing bar schedules, stirrup spacing, diagrams of bent bars and arrangement of concrete reinforcement. Include special reinforcement required at openings through concrete structures.
- C. Samples: Submit samples of materials as specified and as otherwise requested by Architect, including names, sources and descriptions.
- D. Laboratory Test Reports: Submit laboratory test reports for concrete materials and mix design test if trial batch method is used for proportioning concrete mixes.
- E. Strength Tests: Provide required records of strength tests if field experience method is used for proportioning concrete mixes.

### PART 2 - PRODUCTS

### 2.01 FORM MATERIALS:

A. Forms for Exposed Finish Concrete: Unless otherwise indicated, construct formwork for exposed concrete surfaces with plywood, metal, metal-framed plywood faced or other acceptable panel-type materials, to provide continuous, straight, smooth, exposed surfaces. Furnish in largest practicable sizes to minimize number

### CAST-IN-PLACE-CONCRETE

of joints and to conform to joint system shown on drawings. Provide form material with sufficient thickness to withstand pressure of newly-placed concrete without bow or deflection.

- Use plywood complying with U.S. Product Standard PS-1 "B-B (Concrete Form) Plywood", Class I, Exterior Grade or better, mill-oiled and edge-sealed, with piece bearing legible inspection trademark.
- B. Forms for Unexposed Finish Concrete: Form concrete surfaces which will be unexposed in finished structure with plywood, lumber, metal or other acceptable material. Provide lumber dressed on at least 2 edges and one side for tight fit.
- C. Form Coatings: Provide commercial formulation form-coating compounds that will not bond with, stain nor adversely affect concrete surfaces, and will not impair subsequent treatments of concrete surfaces.

### 2.02 REINFORCING MATERIALS:

- A. Reinforcing Bars: ASTM A 615, Grade 60, deformed.
- B. Fiber Reinforcing: ASTM C1116, Type III virgin polypropylene fibers as manufactured by FIBERMESH.
  - The Fiber size (length) required shall be based on the largest size of the coarse aggregate in the concrete mix and determined by the manufacturer. Manufacturer shall submit written confirmation as to size of fibers which will be used based on concrete mix specified.
- C. Welded Wire Fabric: ASTM A 185, welded steel wire fabric. Provide welded wire fabric in flat sheets.
- D. Supports for Reinforcement: Provide supports for reinforcement including bolsters, chairs, spacers, and other devices for spacing, supporting and fastening reinforcing bars and welded wire fabric in place. Use wire bar type supports complying with CRSI recommendation, unless otherwise specified. Wood, brick and other devices are not acceptable.
  - 1. For slabs-on-grade, use supports with sand plates or horizontal runners where base material will not support chair legs.

# CAST-IN-PLACE CONCRETE

2. For exposed-to-view concrete surfaces, where legs of supports are in contact with forms, provide supports with legs which are plastic protected (CRSI, Class I) or stainless steel protected (CRSI, Class 2).

# 2.03 CONCRETE MATERIALS:

- A. Portland Cement: ASTM C 150, Type I or Type II, unless otherwise acceptable to Architect. Use one brand of cement throughout project, unless otherwise acceptable to Architect.
- B. Normal Weight Aggregates: ASTM C 33. Provide from a single source for exposed concrete. Do not use aggregates containing soluble salts or other substances such as iron sulfides, pyrite, marcasite, or othre which can cause stains on exposed concrete surfaces.
- C. Light Weight Aggregates: ASTM C 330.
- D. Water: Potable.
- E. Air-Entraining Admixture: ASTM C 260.
- F. High-Range Water-Reducing Admixture (Super Plasticizer): ASTM C 494, Type F or Type G containing not more than 1% chloride ions.
  - Fiber reinforcing shall be added and distributed prior to incorporation of Super Plasticizer.
- G. Normal range water reducing admixture: ASTM C 494 Type A containing no calcium chloride.
- H. Accelerating Admixture: ASTM C 494, Type C or E.
- I. Calcium Chloride not permitted.

### 2.04 RELATED MATERIALS:

- A. Moisture Barrier: Provide moisture barrier cover over prepared base material where indicated. Use only materials which are resistant to decay when tested in accordance with ASTM E154, as follows:
  - 1. Reinforced Polyethylene sheet not less than 6 mils thick.

### CAST-IN-PLACE-CONCRETE

- B. Non-Shrink Cement-based Grout: Provide grout consisting of premeasured, prepackaged materials supplied by the manufacturer requiring only the addition of water. Manufacturer's instructions must be printed on the outside of each bag.
  - Non-shrink: No shrinkage (0.0%) and a maximum 4.0% expansion when tested in accordance with ASTM C-827. No shrinkage (0.0%) and a maximum of 0.2% expansion in the hardened state when tested in accordance with CRD-C-621.
  - Compressive strength: A minimum 28 day compressive strength of 5000 psi when tested in accordance with ASTM C-109.
  - Setting time: A minimum initial set time of 60 minutes when 3. tested in accordance with ASTM C-191.
  - 4. Composition: Shall not contain metallic particles or expansive cement.
- C. Absorptive Cover: Burlap cloth made from jute or kenaf, weighing approximately 9 oz. per sq. yd., complying with AASHTO M182, Class 2.
- D. Moisture-Retaining Cover: One of the following, complying with ANSI/ASTM C 171.
  - 1. Waterproof paper.
  - 2. Polyethylene film.
  - 3. Polyethylene-coated burlap.
- E. Liquid Membrane-Forming Curing Compound:
  - 1. Liquid type membrane forming curing compound complying with ASTM C 309, Type I, Class A unless other type acceptable to Architect. Curing compound shall not impair bonding of any material to be applied directly to the concrete. Demonstrate the non-impairment prior to use.
- F. Preformed Expansion Joint Formers:
  - Bituminous Fiber Type, ASTM D 1751.

# CAST-IN-PLACE CONCRETE

- 2. Felt Void, Poly-Styrene Cap with removable top as manufactured by SUPERIOR.
- G. Slab Joint Filler:
  - 1. Multi-component polyurethane sealant (self-leveling type).
- H. WaterStop: Duroseal Gasket Waterstop & Duroseal paste by AWS (Absolute Waterproofing Systems, Inc.). Install per manufacturers printed instructions where required.

# 2.05 PROPORTIONING AND DESIGN OF MIXES:

- A. Prepare design mixes for each type and strength of concrete by either laboratory trial batch or field experience methods as specified in ACI 301. Use material, including all admixtures, proposed for use on the project. If trial batch method used, use an independent testing facility acceptable to Architect for preparing and reporting proposed mix designs. The testing facility shall not be the same as used for field quality control testing unless otherwise acceptable to Architect.
- B. Submit written reports to Architect of each proposed mix for each class of concrete at least 14 days prior to start of work. Do not begin concrete production until mixes have been reviewed by Architect.
- C. Proportion design mixes to provide concrete with the following properties:
  - Interior Elevated Slab:
    - a. Strength: 4000 psi @28 days, 3/4" aggr.
    - b. W/C Ratio: 0.44
    - c. Entrained Air: 4% + 1%
    - d. Slump: 3" + 1"
  - Interior Slabs-on-grade
    - a. Strength: 3500 psi @28 days, 3/8" aggr.
    - b. W/C Ratio: 0.44
    - c. Entrained Air: 4% + 1%
    - d. Slump: 3" + 1"
  - 3. Footings, Frost Walls & Piers.
    - a. Strength: 4000 psi @ 28 days, 3/4" aggr.

# CAST-IN-PLACE-CONCRETE

- b. W/C Ratio: 0.46
- c. Entrained Air: 4% + 1%
- d. Slump: 3" + 1"
- 4. Add air entraining admixture at manufacturers prescribed rate to result in concrete at point of placement having the above noted air contents.
  - a. 4% to 8% for maximum 3/4" aggregate.
  - b. 6% to 10% for maximum 3/8" aggregate.
- D. Adjustment to Concrete Mixes: Mix design adjustments may be requested by Contractor, when characteristics of materials, job conditions, weather, test results, or other circumstances warrant, at no additional cost to Owner and as accepted by Architect. Laboratory test data for revised mix design and strength results must be submitted to and accepted by Architect before using in work.
  - 1. Water may be added at the project only if the maximum specified slump and design mix maximum water/cement ratio is not exceeded.
  - 2. During hot weather, or under conditions contributing to rapid setting of concrete, a shorter mixing time than specified in ASTM C 94 may be required.

# 2.06 CONCRETE MIXING:

- A. Job-Site Mixing: Will not be permitted.
- B. Ready-Mix Concrete: Must comply with the requirements of ASTM C 94, and as herein specified. Provide batch ticket for each batch discharged and used in work, indicating project name, mix type, mix time and quantity.
  - During hot weather, or under conditions contributing to rapid setting of concrete, a shorter mixing time than specified in ASTM C 94 may be required by Engineer.
  - 2. When the air temperature is between 85 degrees F. and 90 degrees F., reduce the mixing and delivery time from 1 1/2 hours to 75 minutes, and when the air temperature is above 90 degrees F., reduce the mixing and delivery time to 60 minutes.

# PART 3 - EXECUTION

### 3.01 FORMS:

# CAST-IN-PLACE CONCRETE

- A. Design, erect, support, brace and maintain formwork to support vertical and lateral loads that might be applied until such loads can be supported by concrete structure. Construct formwork so concrete members and structures are of correct size, shape, alignment, elevation and position.
- B. Design, construct, erect, maintain, and remove forms for cast-inplace concrete work in compliance with ACI 347.
- C. Design formwork to be readily removable without impact, shock or damage to cast-in-place concrete surfaces and adjacent materials.
- D. Construct forms to sizes, shapes, lines and dimensions shown, and to obtain accurate alignment, location, grades, level and plumb work in finished structures. Provide for openings, offsets, keyways, recesses, moldings, rustication's, reglets, chamfers, blocking, screeds, bulkheads, anchorages and inserts, and other features required in work. Use selected materials to obtain required finishes. Solidly butt joints and provide backup at joints to prevent leakage of cement paste.
- E. Fabricate forms for easy removal without hammering or prying against concrete surfaces. Provide crush plates or wrecking plates where stripping may damage cast concrete surfaces. Provide top forms for inclined surfaces where slope is too steep to place concrete with bottom forms only. Kerf wood inserts for forming keyways, reglets, recesses, and the like to prevent swelling and for easy removal.
- F. Provide temporary openings where interior area of formwork is inaccessible for clean out, for inspection before concrete placement and for placement of concrete. Securely brace temporary openings and set tightly to forms to prevent loss of concrete mortar. Locate temporary openings on forms at inconspicuous locations.
- G. Chamfer exposed corners and edges as indicated, using wood, metal, PVC or rubber chamfer strips fabricated to produce uniform smooth lines and tight edge joints.
- H. Form Ties: Factory-fabricated, adjustable-length, removable or snapoff metal form ties, designed to prevent form deflection, and to prevent spalling concrete surfaces upon removal.
  - 1. Unless otherwise indicated, provide ties so portion remaining within concrete after removal is 1" inside concrete and will not leave holes larger than 1" diameter in concrete surface.

# CAST-IN-PLACE-CONCRETE

- I. Provision for Other Trades: Provide openings in concrete formwork to accommodate work of other trades. Determine size and location of openings, recesses, and chases from trades providing such items. Accurately place and securely support items built into forms.
- J. Cleaning and Tightening: Thoroughly clean forms and adjacent surfaces to receive concrete. Remove chips, wood, sawdust, dirt or other debris just before concrete is placed. Retighten forms and bracing after concrete placement as required to eliminate mortar leaks and maintain proper alignment.

# 3.02 PLACING REINFORCEMENT:

- A. Comply with Concrete Reinforcing Steel Institute's recommended practice for "Placing Reinforcing Bars", for details and methods of reinforcement placement and supports, and as herein specified.
  - Clean reinforcement of loose rust and mill scale, earth, ice, and other materials which reduce or destroy bond with concrete.
  - Accurately position, support and secure reinforcement against displacement by formwork, construction, or concrete placement operations. Locate and support reinforcing by metal chairs, runners, bolsters, spacers and hangers, as required.
  - 3. Place reinforcement to obtain specified coverages for concrete protection within tolerances of ACI-318. Arrange, space and securely tie bars and bar supports to hold reinforcement in position during concrete placement operations. Set wire ties so ends are directed into concrete, not toward exposed concrete surfaces.
  - 4. Fiber Reinforcing shall be introduced directly into the concrete either at the batch plant or job site at the rate of 1.6 pounds (minimum) per cubic yard. If introduced at the batch plant with the aggregate, no extra mixing time is required. If added at the job site, approximately 3 to 5 minutes mixing at agitating speed is required.

# CAST-IN-PLACE CONCRETE

5. Install welded wire fabric in flat sheets in as long lengths as practicable. Lap adjoining pieces at least one full mesh and lace splices with wire. Offset end laps in adjacent widths to prevent continuous laps in either direction.

# 3.03 JOINTS:

- A. Construction Joints: Locate and install construction joints, which are not shown on drawings, so as not to impair strength and appearance of the structure, as acceptable to Architect.
  - Provide keyways at least 1-1/2" deep in construction joints in walls, and slabs; accepted bulkheads designed for this purpose may be used for slabs.
  - 2. Roughened surfaces shall be used between walls and footings unless shown otherwise on the drawings. The footing surface shall be roughened to at least an amplitude of 1/4" for the width of the wall before placing the wall concrete.
  - 3. Place construction joints perpendicular to the main reinforcement. Continue reinforcement across construction joints.
  - 4. Joints in slabs on grade shall be located and detailed as indicated on the drawings. If saw-cut joints are required or permitted, cutting shall be timed properly with the set of the concrete: Cutting shall be started as soon as the concrete has been hardened sufficiently to prevent aggregate being dislodged by the saw, and shall be completed before shrinkage stresses become sufficient to produce cracking.

# 3.04 INSTALLATION OF EMBEDDED ITEMS:

- A. General: Set and build into work anchorage devices and other embedded items required for other work that is attached to, or supported by, cast-in-place concrete. Use setting drawings, diagrams, instructions and directions provided by suppliers of items to be attached thereto. Notify other trades to permit installation of their work.
- B. Edge Forms and Screed Strips for Slabs: Set edge forms or bulkheads and intermediate screed strips for slabs to obtain required elevations and contours in finished slab surface.

# 3.05 INSTALLATION OF GROUT

# CAST-IN-PLACE-CONCRETE

- A. Place grout for base plates in accordance with manufacturer's recommendations.
- B. Grout below setting plates as soon as practicable to facilitate erection of steel and prior to removal of temporary bracing and quys. If leveling bolts or shims are used for erection grout shall be installed prior to addition of any column load.
- C. Pack grout solidly between bearing surfaces and bases or plates to ensure that no voids remain. Finish exposed surfaces, protect installed materials and allow to cure. For proprietary grout materials, comply with manufacturer's instructions.

# 3.06 PREPARATION OF FORM SURFACES:

- A. Coat contact surfaces of forms with a form-coating compound before reinforcement is placed.
- B. Thin form-coating compounds only with thinning agent of type, and in amount, and under conditions of form-coating material manufacturer's directions. Do not allow excess form coating to accumulate in forms or to come into contact with concrete surfaces against which fresh concrete will be placed. Apply in compliance with manufacturer's instructions.

# 3.07 CONCRETE PLACEMENT:

- A. Preplacement Review: Footing bottoms, reinforcement and all work shall be subject to review by the Architect. Verify that reinforcing, ducts, anchors, seats, plates and other items to be cast into concrete are placed and securely held. Notify Architect 48 hours prior to scheduled placement and obtain approval or waiver of review prior to placement. Moisten wood forms immediately before placing concrete where form coatings are not used. Be sure that all debris and other foreign matter is removed from forms.
- B. General: Comply with ACI 304, and as herein specified.
  - Deposit concrete continuously or in layers of such thickness that no concrete will be placed on concrete which has hardened sufficiently to cause the formation of seams or planes of weakness. If a section cannot be placed continuously, provide construction joints as herein specified. Deposit concrete as

# CAST-IN-PLACE CONCRETE

nearly as practicable to its final location to avoid segregation due to rehandling or flowing.

- 2. Concrete shall be handled from the mixer to the place of final deposit as rapidly as practicable by methods which will prevent segregation or loss of ingredients and in a manner which will assure that the required quality of the concrete is maintained.
- 3. Conveying equipment shall be approved and shall be of a size and design such that detectable setting of concrete shall not occur before adjacent concrete is placed. Conveying equipment shall be cleaned at the end of each operation or work day. Conveying equipment and operations shall conform to the following additional requirements:
  - Belt conveyors shall be horizontal or at a slope which will not cause excessive segregation or loss of ingredients. Concrete shall be protected against undue drying or rise in temperature. An arrangement shall be used at the discharge end to prevent apparent segregation. Mortar shall not be allowed to adhere to the return length of the belt. Long runs shall be discharged into a hopper or through a baffle.
  - b. Chutes shall be metal or metal-lined and shall have a slope not exceeding 1 vertical to 2 horizontal and not less than 1 vertical to 3 horizontal. Chutes more than 20 feet long, and chutes not meeting the slope requirements may be used provided they discharge into a hopper before distribution.
  - Pumping or pneumatic conveying equipment shall be of suitable kind with adequate pumping capacity. Pneumatic placement shall be controlled so that segregation is not apparent in the discharged concrete.
  - The loss of slump in pumping or pneumatic conveying equipment shall not exceed 2 inches. Concrete shall not be conveyed through pipe made of aluminum alloy. Standby equipment shall be provided on the site.
  - e. Tined rakes are prohibited as a means of conveying fiber reinforced concrete.
- 4. Do not use reinforcement as bases for runways for concrete conveying equipment or other construction loads.

# CAST-IN-PLACE-CONCRETE

- C. Placing Concrete in Forms: Deposit concrete in forms in horizontal layers not deeper than 18 inches and in a manner to avoid inclined construction joints. Where placement consists of several layers, place each layer while preceding layer is still plastic to avoid cold joints.
  - Consolidate placed concrete by mechanical vibrating equipment supplemented by hand-spading, redoing or tamping. Use equipment and procedures for consolidation of concrete in accordance with ACI recommended practices.
  - Use vibrators designed to operate with vibratory equipment submerged in concrete, maintaining a speed of not less than 8000 impulses per minute and of sufficient amplitude to consolidate the concrete effectively. Do not use vibrators to transport concrete inside forms. Insert and withdraw vibrators vertically at uniformly spaced locations not farther than visible effectiveness of machine, generally at points 18 inches maximum apart. Place vibrators to rapidly penetrate placed layer and at least 6 inches into the preceding layer. Do not insert vibrators into lower layers of concrete that have begun to set. At each insertion maintain the duration of vibration for the time necessary to consolidate concrete and complete embedment of reinforcement and other embedded items without causing segregation of mix, generally from 5 to 15 seconds. A spare vibrator shall be kept on the job site during all concrete placing operation.
- D. Placing Concrete Slabs: Deposit and consolidate concrete slabs in a continuous operation, within limits of construction joints, until the placing of a panel or section is completed.
  - 1. Consolidate concrete using internal vibrators during placing operations so that concrete is thoroughly worked around reinforcement and other embedded items and into corners.
  - 2. Bring slab surfaces to correct level with straightedge and strikeoff. Use bull floats or darbies to smooth surface, free of humps or hollows. Do not disturb slab surfaces prior to beginning finishing operations. Do not sprinkle water on plastic surface.
  - 3. Maintain reinforcing in proper position during concrete placement operations.

# CAST-IN-PLACE CONCRETE

- E. Cold Weather Placing: Protect concrete work from physical damage or reduced strength which could be caused by frost, freezing actions, or low temperatures, in compliance with ACI 306 and as herein specified.
  - When air temperature has fallen to or is expected to fall below 40 deg.F (4 deg.C), uniformly heat water and aggregates before mixing to obtain a concrete mixture temperature of not less than 50 deg.F (10 deg.C), and not more than 80 deg.F (27 deg.C) at point of placement.
  - Do not use frozen materials or materials containing ice or snow. Do not place concrete on frozen subgrade or on subgrade containing frozen materials.
  - 3. Do not use calcium chloride, salt and other materials containing antifreeze agents or chemical accelerators.
  - 4. All temporary heat, form insulation, insulated blankets, coverings, hay or other equipment and materials necessary to protect the concrete work from physical damage caused by frost, freezing action, or low temperature shall be provided prior to start of placing operations.
  - 5. When the air temperature has fallen to or is expected to fall below 40 deg.F, provide adequate means to maintain the temperature in the area where concrete is being placed between 50 and 70 deq.F.
- F. Hot Weather Placing: When hot weather conditions exist that would seriously impair quality and strength of concrete, place concrete in compliance with ACI 305 and as herein specified.

Cool ingredients before mixing to maintain concrete temperature at time of placement below 90 deg.F. Mixing water may be chilled, or chopped ice may be used to control the concrete temperature provided the water equivalent of the ice is calculated to the total amount of mixing water.

Cover reinforcing steel with water-soaked burlap if it becomes too hot, so that the steel temperature will not exceed the ambient air temperature immediately before embedment in concrete.

Wet forms thoroughly before placing concrete.

### CAST-IN-PLACE-CONCRETE

Do not use retarding admixtures without the written acceptance of the Architect.

# 3.08 FINISH OF FORMED SURFACES:

- A. Rough Form Finish: For formed concrete surfaces not exposed-to-view in the finish work or by other construction, unless otherwise indicated. This concrete surface shall have texture imparted by form facing material, with tie holes and defective areas repaired and patched and fins and other projections exceeding 1/4 in. in height rubbed down or chipped off.
- B. Smooth Form Finish: For formed concrete surfaces exposed-to-view, or that are to be covered with a coating material applied directly to concrete, or a covering material applied directly to concrete, such as waterproofing, damp-proofing, painting or other similar system. This as-cast concrete surface shall be obtained with selected form facing material, arranged orderly and symmetrically with a minimum of seams. Repair and patch defective areas with fins or other projections completely removed and smoothed.
- C. Grout Cleaned Finish: Provide grout cleaned finish to scheduled concrete surfaces which have received smooth form finish treatment. Combine one part Portland cement to 1-1/2 parts fine sand by volume and mix with water to consistency of thick paint. Proprietary additives may be used at Contractor's option. Blend standard Portland cement and white Portland cement, amounts determined by trial patches, so that final color of dry grout will closely match adjacent surfaces.

Thoroughly wet concrete surfaces and apply grout to coat surfaces and fill small holes. Remove excess grout by scraping and rubbing with clean burlap. Keep damp by fog spray for at least 36 hours after rubbing.

D. Related Unformed Surfaces: At tops of walls and grade beams, horizontal offset surfaces occurring adjacent to formed surfaces, strike-off, smooth and finish with a texture matching adjacent uniformed surfaces. Continue final surface treatment of formed surfaces uniformly across adjacent unformed surfaces, unless otherwise indicated.

### 3.09 MONOLITHIC SLAB FINISHES:

# CAST-IN-PLACE CONCRETE

- A. Scratch Finish: Apply scratch finish to monolithic slab surfaces that are to receive concrete floor topping or mortar setting beds, and as otherwise indicated.
  - 1. After placing slabs, plane surface to a tolerance not exceeding 1/2 in. in 10 ft. when tested with a 10-ft. straightedge. Slope surfaces uniformly to drains where required. After leveling, roughen surface before final set with stiff brushes, brooms or rakes.
- B. Float Finish: Apply float finish to monolithic slab surfaces to receive trowel finish and other finishes as hereinafter specified, and slab surfaces which are to be covered with membrane or elastic waterproofing, and as otherwise indicated.
  - 1. After screening, consolidating, and leveling concrete slabs, do not work surface until ready for floating. Begin floating when surface water has disappeared or when concrete has stiffened sufficiently to permit operation of power-driven floats, or by hand-floating if area is small or inaccessible to power units. Check and level surface plane to a tolerance not exceeding 1/4 in. in 10 ft. when tested with a 10 ft. straightedge. Cut down high spots and fill low spots. Uniformly slope surfaces to drains. Immediately after leveling, refloat surface to a uniform, smooth, granular texture.
- C. Trowel Finish: Apply trowel finish to monolithic slab surfaces indicated, including slab surfaces to be covered with carpet, resilient flooring, paint or other thin-film finish coating system.
  - 1. After floating, begin first trowel finish operation using a power-driven trowel. Begin final troweling when surface produces a ringing sound as trowel is moved over surface. Consolidate concrete surface by final hand-troweling operation, free of trowel marks, uniform in texture and appearance, and with a surface plane tolerance not exceeding 1/4 in. in 10 ft. when tested with a 10-ft. straightedge. Grind smooth any surface defects which would telegraph through applied floor covering system.
- D. Non-Slip Broom Finish: Apply non-slip broom finish to exterior concrete platforms, steps and ramps, and elsewhere as indicated.
  - Immediately after trowel finishing, slightly roughen concrete surface by brooming with fiber bristle broom perpendicular to

# CAST-IN-PLACE-CONCRETE

main traffic route. Coordinate required final finish with Architect before application.

### 3.10 CONCRETE CURING AND PROTECTION:

- A. General: Protect freshly placed concrete from premature drying and excessive cold or hot temperatures. Protect concrete work from physical damage or reduced strength which could be caused by frost, freezing actions, or low temperatures, in compliance with the requirements of ACI 306 as herein specified.
  - 1. Start initial curing as soon as free water has disappeared from concrete surface after placing and finishing. Weather permitting, keep continuously moist for not less than 7 days.
  - 2. Begin final curing procedures immediately following initial curing and before concrete has dried. Continue final curing for at least 7 days in accordance with ACI 301 procedures. Avoid rapid drying at end of final curing period.
    - Curing shall be continued for at least 7 days in the case of all concrete except high-early-strength concrete for which the period shall be at least 3 days. Alternatively, if tests are made of cylinders kept adjacent to the structure and cured by the same methods, moisture retention measures may be terminated when the average compressive strength has reached 70 percent of the specified strength, f'c. If one of the curing procedures below is used initially, it may be replaced by one of the other procedures any time after the concrete is 1 day old provided the concrete is not permitted to become surface dry during the transition.
  - 3. When the mean daily temperature is less than 40 deg.F, the temperature of the concrete shall be maintained between 50 and 70 deg.F for the required curing period.
    - When necessary, arrangements for heating, covering, insulation, or housing the concrete work shall be adequate to maintain the required temperature without injury due to concentration of heat. Combustion heaters shall not be used during the first 24 hours unless precautions are taken to prevent exposure of the concrete to exhaust gases which contain carbon dioxide.

# CAST-IN-PLACE CONCRETE

- Keep protections in place and intact at least 24 hours after artificial heat is discontinued. Avoid rapid dry-out of concrete due to overheating and avoid thermal shock due to sudden cooling or heating.
- c. Changes in temperature of the air immediately adjacent to the concrete during and immediately following the curing period shall be kept as uniform as possible and shall not exceed 5 deg.F in any 1 hour or 50 deg.F in any 24 hour period.
- B. Curing Methods: Perform curing of concrete by moist curing, by moisture-retaining cover curing, by curing compound, and by combinations thereof, as herein specified.
  - 1. Provide moisture curing by following methods:
    - Keep concrete surface continuously wet by covering with water.
    - b. Continuous water-fog spray.
    - c. Covering concrete surface with specified absorptive cover, thoroughly saturating cover with water and keeping continuously wet. Place absorptive cover to provide coverage of concrete surfaces and edges, with 4-in. lap over adjacent absorptive covers.
  - 2. Provide moisture-cover curing as follows:
    - Cover concrete surfaces with moisture-retaining cover for curing concrete, placed in widest practicable width with sides and ends lapped at least 3 in. and sealed by waterproof tape or adhesive. Immediately repair any holes or tears during curing period using cover material and waterproof tape.
  - 3. Provide curing compound to slabs as follows:
    - Apply specified curing and sealing compound to concrete slabs as soon as final finishing operations are complete (within 2 hours). Apply uniformly in continuous operation by power-spray or roller in accordance with manufacturer's directions. Recoat areas subjected to heavy rainfall within 3 hours after initial application. Maintain

# CAST-IN-PLACE-CONCRETE

continuity of coating and repair damage during curing period.

- c. Separating compound may be used as a curing medium if applied in accordance with manufacturer's specifications.
- C. Curing Formed Surfaces: Cure formed concrete surfaces, including undersides of beams, supported slabs and other similar surfaces by moist curing with forms in place for full curing period or until forms are removed. If forms are removed, continue curing by methods specified above, as applicable.
- D. Protection From Mechanical Injury: During the curing period, the concrete shall be protected from damaging mechanical disturbances, such as load stresses, heavy shock, and excessive vibration. All finished concrete surfaces shall be protected from damage by construction equipment, materials, or methods, by application of curing procedures, and by rain or running water. Self-supporting structures shall not be loaded in such a way as to overstress the concrete.

### 3.11 REMOVAL OF FORMS:

- A. Formwork not supporting weight of concrete, such as sides of beams, walls, columns, and similar parts of the work, may be removed after cumulatively curing at not less than 50 deg.F (10 deg.C) for 24 hours after placing concrete, provided concrete is sufficiently hard to not be damaged by form removal operations, and provided curing and protection operations are maintained.
- B. Formwork supporting weight of concrete, such as beam soffits, joints, slabs and other structural elements, may not be removed in less than 14 days and until concrete has attained design minimum compressive strength at 28 days. Determine potential compressive strength of in-place concrete by testing field-cured specimens representative of concrete location or members.
- C. Form facing material may be removed 4 days after placement only if shores and other vertical supports have been arranged to permit removal of form facing material without loosening or disturbing shores and support.

# 3.12 REUSE OF FORMS:

# CAST-IN-PLACE CONCRETE

- A. Clean and repair surfaces of forms to be reused in work. Split, frayed, delaminated or otherwise damaged form facing material will not be acceptable for exposed surfaces. Apply new form coating compound as specified for new formwork.
- B. When forms are extended for successive concrete placement, thoroughly clean surfaces, remove fins and laitance, and tighten forms to close joints. Align and secure joint to avoid offsets. Do not use "patched" forms for exposed concrete surfaces, except as acceptable to Architect.

# 3.13 MISCELLANEOUS CONCRETE ITEMS:

A. Filling In: Fill in holes and openings left in concrete structures for passage of work by other trades, unless otherwise shown or directed, after work of other trades is in place. Mix, place, and cure concrete as herein specified, to blend with in-place construction. Provide other miscellaneous concrete filling shown or required to complete work.

# 3.14 CONCRETE SURFACE REPAIRS:

- A. Patching Defective Areas: Repair and patch defective areas with cement mortar immediately after removal of forms, when acceptable to the Architect.
  - 1. Cut out honeycomb, rock pockets, voids over 1/4 inch in any dimension, and holes left by tie rods and bolts, down to solid concrete but in no case to a depth of less than 1 inch. Make edges of cuts perpendicular to the concrete surface. Thoroughly clean, dampen with water, and brush coat the area to be patched with specified bonding agent. Place patching mortar after bonding compound has dried.
  - 2. For exposed-to-view surfaces, blend white Portland cement and standard Portland cement so that, when dry, patching mortar will match color surrounding. Provide test areas at inconspicuous location to verify mixture and color match before proceeding with patching. Compact mortar in place and strike-off slightly higher than surrounding surface.
- B. Repair of Formed Surfaces: Remove and replace concrete having defective surfaces if defects cannot be repaired to satisfaction of Architect. Surface defects, as such, include color and texture irregularities, cracks, spalls, air bubbles, honeycomb, rock

# CAST-IN-PLACE-CONCRETE

pockets, fins, and other projections on surface and stains and other discolorations that cannot be removed by cleaning. Flush out form tie holes, fill with dry pack mortar or precast cement cone plugs secured in place with bonding agent.

- Repair concealed formed surfaces, where possible, that contain defects that affect the durability of concrete. If defects cannot be repaired, remove and replace concrete.
- 2. Correct high areas in unformed surfaces by grinding after concrete has cured at least 14 days.
- 3. Correct low areas in unformed surfaces during, or immediately after completion of surface finishing operations by cutting out low areas and replacing with fresh concrete. Proprietary patching compounds may be used when acceptable to Architect.
- 4. Repair defective areas, except random cracks and single holes not exceeding 1 inch in diameter, by cutting out and replacing with fresh concrete. Remove defective areas to sound concrete with clean, square cuts and expose reinforcing steel with at least 3/4 inch clearance all around. Dampen concrete surfaces in contact with patching concrete and apply bonding compound. Mix patching concrete of same materials to provide concrete of same type or class as original concrete. Place, compact, and finish to blend with adjacent finished concrete. Cure in the same manner as adjacent concrete.
- 5. Repair isolated random cracks and single holes not over 1 inch in diameter by dry-pack method. Groove top of cracks and cut out holes to sound concrete and clean of dust, dirt, and loose particles. Dampen cleaned concrete surfaces and apply bonding compound. Mix dry-pack, consisting of one part Portland cement to 2-1/2 parts fine aggregate passing a No. 16 mesh sieve, using only enough water as required for handling and placing. Place dry-pack after bonding compound has dried. Compact dry-pack mixture in place and finish to match adjacent concrete. Keep patched area continuously moist for not less than 72 hours.
- 6. Use epoxy-based mortar for structural repairs, where directed by the Architect.
- 7. Repair methods not specified above may be used, subject to acceptance of the Architect.

# CAST-IN-PLACE CONCRETE

# 3.15 QUALITY CONTROL TESTING DURING CONSTRUCTION:

- A. The Contractor shall employ a testing laboratory to inspect, sample and test the materials and the production of concrete and to submit test reports. Concrete testing shall be performed by technicians certified by the Maine Concrete Technician Certification Board.
- B. Concrete shall be sampled and tested for quality control during placement of concrete shall include the following, unless otherwise directed by Architect.
- C. Sampling Fresh Concrete: ASTM C 172.
  - 1. Slump: ASTM C 143; one test for each concrete load at point of discharge and one test for each set of compressive strength test specimens. A slump test must be run prior to the incorporation of the CFP fibers per recommendations of ACI 544.
  - 2. Air Content: ASTM C 231 "Pressure method for normal weight concrete." One for each set of compressive strength test specimens.
  - Concrete Temperature: Test hourly when air temperature is 40 deg.F (4 deg.C) and below, and when 80 deg.F (27 deg.C) and above; and each time a set of compression test specimens are made.
  - Compression Test Specimen: ASTM C 31; one set of 4 standard cylinders for each compressive strength test, unless otherwise directed. Mold and store cylinders for laboratory cured test specimens except when field-cure test specimens are required.
    - Fiber reinforced concrete test specimens shall be vibrated externally per recommendations ACI 544.
  - Compressive Strength Tests: ASTM C 39; one set for each 100 cu. yds. or fraction thereof, of each concrete class placed in any one day or for each 5,000 sq. ft. of surface area placed; 1 specimen tested at 7 days, 2 specimens tested at 28 days, and 1 specimen retained in reserve for later testing if required.
    - When frequency of testing will provide less than 5 strength tests for a given class of concrete, conduct testing from at least 5 randomly selected batches or from each batch if fewer than 5 used.

# CAST-IN-PLACE-CONCRETE

- When total quantity of a given class of concrete is less than 50 cu. yds., strength test may be waived, if in the Architect's judgement, adequate evidence of satisfactory strength is provided.
- When strength of field-cured cylinders is less than 85 percent of companion laboratory-cured cylinders, evaluate current operations and provide corrective procedures for protecting and curing the in-place concrete.
- Strength level of concrete will be considered satisfactory if averages of sets of three consecutive strength test results equal or exceed specified compressive strength and no individual strength test result falls below specified compressive strength by more than 500 psi.
- e. Test results will be reported in writing to Architect and Contractor on the day after tests are made. Reports of compressive strength tests shall contain the project identification name and number, date of concrete placement, name of concrete testing service, concrete type and class, location of concrete batch in structure, design compressive strength at 28 days, concrete mix proportions and materials compressive breaking strength, and type of break for both 7-day tests and 28-day tests.
- D. Additional Tests: The testing service will make additional tests of in-place concrete when test results indicate specified concrete strengths and other characteristics have not been attained in the structure, as directed by the Architect. Testing service may conduct tests to determine adequacy of concrete by cored cylinders complying with ASTM C 42, or by other methods, as directed. Contractor shall pay for such tests conducted, and any other additional testing as may be required, when unacceptable concrete is verified.

# 3.16 ENGINEER'S REVIEW

A. The Engineer of Record will conduct periodic reviews of the construction for compliance with the provisions of the Design Documents during the construction period.

# CAST-IN-PLACE CONCRETE

B. The General Contractor shall employ a licensed professional engineer to analyze and design modifications and repairs for construction not in conformance with the provisions of the Contract Documents. These modifications and repair details shall be stamped by an engineer licensed to practice in the State of Maine and submitted with calculations for approval by the Engineer of Record. Modifications shall not be made without express written approval.

END OF SECTION