

YMCA High Street Entry				
Portland, ME				5/13/2005
Hardware Schedule				
Item/function	Manufacturer	Model No.	Finish	Remarks
Lockset No. 1	Sargent	8205LB	626	Mortice Lever - Office/Entrance Function
Storage Set	Sargent	8204LB	626	Mortice Lever - Storage Function
Passage Set	Sargent	8215LB	626	Mortice Lever - Passage Function
Privacy Set	Sargent	8265LB	626	Mortice Lever - Privacy Function
Push/Pull	Ives	8102-8 Pull 8200 4x16 Push	626	
Top & Bottom Flush Bolts	Ives	358	626	Install top and bottom of inactive leaf (left upon exit)
Exit Device No. 1	Sargent	8513 713ETA	626	
Exit Device No. 2	Sargent	8613 713 ETA	626	
Exit Device No. 3	Sargent	8515 713 ETA	626	
Closer No. 1	Sargent	281 Series	626	w/ hold open
Closer No. 2	Sargent	1430/1431	626	w/ hold open
Threshold	Pemko	252X3	Alum	Thermal barrier, ADA compliant - maximum 1/2" height
Hinges	Hager	Full Mortise	26D	Provide ball bearing hinges at all doors.
Floor Stop	Ives	436	Alum	
Wall Stop	Ives	406 1/2	Alum	
Door Bottom Sweep	National Guard	96DkB		
Weatherstripping	National Guard	160V & 5050B		
8x32 Kick Plate	Ives	8400	SS	
Electric Strike	Folger Adam	700 Series		
Power Assisted Operator	Dor-O-Matic	Senior Swing		Provide push botton activators at interior and exterior side of doors
Notes				
Provide masterkey system with construction keying. Consult with Owner for instructions on keying.				
Products of one or more manufacturers are listed to establish quality and performance characteristics.				
Products of other manufacturers may be accepted subject to review and approval by Architect prior to bid.				
Provide wall or floor stops at all swinging doors				
Acceptable Manufacturers				
Locksets:	Sargent, Schlage			
Closers:	Sargent, Dorma, Norton			
Hinges:	Hager, Stanley, Lawrence			
Thresholds:	National Guard Products, Pemko, Reese, Zero			
Panic sets:	Sargent, Von Duprin			
Accessories	Ives, Hiawatha, Rockwood			