FOOTING SCHEDULE

MARK	SIZE	REINF
F4	4'-0"x4'-0"x1'-0"	4#5 E.W.B.
F5	5'-0"x5'-0"x1'-0"	5#5 E.W.B.
F6	6'-0"x6'-0"x1'-0"	5#5 E.W.B.
F7	7'-0"x7'-0"x1'-2"	6#6 E.W.B.
F8	8'-0"x8'-0"x1'-4"	7#6 E.W.B.
F9	9'-0"x9'-0"x1'-6"	7#7 E.W.B.
F10	10'-0"x10'-0"x1'-6"	8#7 E.W.B.
F11	11'-0"x11'-0"x1'-8"	8#8 E.W.B.
F75	7'-0"x5'-0"x1'-2"	6#6 L.W.B. 8#5 S.W.B.

FOUNDATION PLAN

1/8"=1'-0"

NOTES:

1. TOP OF SLAB EL 100'-0". SITE DATUM EL 67.90'
2. TOP OF WALL EL, SEE PLAN
3. P1, P2, ETC INDICATES CONC PIER. {X'-XX"} INDICATES TOP OF PIER EL. SEE PIER DETAILS DWG S2.3 FOR ADDL INFO.
4. F3, F4, ETC INDICATES FOOTING TYPE. (X'-X") INDICATES TOP OF FOOTING EL. SEE SCHEDULE THIS DWG.
5. C.J. INDICATES CONSTRUCTION/CONTRACTION JOINT. SEE TYP DETAILS DWG S2.1 FOR ADDL INFO.
6. S.K. INDICATES SHEAR KEY TO BE FORMED IN CONC PIER OR FOOTING.
7. BP-X INDICATES COLUMN BASE PLATE TYPE. SEE BASE PLATE DETAILS DWG S3.1 FOR ADDL INFO.
8. NOTE ALL SLABS SHALL CONTAIN BARRIER 1 ADMIXTURE. REFERENCE SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.

CITY OF PORTLAND, MAINE
Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 01/14/15

CWS Architects

STATE OF MAINE
ETHAN A. RHILE
NO.10266
LICENSED PROFESSIONAL ENGINEER

BECKER STRUCTURAL ENGINEERS
75 York Street, Portland, Maine 04101
207.879.1838 ▪ beckerstructural.com

OWNER / DEVELOPER
AVESTA 409 CUMBERLAND LP
C/O AVESTA HOUSING
307 CUMBERLAND AVENUE
PORTLAND ME

PROJECT TITLE
409 CUMBERLAND AVENUE
PORTLAND ME
409 CUMBERLAND AVENUE
PORTLAND ME

DRAWING TITLE
FOUNDATION PLAN
CWS PROJ. NO.: 11.449

DATE

REVISION DESCRIPTION

DRAWING NUMBER
S1.1

SCALE: NOTED
DATE: 09/16/2013

9/17/2013 3:30 PM

H:\PROJECTS\#11000-3000\3028 409 Cumberland Ave Housing\CAD\STRUCT\S01\3028A1.