

SimplexGrinnell
20 Thomas Dr.
Westbrook, ME 04092
Tel: 207-842-6440

CERTIFICATE OF INSTALLATION

Customer	Avesta Housing, 409 Cumberland
Address	409 Cumberland Ave. Portland, ME 04101
Hazard location	4' island type kitchen hoods, first floor
System location	Ansul control box and cylinder located on side of hood above the ceiling.
System Type	Ansul model R102, UL300 wet chemical per NFPA 17A & 96 and design manual UL EX 3470
System size	3-gallon (1 cylinder)
Remarks	A. System includes: (1) 3-gallon cylinders, (4) discharge nozzles, (1) fusible link detectors, (1) pull station (1) 3/4" electrical gas shutoff valve and micro-switches for gas valve/relay shutdowns and fire alarm connection. B. System nozzles include: (1) 1N nozzle for v-plenum, (1) 1W nozzle for exhaust duct and (2) 245 nozzles for 5-burner range.
Installation date	Installed 1/14/15 but wiring not complete and system not tested.
Next inspection due	Semi-annual : July 2015, January 2016 etc.
Installed by	Installation by Bryan Ross