

2009 NFPA: CODE DATA		CH. 38 BUSINESS EXISTING BUILDING
TYPE OF CONSTRUCTION	TYPE II O.G.O. (EXISTING)	
OCCUPANT LOAD - RENOVATED AREA	803S F. /100 = 9 SF/PP	
EXTERIOR BEARING WALLS	0 HOUR	
EXTERIOR NONBEARING WALLS	0 HOUR	
INTERIOR BEARING WALLS	0 HOUR	
COLUMNS	0 HOUR	
BEAMS GIRDERS, TRUSSES	0 HOUR	
FLOOR CONSTRUCTION	0 HOUR	
FLOOR SEPARATION AT ASSEMBLY USE GROUP	1 HOUR	
MECHANICAL / ELECTRICAL ROOMS	1 HOUR	
TENANT SEPARATION	0 HOUR	
SYSTEMS ENGINEERING - PARTIAL FIRST FLOOR	803 S.F.	
TOTAL FLOOR AREA - FIRST FLOOR	27,000 S.F. +/- TOTAL FLOOR	
BUILDING HEIGHT	70' +/-, 6 STORIES	
FIRE SUPPRESSION	YES	
HAZARD	1 HOUR	
FIRE EXTINGUISHERS	PER NFPA 2009	
COMMON PATH OF TRAVEL LIMIT	75'	
DEAD-END LIMIT	50'	
TRAVEL DISTANCE LIMIT	200'	
EXITS	36"	
CORRIDOR WIDTH	1 HOUR	
STAIR ENCLOSURES	1 HOUR	
SHAFTS	1 HOUR	
EXIT ACCESS CORRIDORS	0 HOUR	
FLAME SPREAD RATINGS:		
INTERIOR FINISH REQUIREMENTS (SPRINKLERED BLDG)	CLASS A, B OR C	
WALLS AND CEILINGS	CLASS A OR CLASS B	
EXIT ACCESS CORRIDORS	CLASS A OR CLASS B	
INTERIOR FLOOR FINISH REQUIREMENTS	CLASS I OR CLASS II REDUCTION PERMITTED OF ONE CLASS IN SPRINKLERED BUILDING	
EXITS		
CORRIDORS		
GENERAL NOTES	1. ALL PENETRATIONS OF SMOKE BARRIERS, PARTITIONS, FIRE RATED WALLS AND FLOORS SHALL BE SEALED WITH PROPER APPROVED MATERIALS	

2009 IBC: CODE DATA		SECTION 403 HIGH RISE BUILDINGS
OCCUPANT LOAD	Business Occupancy (EXISTING BLDG) 803/100 = 9	
USE GROUP CLASSIFICATION	BUSINESS	
TYPE OF CONSTRUCTION	TYPE II B (EXISTING)	
ACTUAL FLOOR AREA	27,000 S.F. - RENOVATED AREA IS 803S F.	
TOTAL BUILDING AREA	150,000 SF +/-	
ACTUAL BUILDING HEIGHT	70' +/-	
EXIT ACCESS TRAVEL DISTANCE	200'-0"	
DEAD END CORRIDORS	20'-0" / 50'-0" W/ FIRE SUPPRESSION SYSTEM	
CORRIDOR WIDTH	36"	
STAIRWAY WIDTH	44"	
FIRE RATING:		
EXTERIOR BEARING WALLS	0 HOUR	
INTERIOR BEARING WALLS	0 HOUR	
NON-BEARING WALLS & PARTITIONS	0 HOUR	
FLOOR CONSTRUCTION	0 HOUR	
ROOF CONSTRUCTION	0 HOUR	
CORRIDORS	0 HOUR	
STAIR ENCLOSURES	1 HOUR	
SHAFTS	1 HOUR FOR <= 4 STORIES	
UNIT SEPARATION	1 HOUR	
MECHANICAL/ELECTRICAL ROOMS	1 HOUR	
LAUNDRY/STORAGE >100 SF	1 HOUR	
WASTE COLLECTION >100 SF	1 HOUR	
FLAME SPREAD RATINGS:		
INTERIOR WALL & CEILING FINISH REQUIREMENTS	A	
EXIT ENCLOSURES & EXIT PASSAGEWAYS	B	
CORRIDORS	C	
ROOMS OR ENCLOSED SPACES		
INTERIOR FLOOR FINISH REQUIREMENTS	CLASS II	
EXIT ENCLOSURES & EXIT PASSAGEWAYS	CLASS II	
CORRIDORS	CLASS II	
GENERAL NOTES	1. ALL PENETRATIONS OF SMOKE BARRIERS, PARTITIONS, FIRE RATED WALLS AND FLOORS SHALL BE SEALED WITH PROPER APPROVED MATERIALS 2. ALL WORK SHALL CONFORM TO LOCAL AND STATE CODES, ORDINANCES AND REQUIREMENTS, ACCESSIBILITY PER A.D.A.G.	