



GROSS S.F. - 14,697 S.F.

NFPA 101
 BUILDING OCCUPANCY-CHAPTER 39
 GROUND FLOOR AREA SEPARATED FROM SECOND FLOOR

OCCUPANT LOAD - 166 BASED ON SEATING

38.1.7

MEANS OF EGRESS PER CHAPTER 7
 CAPACITY OF MEANS OF EGRESS $166 \times 2 = 33.2"$
 MIN CORRIDOR WIDTH 44"

TABLE 7.3.3.1
 38.2.3.2

ARRANGEMENT OF MEANS OF EGRESS

EXITS @ LEAST $\frac{1}{2}$ DIAGONAL 7.5.1.3.2
 DEAD END CORRIDORS NOT TO EXCEED 20' W/OUT SPRINKLER 38.2.5.2.1
 COMMON PATH 75' W/OUT SPRINKLER 38.2.5.3
 TRAVEL DISTANCE 200' W/OUT SPRINKLER 38.2.6.2
 EMERGENCY LIGHTING REQUIRED 38.2.9
 INTERIOR FINISHES
 WALL & CEILING CLASS A OR B IN EXITS AND EXIT ACCESS CORRIDORS 38.3.3.2.1
 WALL & CEILING CLASS A, B OR C IN ALL OTHER AREAS 38.3.3.2.2
 PORTABLE FIRE EXTINGUISHERS ACCORDING TO 9.7.4.1 38.3.5

NOTES:

1. CONFIRM LOCATION OF PORTABLE FIRE EXTINGUISHERS W/ CITY FIRE
2. HARDWARE ON ALL EXIT DOORS TO BE EXIT DEVICE

Prepared For:

Consultant:

Architect: ARCHETYPE
 48 Union Wharf Portland, Maine 04101
 (207) 772-6022 Fax (207) 772-4056

Project: MECA STUDIOS
 380 CUMBERLAND AVE
 PORTLAND, ME

Revisions:

Date: 6-1-2016
 Scale: AS NOTED
 LIFE SAFETY PLAN

A1.02