

# Protection Professionals

325 US Route 1  
 Falmouth, ME 04105  
 Ph 207-775-5755  
 Fax 207-781-2064

# Device List

No. 5016

List Date
2/22/2013

Bill To Name / Address
Favreau Electric Attn: Mr Tobie A. Kay 37 Jordan Avenue Brunswick, ME 04011

Job Site
Eastland Park Hotel 157 High Street Portland, ME 04101

**CHANGING THIS DEVICE LIST DOES NOT ALTER THE ORIGINAL ESTIMATE**  
**Attach copy to Purchase Order for accounting**

Estimate No.

Item	Description	Qty To Order	Qty Ordered
500-636029	<p>This quote reflects the FA series of floor plans FA 1.01 to FA 1.12 dated 1-8-13 plus floor plans E3.05 to E3.12 dated 7-9-12 for the smoke guard locations only. We exclude all of the information and listed equipment on plans FA0.01 and FA0.02 dated 1-2-13 except for the legend and the reference to the phone jacks 6-E. All fire alarm system sequence of Operation has to meet the City of Portland requirements as well as the capabilities of the existing equipment. Any variations will require a revised quote. This quote will include additional devices as requested on the FA plans plus floor above and floor below activation of the voice evacuation panel. This quote does not include any smoke control system integration except for the elevator smoke guard door relays and the elevator dampers.</p> <p>The floor plan matrix is shown on floor plan FA0.02.</p> <p>The number of devices in each ADA or hearing impaired rooms. This quote is based upon the following rooms being hearing impaired: 233, 302, 310, 318, 328, 329, 330, 404, 410, 419, 428, 502, 518, 529, 510, 603, 610, 628, 710, 810, 910, 1003, 1028, 1010, 1429, and 1431 only.</p> <p>The current fire alarm system is a Class A system with all of the fire alarm panels in the electrical or linen closets on each floor. The cabling is run between the floors either in the electrical closets, in the service elevator area, or in one of the three stair towers.</p> <p>Annunciator will be located by the front desk. This is not shown on the floor plans.</p> <p>The parts below are the additional parts needed when the existing parts are reused.                      SE-R, Speaker only, wall mount, red, 4" deep box required, 25VDC or 70VDC, 1/8, 1/4, 1/2, 1, or 2 watts (for all of the additional rooms)</p>	100	

Ordered By: \_\_\_\_\_

Date: \_\_\_\_\_

Received By: \_\_\_\_\_

Date: \_\_\_\_\_

# Protection Professionals

325 US Route 1  
 Falmouth, ME 04105  
 Ph 207-775-5755  
 Fax 207-781-2064

# Device List

No. 5016

List Date
2/22/2013

Bill To Name / Address
Favreau Electric Attn: Mr Tobie A. Kay 37 Jordan Avenue Brunswick, ME 04011

Job Site
Eastland Park Hotel 157 High Street Portland, ME 04101

**CHANGING THIS DEVICE LIST DOES NOT ALTER THE ORIGINAL ESTIMATE**  
**Attach copy to Purchase Order for accounting**

Estimate No.

Item	Description	Qty To Order	Qty Ordered
500-636169	ZR-MC-R Strobe only, red, wall mount, 15cd, 30cd, 75cd, or 110cd (no additional strobes are required)	0	
500-636025	SE-MC-R, Speaker/strobe, wall mount, 4" deep box required, red, 25VDC or 70VDC, 1/8, 1/4, 1/2, 1, or 2 watts, 15cd, 30cd, 75cd, or 110cd	82	
500-636027	SE-HMC-R, Speaker/strobe, wall mount, red, 25 or 70 volts, 1/8, 1/4, 1/2, 1, or 2 watts, 135 cd or 185cd (for ADA bedrooms)	34	
500-033300FA	8704 Module for Contact Devices with Relay (for two new elevator and damper control)	9	
500-033300FA	8704 Module for Contact Devices with Relay (for smoke guard controls)	23	
500-034000FA	8701 Mini-Module for Contact Devices (room annunciation)	289	
AX-AL842ULADA	NAC power supply, 8 amps, Class A or B, 4 circuits, 2 amps per circuit (add one for each floor listed to provide floor above, floor below activation: 3rd, 5th, 6th, 8th, 10th, and the 12th)	6	
Bat 12-7	12V 7AH Batteries	12	
500-033300FA	8704 Module for Contact Devices with Relay (one per floor for floor above, floor below activation)	13	
Misc Non-Inventory ...	Upgrade software of current evacuation panel to provide floor above, floor below activation	1	
500-033360FA	8703 Dual Module for Contact Devices (additional sprinkler devices as per floor plans)	18	
500-033310FA	8727W LED Annunciator-Wall	29	
500-649308FA	SRU-2 Serial Relay Card	1	
500-649337FA	SRE-8 8 Relay Extender for MPC-6000 & MPC-7000	1	
500-648993FA	Complete Enclosure Package Red for MPC-7000	1	
500-649708FA	Duct detector assembly (reusing 4 assemblies from existing device list)		
500-033290FA	8743 AIR DUCT HOUSING WITH RELAY	10	
500-649711	8713 Photo/Thermal Detector (FireSmart)	10	
500-033370FA	ST-25 SAMPLING TUBE FOR DUCTS OVER 1' TO 3'	10	
	8702 Module for Contact Devices	10	

Ordered By: \_\_\_\_\_

Date: \_\_\_\_\_

Received By: \_\_\_\_\_

Date: \_\_\_\_\_

# Protection Professionals

325 US Route 1  
 Falmouth, ME 04105  
 Ph 207-775-5755  
 Fax 207-781-2064

# Device List

No. **5016**

List Date
2/22/2013

<b>Bill To Name / Address</b>	<b>Job Site</b>
Favreau Electric Attn: Mr Tobie A. Kay 37 Jordan Avenue Brunswick, ME 04011	Eastland Park Hotel 157 High Street Portland, ME 04101

<b>CHANGING THIS DEVICE LIST DOES NOT ALTER THE ORIGINAL ESTIMATE          Attach copy to Purchase Order for accounting</b>	<b>Estimate No.</b>

Item	Description	Qty To Order	Qty Ordered
500-696353FA	8730 Duct Detector Test Switch	10	
BK-CO1224	Carbon Monoxide Detector with alarm and trouble contacts, 20ma standby and 40ma in alarm, 12/24 VDC	1	
500-034000FA	8701 Mini-Module for Contact Devices	1	
GN-GN503F	This option is based upon a volume discount and the list of hearing impaired rooms as listed above only. 120 VAC Smoke/CO detector with relay, 9 volt battery; 918-0007-002	309	
GN-GXS120177WR	GENTEX 120VAC STROBE, RED (wall mounted) State of Maine Sales Tax	56	

Ordered By: \_\_\_\_\_

Date: \_\_\_\_\_

Received By: \_\_\_\_\_

Date: \_\_\_\_\_