

City of Portland, Maine – Building or Use Permit Application 389 Congress Street, 04101, Tel: (207) 874-8703, FAX: 874-8716

Location of Construction: 37 Kellogg St.		Owner: Bethany L. Lawrence		Phone:		Permit No: 000918	
Owner Address: 37 Kellogg St., Apt. #2, Portland		Lessee/Buyer's Name:		Phone: 771-0991		BusinessName:	
Contractor Name: Edward Morse		Address: 16 Welsh St, Peaks Island		Phone:		Permit Issued: AUG 22 2000	
Past Use: Multi Family		Proposed Use: Same		COST OF WORK: \$1,950.00		PERMIT FEE: \$36.00	
Proposed Project Description: <i>legal 3 family only</i> Replace existing footing & add deck to second floor		FIRE DEPT. <input checked="" type="checkbox"/> Approved <input type="checkbox"/> Denied		INSPECTION: Use Group: <i>A-2 Type 5B</i> <i>BOCA 99</i>		Zone: <i>A-C</i> CBL: 037-E-024	
		Signature: <i>[Signature]</i>		Signature: <i>[Signature]</i>		Zoning Approval: <i>3 family per municipality</i>	
		PEDESTRIAN ACTIVITIES DISTRICT (P.A.D.)		Action: <input type="checkbox"/> Approved <input type="checkbox"/> Approved with Conditions <input type="checkbox"/> Denied		Special Zone or Reviews: <input type="checkbox"/> Shoreland <input type="checkbox"/> Wetland <input type="checkbox"/> Flood Zone <i>with conditions</i> <input type="checkbox"/> Subdivision <i>8/15/00</i> <input type="checkbox"/> Site Plan maj <input type="checkbox"/> Immot <input type="checkbox"/> Imm <input type="checkbox"/>	
Signature: _____ Date: _____		Signature: _____ Date: _____		Signature: _____ Date: _____		Signature: _____ Date: _____	
Permit Taken By: Gayle		Date Applied For: August 11, 2000 GG					

1. This permit application does not preclude the Applicant(s) from meeting applicable State and Federal rules.
2. Building permits do not include plumbing, septic or electrical work.
3. Building permits are void if work is not started within six (6) months of the date of issuance. False information may invalidate a building permit and stop all work..

*** Call : Bethany L. Lawrence @ 771-0991

PERMIT ISSUED WITH REQUIREMENTS

CERTIFICATION

I hereby certify that I am the owner of record of the named property, or that the proposed work is authorized by the owner of record and that I have been authorized by the owner to make this application as his authorized agent and I agree to conform to all applicable laws of this jurisdiction. In addition, if a permit for work described in the application is issued, I certify that the code official's authorized representative shall have the authority to enter all areas covered by such permit at any reasonable hour to enforce the provisions of the code(s) applicable to such permit

August 11, 2000

SIGNATURE OF APPLICANT	ADDRESS:	DATE:	PHONE:
RESPONSIBLE PERSON IN CHARGE OF WORK, TITLE			PHONE:

White-Permit Desk Green-Assessor's Canary-D.P.W. Pink-Public File Ivory Card-Inspector

Zoning Appeal

Variance
 Miscellaneous
 Conditional Use
 Interpretation
 Approved
 Denied

Historic Preservation

Not in District or Landmark
 Does Not Require Review
 Requires Review

Action:

Approved
 Approved with Conditions
 Denied

Date: *[Signature]*

PERMIT ISSUED WITH REQUIREMENTS
CEO DISTRICT

THIS IS NOT A PERMIT/CONSTRUCTION CANNOT COMMENCE UNTIL THE PERMIT IS ISSUED

**Building or Use Permit Pre-Application
Attached Single Family Dwellings/Two-Family Dwelling
Multi-Family or Commercial Structures and Additions Thereto**

In the interest of processing your application in the quickest possible manner, please complete the Information below for a Building or Use Permit.

NOTE**If you or the property owner owes real estate or personal property taxes or user charges on ANY PROPERTY within the City, payment arrangements must be made before permits of any kind are accepted.

Location/Address of Construction (include Portion of Building): 37 Kellogg St., Portland, ME 04101		
Total Square Footage of Proposed Structure 6659 Ft.	Square Footage of Lot # 3200.	
Tax Assessor's Chart Block & Lot Number Plan BK4 37 DE Chart# Page 11 Block# D Lot# 35	Owner X Bethany L. Lawrence	Telephone#: (207) 771-0991
Owner's Address 37 Kellogg St. Apt # 2 Portland, ME 04101	#2 see/Buyer's Name (If Applicable)	Cost Of Work: \$ 1950.00 Fee \$ 36.
Proposed Project Description: (Please be as specific as possible) Replace existing footings + second floor deck and add a deck above the second floor deck. Current deck is at the rear of the building Addition of 11' x 6' deck to the rear of third floor apt.		
Contractor's Name, Address & Telephone Edward Morse 16 Welch St. Peaks Island, ME 04108 766-3029		Rec'd By <i>[Signature]</i> 8/10 11:50
Current Use: 3 Unit Apt Bldng	Proposed Use: 3 Unit Apt Building	

Separate permits are required for Internal & External Plumbing, HVAC and Electrical installation.

- All construction must be conducted in compliance with the 1996 B.O.C.A. Building Code as amended by Section 6-Art II.
- All plumbing must be conducted in compliance with the State of Maine Plumbing Code.
- All Electrical Installation must comply with the 1996 National Electrical Code as amended by Section 6-Art III.
- HVAC (Heating, Ventilation and Air Conditioning) installation must comply with the 1993 BOCA Mechanical Code.

You must include the following with you application:

- 1) A Copy of Your Deed or Purchase and Sale Agreement
- 2) A Copy of your Construction Contract, if available
- 3) A Plot Plan/Site Plan

** If available also submit plans on ADOBE or CAD format*

Minor or Major site plan review will be required for the above proposed projects. The attached checklist outlines the minimum standards for a site plan.

Building Plans

Unless exempted by State Law, construction documents must be designed by a registered design professional.

A complete set of construction drawings showing all of the following elements of construction:


- Cross Sections w/Framing details (including porches, decks w/ railings, and accessory structures)
- Floor Plans & Elevations
- Window and door schedules
- Foundation plans with required drainage and damp-proofing
- Electrical and plumbing layout. Mechanical drawings for any specialized equipment such as furnaces, chimneys, gas equipment, HVAC equipment (air handling) or other types of work that may require special review must be included.

Certification

I hereby certify that I am the Owner of record of the named property, or that the proposed work is authorized by the owner of record and that I have been authorized by the owner to make this application as his/her authorized agent. I agree to conform to all applicable laws of this jurisdiction. In addition, if a permit for work described in this application is issued, I certify that the Code Official's authorized representative shall have the authority to enter all areas covered by this permit at any reasonable hour to enforce the provisions of the codes applicable to this permit.

Signature of applicant: <i>[Signature]</i>	Date: 081000
--	--------------

Building Permit Fee: \$30.00 for the 1st \$1000.00 cost plus \$6.00 per \$1,000.00 construction cost thereafter.
Additional Site review and related fees are attached on a separate addendum



BUILDING PERMIT REPORT

DATE: 11 August 2008 ADDRESS: 37 Kellogg St. CBL: 037-E-024
REASON FOR PERMIT: Replacing Foundation & add deck to Second Floor
BUILDING OWNER: Bethany L. Lawrence
PERMIT APPLICANT: _____ CONTRACTOR Edward Morse
USE GROUP: A-2 CONSTRUCTION TYPE: 50 CONSTRUCTION COST: 1,950.00 PERMIT FEES: 96.00

The City's Adopted Building Code (The BOCA National Building code/1999 with City Amendments)
The City's Adopted Mechanical Code (The BOCA National Mechanical Code/1993)

CONDITION(S) OF APPROVAL

This permit is being issued with the understanding that the following conditions are met: #1, #2, #11, #29, #32, #31, #34, #36, #37, #38, #39, #40

- 1. This permit does not excuse the applicant from meeting applicable State and Federal rules and laws.
2. Before concrete for foundation is placed, approval from the Development Review Coordinator and Inspection Services must be obtained. (A 24 hour notice is required prior to inspection) "ALL LOT LINES SHALL BE CLEARLY MARKED BEFORE CALLING."
3. Foundation drain shall be placed around the perimeter of a foundation that consists of gravel or crushed stone containing not more than 10 percent material that passes through a No. 4 sieve. The drain shall extend a minimum of 12 inches beyond the outside edge of the footing. The thickness shall be such that the bottom of the drain is not higher than the bottom of the base under the floor, and that the top of the drain is not less than 6 inches above the top of the footing. The top of the drain shall be covered with an approved filter membrane material. Where a drain tile or perforated pipe is used, the invert of the pipe or tile shall not be higher than the floor elevation. The top of joints or top of perforations shall be protected with an approved filter membrane material. The pipe or tile shall be placed on not less than 2" of gravel or crushed stone, and shall be covered with not less than 6" of the same material. Section 1813.5.2
4. Foundations anchors shall be a minimum of 1/2" in diameter, 7" into the foundation wall, minimum of 12" from corners of foundation and a maximum 6' O.C. between bolts. Section 2305.17
5. Waterproofing and dampproofing shall be done in accordance with Section 1813.0 of the building code.
6. Precaution must be taken to protect concrete from freezing. Section 1908.0
7. It is strongly recommended that a registered land surveyor check all foundation forms before concrete is placed. This is done to verify that the proper setbacks are maintained.
8. Private garages located beneath habitable rooms in occupancies in Use Group R-1, R-2, R-3 or I-1 shall be separated from adjacent interior spaces by fire partitions and floor/ceiling assembly which are constructed with not less than 1-hour fire resisting rating. Private garages attached side-by-side to rooms in the above occupancies shall be completely separated from the interior spaces and the attic area by means of 1/2 inch gypsum board or the equivalent applied to the garage side. (Chapter 4, Section 407.0 of the BOCA/1999)
9. All chimneys and vents shall be installed and maintained as per Chapter 12 of the City's Mechanical Code. (The BOCA National Mechanical Code/1993). Chapter 12 & NFPA 211
10. Sound transmission control in residential building shall be done in accordance with Chapter 12, Section 1214.0 of the City's Building Code.
11. Guardrails & Handrails: A guardrail system is a system of building components located near the open sides of elevated walking surfaces for the purpose of minimizing the possibility of an accidental fall from the walking surface to the lower level. Minimum height all Use Groups 42", In occupancies in Use Group A,B,H-4, I-1, I-2, M and R and public garages and open parking structures, open guards shall have balusters or be of solid material such that a sphere with a diameter of 4" cannot pass through any opening. Guards shall not have an ornamental pattern that would provide a ladder effect. (Handrails shall be a minimum of 34" but not more than 38". Use Group R-3 shall not be less than 30", but not more than 38"). Handrail grip size shall have a circular cross section with an outside diameter of at least 1 1/4" and not greater than 2". (Sections 1021 & 1022.0). Handrails shall be on both sides of stairway. (Section 1014.7)
12. Headroom in habitable space is a minimum of 7'6". (Section 1204.0)
13. Stair construction in Use Group R-3 & R-4 is a minimum of 10" tread and 7 1/2" maximum rise. All other Use Group minimum 11" tread, 7" maximum rise. (Section 1014.0)
14. The minimum headroom in all parts of a stairway shall not be less than 80 inches. (6'8") 1014.4
15. Every sleeping room below the fourth story in buildings of Use Groups R and I-1 shall have at least one operable window or exterior door approved for emergency egress or rescue. The units must be operable from the inside without the use of special knowledge or separate tools. Where windows are provided as means of egress or rescue they shall have a sill height not more than 44 inches (1118mm) above the floor. All egress or rescue windows from sleeping rooms shall have a minimum net clear opening height dimension of 24 inches (610mm). The minimum net clear opening width dimension shall be 20 inches (508mm), and a minimum net clear opening of 5.7 sq. ft. (Section 1010.4)
16. Each apartment shall have access to two (2) separate, remote and approved means of egress. A single exit is acceptable when it exits directly from the apartment to the building exterior with no communications to other apartment units. (Section 1010.1)
17. All vertical openings shall be enclosed with construction having a fire rating of at least one (1) hour, including fire doors with self closer's. (Over 3 stories in height requirements for fire rating is two (2) hours. (Section 710.0)
18. The boiler shall be protected by enclosing with (1) hour fire rated construction including fire doors and ceiling, or by providing automatic extinguishment. (Table 302.1.1) w/s make protects

8/11/00
3 unit 3

19. All single and multiple station smoke detectors shall be of an approved type and shall be installed in accordance with the provisions of the City's Building Code Chapter 9, Section 920.3.2 (BOCA National Building Code/1999), and NFPA 101 Chapter 18 & 19. (Smoke detectors shall be installed and maintained at the following locations):

- In the immediate vicinity of bedrooms
- In all bedrooms
- In each story within a dwelling unit, including basements

20. A portable fire extinguisher shall be located as per NFPA #10. They shall bear the label of an approved agency and be of an approved type. (Section 921.0)

21. The Fire Alarm System shall maintained to NFPA #72 Standard.

22. The Sprinkler System shall installed and maintained to NFPA #13 Standard.

23. All exit signs, lights and means of egress lighting shall be done in accordance with Chapter 10 Section & Subsections 1023.0 & 1024.0 of the City's Building Code. (The BOCA National Building Code/1999)

24. Section 25 - 135 of the Municipal Code for the City of Portland states, "No person or utility shall be granted a permit to excavate or open any street or sidewalk from the time of November 15 of each year to April 15 of the following year".

25. The builder of a facility to which Section 4594-C of the Maine State Human Rights Act Title 5 MRSA refers, shall obtain a certification from a design professional that the plans commencing construction of the facility, the builder shall submit the certification the Division of Inspection Services.

26. Ventilation shall meet the requirements of Chapter 12 Sections 1210.0 of the City's Building Code. (Crawl spaces & attics).

27. All electrical, plumbing and HVAC permits must be obtained by a Master Licensed holders of their trade. No closing in of walls until all electrical (min. 72 hours notice) and plumbing inspections have been done.

28. All requirements must be met before a final Certificate of Occupancy is issued.

~~29.~~ All building elements shall meet the fastening schedule as per Table 2305.2 of the City's Building Code (The BOCA National Building Code/1999).

30. Ventilation of spaces within a building shall be done in accordance with the City's Mechanical code (The BOCA National Mechanical Code/1993). (Chapter M-16)

31. Please read and implement the attached Land Use Zoning report requirements. *6 or more 3 Dwelling units. This is Not an approval to increase the numbers*

~~32.~~ Boring, cutting and notching shall be done in accordance with Sections 2305.3, 2305.3.1, 2305.4.4 and 2305.5.1 of the City's Building Code. *of dwelling units*

33. Bridging shall comply with Section 2305.16.

~~34.~~ Glass and glazing shall meet the requirements of Chapter 24 of the building code. (Safety Glazing Section 2405.0)

35. All signage, shall be done in accordance with Section 3102.0 signs of the City's Building Code, (The BOCA National Building Code/1999).

~~36.~~ *The proposed foundation for the new decks shall be a minimum of 4" below grade on footing with Eastern between footing and foundation. Foundation and columns and columns and decking.*

~~37.~~ *Bracking shall be used on column to deck framing.*

~~38.~~ *The deck framing shall be lagged bolted to the main bldg.*

~~39.~~ *see attached requirements for guardrails*

~~40.~~ *There shall be NO interconnecting exterior stairway. None is shown on the plans and none shall be built.*

[Signature]
Samuel Hoffes, Building Inspector

[Signature]
Lt. McDougall, PFD

Marge Schmuckal, Zoning Administrator

PSH 11/25/99

****This Permit is herewith issued, on the basis of plans submitted and conditions placed the plans, any deviations shall require a separate approval.**

*****THIS PERMIT HAS BEEN ISSUED WITH THE UNDERSTANDING THAT ALL THE CONDITIONS OF THE APPROVAL SHALL BE COMPLETED. THEREFORE, BEFORE THE WORK IS COMPLETED A REVISED PLAN OR STATEMENT FROM THE PERMIT HOLDER SHALL BE SUBMITTED TO THIS OFFICE SHOWING OR EXPLAINING THAT THE CONDITIONS HAVE BEEN MET. IF THIS REQUIREMENT IS NOT RECEIVED YOUR CERTIFICATE OF OCCUPANCY SHALL BE WITHHELD.**

****** Certificate of Occupancy Fees: \$50.00 each**

******* ALL PLANS THAT REQUIRE A PROFESSIONAL DESIGN'S SEAL, (AS PER SECTION 114.0 OF THE BUILDING CODE) SHALL ALSO BE PRESENTED TO THIS DIVISION ON AUTO CAD LT. 2000 OR REQUIVALENT.**

WARRANTY DEED

Know All Men By These Presents That We, Alicia D. Harding and
Bradley E. Harding
of 37 Kellogg Street, Portland,
County of Cumberland and State of Maine,

for consideration paid, grant to Bethany L. Lawrence
of 23 City Point Road, Peaks Island,
County of Cumberland and State of Maine

with WARRANTY COVENANTS:

A certain lot or parcel of land together with any buildings thereon situated in
Portland County of Cumberland
and State of Maine, more particularly described in Exhibit A attached hereto and
incorporated herein by reference.

In Witness Whereof, we have hereunto set our hand(s) this 1st day of
June, 2000.

Wendy Swan
Witness

Alicia D. Harding
Alicia D. Harding
Bradley E. Harding
Bradley E. Harding

State of Maine
County of Cumberland ss.

On this 1st day of June, 2000, personally appeared before me the
above named Alicia D. Harding and Bradley E. Harding
and acknowledged the foregoing to be his/her/their free act and deed.

Wendy Swan
Notary Public, ~~Attorney at Law~~
10/13/04

Return to: Bethany L. Lawrence

Exhibit A - Deed

A certain lot or parcel of land, with any buildings thereon, situated in Portland, County of Cumberland, and State of Maine, being more particularly bounded and described as follows:

Beginning at the southerly corner of land conveyed by Amelia C. Percy and others to Abram H. Chapman by deed dated June 13, 1918 and recorded in Cumberland County Registry of Deeds in Book 1008, Page 452; thence southeasterly by said Kellogg Street 40 feet to land conveyed by Anna M. Deering, et als to Isaac Littlejohn by deed dated July 14, 1887, recorded in said Registry in Book 543, Page 24; thence from these two points extending back northeasterly from said Kellogg Street at right angles thereto a distance of 80 feet, keeping the width of 40 feet; being lot No. 35 in the block of lots marked D of Plan recorded in Plan Book 4, Page 17.

Subject to easements and restrictions of record, if any.

Meaning and intending to convey and hereby conveying the same premises described in a deed from James A. Wescott and Diana H. Wescott dated November 14, 1986 to Alicia D. Harding and Bradley E. Harding and recorded in the Cumberland County Registry of Deeds in Book 7486, Page 68.

all pressure treated lumber
11x6"

3RD Floor
Proposed

450
2x2
by rights

Ledger
lagged
to floor


2CD
Floor
(Existing)
2x6 + 2x4

Guardrails
see 1022.φ

1ST
Floor
Brace


Fasten to Table
2x6

Concrete footing



B-6

rear 20' req - 20' shown
Side 10' req - 11' & 18' shown
Front - NA



37 Kellogg St.

There is an existing deck 11' x 6' ft on the Second Floor in the rear of the building. I would like to replace it and add an additional deck above it for the third floor Apt. The deck will be same size 11' x 6'.

See attached Diagram of Deck + Material

37 KELLOGG ST.
OWNER OF RECORD: James A. & Diana H. Mescott
LOCUS: Portland, Maine

"THIS IS NOT A BOUNDARY SURVEY"

SCALE: 1" = 10'

[Handwritten Signature]

Carpentry Plus

**Edward Morse
16 Welch St.
Peaks Island, Maine
766-3029**

Residential work estimate

Customer - Beth Lawrence
Kellogg St. #37

Contracted work-

DECK

- ~~(1) Obtain all necessary building/demolition permits. (1d@\$200)~~
- (2) Demo and remove entire deck system.(1d@\$350)
- (3) Lay new footings for new deck.(1d@\$150)
- (4) Repair damage to existing roof structure.(1d@\$250) ✓
- (5) Design layout for new deck(PT construction)(included with installation of deck)
- (6) Lay in new frame for deck.(2d@\$400) ✓
- (7) Lay decking and install rail.(1d@\$400) ✓

(1950)