LIGHT FIXTURE SCHEDULE

A1 - 6' LONG TRACK LIGHT, 3 HEADS
A2 - 8' LONG TRACK LIGHT, 5 HEADS
A3 - 12' LONG TRACK LIGHT, 7 HEADS
A4 - 14' LONG TRACK LIGHT, 8 HEADS

B - RECESSED DOWNLIGHT 6" ROUND (INTERIOR)

C - 24" X 24" LAY-IN LED (ACT GRID CEILING)

D - DECORATIVE PENDANT

E - DECORATIVE WALL SCONCE

GENERAL CEILING NOTES

1. EXISTING GWB CEILING INSTALLED ON WOOD STRUCTURE ABOVE TO REMAIN.
2. ALL EXISTING ACT CEILINGS TO BE REMOVED.
3. INSTALL NEW 1-HOUR FIRE RATED CEILING CONTINUOUS THROUGHOUT TENANT SPACE. SEAL ALL PENETRATIONS WITH FIRESTOPPING.
4. MECHANICAL DIFFUSERS NOT SHOWN. GC COORDINATE WITH DESIGN - BUILD MECHANICAL CONTRACTOR
5. SPRINKLER SYSTEM NOT SHOWN. GC COORDINATE WITH SPRINKLER MANUFACTURE FOR NFPA 13 COMPLIANT SPRINKLER SYSTEM

ELECTRICAL/LIGHTING SYMBOL LEGEND

	4' SURFACE MOUNTED FLUORESCENT LIGHT FIXTURE		SURFACE MOUNTED LIGHT FIXTURE
	UNDER-CABINET LIGHT FIXTURE		RECESSED LIGHT FIXTURE
	PENDANT LIGHT FIXTURE		WALL MOUNTED LIGHT FIXTURE
	WALL MOUNTED STRIP LIGHT		EXHAUST FAN/LIGHT
	TRACK LIGHTING		HORN/STROBE NOTIFICATION DEVICE
SD	SMOKE DETECTOR		STROBE ONLY NOTIFICATION DEVICE
HD	HEAT DETECTOR		EMERGENCY LIGHT
FACP	FIRE ALARM CONTROL PANEL		2X2 LED TROFFER LIGHT FOR ACT INSTALLATION

1 LEVEL 1 - RCP
1/4" = 1'-0"

Reviewed for Code Compliance
Inspection Division
Portland, Maine
Date: 04/25/17

LICENSED ARCHITECT
CHRISTOPHER M. BRILEY
No. 2788
STATE OF MAINE

24 PREBLE STREET
1ST FLOOR RENOVATIONS
PORTLAND, MAINE 04101

BRIBURN architecture for life
28 Maple St. Suite 202, Portland, ME 04101
207-774-0402

CONSULTANTS:

REVISIONS:

No.	Name	Date

ISSUED:	12/29/16
PROJECT No:	1606
DRAWN BY:	RIP
CHECKED BY:	CMB

SHEET TITLE:
FIRST FLOOR RCP

A111