DOOR SCHEDULE								
MARK	TYPE	WIDTH	HEIGHT	HARDWARE	CLOSER	POSITIVE LATCH	RATING	COMMENTS
101	D3	6' - 0"	6' - 8"	H3	X	X		
105	D1	3' - 0"	7' - 0"	H2	X			
106	D4	6' - 9"	8' - 0"	H4				
107	D1	3' - 0"	7' - 0"	H1	X			
108	D1	3' - 0"	7' - 0"	H1	X			

HARDWARE SETS:

H1
- HINGES
- CLOSER
- PUSH PLATE
- PULL BAR
- MOP PLATE
- FLOOR STOP

H2
- HINGES
- CLOSER
- PUSH PLATE
- PULL BAR
- MOP PLATE

H3
- HINGES
- CLOSER
- MORTISE LOCKSET
- LEVER HANDLE
- PUSH BAR EXIT DEVICE
- WEATHER STRIPPING
- DOOR SWEEP
- FLOOR STOP

H4
- BOXRAIL OVERHEAD SLIDING DOOR TRACK (3)
- WALL STOP (3)
- FLUSH PULL (3)

GENERAL DOOR NOTES

1. ALL GLASS TO BE TEMPERED AND/OR RATED AS REQUIRED BY CODE
2. PROVIDE 3/4" UNDERCUT ON ALL BATHROOM DOORS, AND ANY OTHER DOORS TO SPACES WITH EXHAUST VENTILATION ONLY.
3. DOOR UNDERCUTS TO BE COORDINATED WITH FLOORING MATERIAL AND THRESHOLDS (IF ANY)
4. DOOR UNDERCUTS MUST NOT EXCEED MANUFACTURER'S RECOMMENDATIONS FOR FIRE-RATED DOORS
5. DOORS TAGGED 'EX' ON FLOOR PLANS ARE EXISTING TO REMAIN AND DO NOT REQUIRE ANY WORK UNDER THIS PHASE OF WORK

D1 — FLUSH SOLID CORE WOOD DOOR

D2 — FLUSH SOLID CORE WOOD DOOR 60-MIN FIRE RATED

D3 — PAINTED WOOD DOUBLE ENTRY DOOR

D4 — 3-PANEL WOOD SLIDING "BARN" DOOR

DOOR LEGEND
1/2" = 1'-0"

NOTE: PROVIDE MOISTURE RESISTANT GWB AND ACOUSTICAL BATT INSULATION AT ALL BATHROOM WALLS

WALL TYPES
1 1/2" = 1'-0"

FINISH SCHEDULE								
#	ROOM NAME	FLOOR	BASE	WALL FINISH				CEILING
				NORTH	EAST	SOUTH	WEST	
101	ENTRY	NEW PT	-	NEW WD	N/A	EX. WD	NEW / EX. WD	EX. GWB
102	CONSOLE GAMES	EX. WD	WD	EX. BRICK	EX. GWB	NEW / EX. GWB	NEW GWB	EX. GWB
103	MAIN LOUNGE	EX. WD	WD	EX. BRICK / NEW GWB	EX. GWB	NEW / EX. GWB	N/A	NEW / EX. GWB
104	BAR	NEW CSV	CSV	EX. BRICK	NEW GWB	N/A	NEW GWB	EX. GWB
105	KITCHEN	NEW CSV	CSV	FRP / STL	FRP	FRP	FRP	ACT2
106	PRIVATE/PUBLIC LOUNGE	EX. WD	WD	EX. BRICK	NEW GWB	NEW GWB	EX. BRICK	NEW GWB
107	MEN'S TOILET	NEW MCT	RB	NEW GWB	NEW GWB	NEW GWB	NEW GWB	NEW GWB
108	WOMEN'S TOILET	NEW MCT	RB	NEW GWB	NEW / EX. GWB	EX. BRICK	EX. BRICK	NEW GWB
109	SERVICE	EX. WD	WD	NEW GWB	N/A	NEW GWB	NEW GWB	ACT1
110	SKEE BALL & ARCADE	EX. WD	WD	N/A	NEW / EX. GWB	EX. BRICK	NEW / EX. GWB	NEW GWB

FINISH MATERIALS

FLOOR:
- CSV - COMMERCIAL SHEET VINYL
- MCT - MARMOLEUM COMPOSITION TILE
- PT - PORCELAIN TILE
- WD - EXISTING WOOD FLOORING

WALL BASE:
- RB - RUBBER
- VCB - VINYL COVE BASE
- WD - WOOD

WALL:
- FRP - FIBERGLASS REINFORCED PLASTIC PANEL
- GWB - GYPSUM WALL BOARD
- PLY - PAINTED PLYWOOD
- PWT - PORCELAIN WALL TILE
- STL - STAINLESS STEEL PANEL
- WD - WOOD PANELING

CEILING:
- ACT1 - 2X2 ACOUSTIC CEILING TILE
- ACT2 - 2X2 ACOUSTIC CEILING TILE (KITCHEN)
- GWB - GYPSUM WALL BOARD

FINISH NOTES

1. INTERIOR WALL AND CEILING FINISH MATERIALS SHALL BE CLASS A, CLASS B OR CLASS C IN ALL INTERIOR CORRIDORS AND LOBIES, AND SHALL BE CLASS A OR CLASS B IN ENCLOSED STAIRWAYS.
2. INTERIOR WALL AND CEILING FINISH MATERIALS SHALL BE CLASS A, CLASS B OR CLASS C IN ASSEMBLY SPACES.
3. INTERIOR FLOOR FINISH IN EXIT ENCLOSURES AND EXIT ACCESS CORRIDORS AND IN SPACES NOT SEPARATED FROM THEM BY WALLS COMPLYING WITH NFPA 101 12.3.6 SHALL BE NOT LESS THAN CLASS II.
4. ALL PENETRATIONS IN FIRE RATED ASSEMBLIES SHALL BE SEALED WITH FIRESTOPPING

Reviewed for Code Compliance
Inspections Division
Date: 04/25/17

LICENSED ARCHITECT
CHRISTOPHER M. BRILEY
No. 2788
STATE OF MAINE

24 PREBLE STREET
1ST FLOOR RENOVATIONS
PORTLAND, MAINE 04101

BRIBURN architecture for life
28 Maple St. Suite 202, Portland, ME 04101
207-774-0402

CONSULTANTS:

REVISIONS:

No.	Name	Date

ISSUED: 12/29/16
PROJECT No: 1606
DRAWN BY: RIP
CHECKED BY: CMB
SHEET TITLE: SCHEDULES

A601