

## CO-LOCATION INERGEN SYSTEM

### NOZZLE PERFORMANCE

START	END	PIPE SIZE	NOZZLE CODE	CU. FT. DISCHARGED
13	301	3/4 40 T	.4375	532.5
14	302	3/4 40 T	.4375	532.5

**TOTAL QUANTITY INERGEN DISCHARGED:** 1064  
**NINETY % DISCHARGED IN APPX.:** 45.42 SECONDS  
**NINETY % DISCHARGE PRESSURE (APPX):** 195 PSI

## ELECTRICAL ROOM INERGEN SYSTEM

### NOZZLE PERFORMANCE

START	END	PIPE SIZE	NOZZLE CODE	CU. FT. DISCHARGED
11	301	1 40 T	.5781	1287

**TOTAL QUANTITY INERGEN DISCHARGED:** 1287  
**NINETY % DISCHARGED IN APPX.:** 53.51 SECONDS  
**NINETY % DISCHARGE PRESSURE (APPX):** 195 PSI

