



DEMOLITION NOTES:  
 1. ALL SUSPENDED CEILINGS ARE TO BE REMOVED UNLESS OTHERWISE NOTED  
 2. ALL CASEWORK IS TO BE REMOVED UNLESS OTHERWISE NOTED  
 3. ALL CASEWORK IS TO BE REMOVED UNLESS OTHERWISE NOTED  
 4. ALL CASEWORK IS TO BE REMOVED UNLESS OTHERWISE NOTED  
 5. AT ELECTRICAL FIXTURE REMOVALS, TAKE WIRING BACK TO POINT OF ORIGIN, DO NOT LEAVE ABANDONED WIRING IN CONCEALED SPACES.  
 6. REMOVE ALL INTERIOR GLAZING SYSTEMS (SPECIES)

**DEMO KEY NOTES**

1	REMOVE WALL ASSOCIATED COMPONENTS AND TRIM
2	REMOVE DOOR, ASSEMBLY & TRIM
3	RELOCATE MECHANICAL
4	REMOVE BATHROOM FIXTURE
5	REMOVE EXISTING STOREFRONT
6	REMOVE EXISTING STAIR
7	REMOVE FALSE COLUMN
8	REMOVE EXISTING SAFE
9	REMOVE SPOUCH
10	REMOVE ROOF STRUCTURE

**WALL LEGEND**

(Solid line)	NEW STUD WALL
(Dashed line)	EXISTING MASONRY WALL
(Dotted line)	EXISTING WALL ELEMENTS TO BE REMOVED

1  
1/4"=1'-0"  
SIXTH FLOOR DEMOLITION PLAN