



GENERAL NOTES:

1. All ceilings: sound attenuation insulation, 1 hour rated 5/8" fire gwb, painted.
2. Stair 2 and 3 shall have pipe railings both sides, inside railings shall be continuous, treads shall be 11" clear, risers shall not exceed 7". SEE A-3.0
3. All doors in rated enclosures shall be rated according to required rating for the enclosure. They shall have steel frames, solid core birch, brushed stainless steel lever hardware, sets of three hinges, rated door closers.

TEEN SHELTER
38 PREBLE STREET

BASEMENT PLAN

Owner:
Preble Street
18 Portland Street
Portland, Maine

Architect:
James Sterling, AIA
Architect
142 High Street
Portland, Maine

PREBLE STREET

A-1.0

