



**REFLECTED CEILING PLAN NOTES**

1. RE ROOM FINISH SCHEDULE FOR CEILING HEIGHTS, TYPES, AND FINISHES, U.N.O.
2. FIRE SPRINKLERS SHALL BE LOCATED IN ALIGNMENT WITH OTHER CEILING ITEMS.
3. FIRE SPRINKLERS SHALL BE CENTERED IN CEILING TILE WHERE APPLICABLE.
4. FIRE SPRINKLERS SHALL BE PLACED TO COORDINATE WITH LIGHT FIXTURE POSITIONS INDICATED.
5. EXCEPT WHERE INDICATED, CENTER CEILING GRIDS IN ROOMS. USE HALF TILES OR GREATER @ PERIMETERS AS POSSIBLE.
6. RELOCATE EXISTING LIGHT FIXTURES TO LOCATIONS SHOWN. NEW LAYOUT TO BE AS SHOWN. RE: ELEC.
7. PATCH AND REPAIR DAMAGE TO EXISTING PLASTER BEAMS WHERE EXPOSED.

**RCP SYMBOL LEGEND**

- 2x4 LAY-IN LIGHT FIXTURE.
- FINELITE PENDANT LIGHTING
- RECESSED CAN LIGHT
- ⊠ CEILING MOUNTED EXIT LIGHT.
- ⊠ RETURN AIR GRILLE.
- ⊠ SUPPLY AIR GRILLE.
- ⊠ EXHAUST AIR GRILLE.
- ⊠ CEILING MOUNTED SPEAKER.
- ⊠ CEILING MOUNTED SMOKE DETECTOR.

1	ISSUED FOR PRICING	5-3-06
0	ISSUED FOR OWNER REVIEW	5-1-06
REV.	DESCRIPTION	DATE

**ISSUED FOR CONSTRUCTION**  
6-2-06

CURRENT ISSUE STATUS:


**SM RT** ARCHITECTURE ENGINEERING PLANNING  
 SMRT  
 144 Fore Street/P.O. Box 618  
 Portland, Maine 04104  
 tel. (207) 772-3846  
 fax. (207) 772-1070

**COMPASS CONSULTING**  
 477 CONGRESS STREET 7TH FLOOR  
 PORTLAND, MAINE

**SEVENTH FLOOR REFLECTED CEILING PLAN**

SHEET TITLE:	AS NOTED	DATE:	05-01-06
SCALE:	JLH	GRAPHIC SCALE:	0" = 1"
PROJECT MANAGER:	PJP	JOB CAP/DRAWN:	JLH
A/E OF RECORD:	JLH	SHEET No.:	AE102
SMRT CAD FILE:	AE102-06049	PROJECT No.:	06049