



22 Oakmont Drive
Old Orchard Beach, ME 04064-4121
Phone: (207) 934-8038
Fax: (207) 934-8039

FIELD NOTES

JOB NAME: **Diversified Communications**
JOB NO.: **13006**
DATE OF VISIT: **Jan. 23, 2013**
CLIENT: **Archetype, P.A.**
OBSERVERS: **David Tetreault, SDC**

I verified the construction of the 4th floor masonry wall at the proposed new ATM opening. The wall is a 12" thick brick wall and appeared to be in good condition. The wall supports wood floor framing. The bottom of the supported framing is approximately 5'-6" above the proposed opening.

The width of the proposed opening in the brick wall will be provided by the ATM supplier. I determined the required lintel size for the opening subsequent to my visit. I assumed a 48" wide opening in determining the lintel size. Please notify me if the rough opening is wider than 48". The required steel lintel is shown below:

