



1 Proposed First Floor Demolition Plan
Scale: 1/4" = 1'-0"

KEYED DEMOLITION NOTES

- 1 Remove existing partition. See Arch. drawings for extent of removal.
- 2 Remove existing raised floor and railings
- 3 Remove existing door(s), frame and hardware.
- 4 Remove existing conveyor belt
- 5 Remove existing window(s), frame and hardware.
- 6 Remove existing stairs and stair parts.
- 7 Remove existing tile flooring
- 8 Remove existing brick wall for new window. Shoring of existing brick by GC
- 9 Remove existing gyp bd soffit
- 10 Remove existing acoustical tile ceiling, grid, and light fixtures
- 11 Existing gyp. bd. soffit to remain
- 12 Remove portion of bar for new entrance to walk-in cooler
- 13 Remove walk-in cooler
- 14 Remove portion of floor for new shaft, refer to Arch. dwgs. for extent
- 15 Remove existing built-in casework
- 16 Remove existing floor finish

GENERAL DEMOLITION NOTES

1. The Contractor is responsible for scheduling, sequencing, and coordination of demolition work.
2. Contractor to protect floor finishes when noted to remain and shall be responsible for damages.
3. This drawing shows general items of selected demolition and is not intended to shall all cutting and patching of items required to accommodate new work.
4. All removed materials are to be disposed of properly.
5. Maintain structural and weather tight integrity throughout demolition.
6. Provide openings in existing walls, floors, and ceilings for new penetrations. Any structural members must be reviewed for new penetrations by a Structural Engineer.
7. Firestopping of penetrations through rated walls, floors and ceilings (if any) shall match partition assembly ratings. Firestopping of penetrations shall be the responsibility of the Contractor installing the work and demolition.
8. The Contractor, Mechanical, Electrical, Fire Projects, and Plumbing subcontractors shall be responsible for the coordination and removal of existing equipment to be reused and removed. The MEP and Fire Protection design is considered Design-build.
9. New roof penetrations shall be coordinated with the Contractor and shall remain weather tight.

DEMOLITION LEGEND

- Existing wall to remain
- Existing construction to be removed
- Line of floor to be removed for new stair and lift
- Area of existing flooring to be removed in preparation of new tile floor
- Concrete slab to be sawcut and removed, refer to notes on Detail 2/D.2