FINISH SCHEDULE

number	room name	finish pkg.	notes
		ili listi pkg.	Tioles
0	BASEMENT		
001	commercial unit		not subject to contract
002	elevator mech	Н	
003	mechanical	Н	
004	stair	G	
005	hall	Н	
006	residential storage	Н	
007	bathroom	D	
800	trash room	Н	smooth concrete finish, painted
009	stair	G	
010	residential storage	Н	
011	comm. stair		not subject to contract
012	comm. stair		not subject to contract
0101	comm. storage		not subject to contract
0102	comm. storage		not subject to contract
0105	comm. storage		not subject to contract
0304	residential storage	Н	
0305	residential storage	Н	
0306	residential storage	Н	
0308	residential storage	Н	
1	FIRST FLOOR		
101	commercial unit		not subject to contract
102	commercial unit		not subject to contract
103	commercial unit		not subject to contract
F-104	residential unit	E	
F-105	residential unit	E	
106	lobby	С	
107	entrance lobby	В	
108	hall	С	
109	stair	G	
110	storage		not subject to contract
111	storage		not subject to contract
	airlock	Α	-
112	an ook		
112	comm. access		not subject to contract

- 1. Exposed brick walls to be cleaned, painted or sealed
- 2. Exposed brick walls to be strapped, insulated and 1/2" GWB, painted
- 3. Exposed brick walls furred 6" metal studs@16 o.c., insulated
- 4. Exposed CMU walls, strap and 1/2" GWB painted
- 5. Walls to be 5/8" MR GWB

Existing ceiling exposed

- 7. Exposed brick walls furred with 1" Z strips @16 o.c., insulated, 1/2 GWB
- 8. Existing brick walls to be strapped, insulated, clear finished plywood
- 9. 5/8" type X GWB, painted
- 10. Existing columns on Congress Street side to be boxed in GWB and
- 11. Existing columns to be propped and painted

FINISH SCHEDULE PACKAGES

NOT SUBJECT TO CONTRACT (commercial tenant): Fit out package for Commercial Space TBD per Owner and Tenant

PACKAGE A (interior public - at entry):

3/8" riff sawn oak plywood, edge butted,

1/2" maple seam Ceiling wood terra turf Floor 8" maple

Note: 107 - 1 hour rated lowered ceiling at entry

PACKAGE B (interior public entry):

3/8" riff sawn oak plywood, edge butted, 1/2" maple seam

wood Floor/ stair slate tile/ stone? Stair riser maple Base 8" maple

PACKAGE C (interior public):

1/2" GWB, Painted Ceiling 1/2" GWB, Painted Floor Carpet Base 4" maple

PACKAGE D (interior public: utility & restrooms):

1/2" MR GWB, kemlite glasbord fs1 smooth Ceiling 1/2" GWB, Painted

tarkett sommer optima sheet vinyl flooring, joints heat welded, 8" base continuous with

NOTE: Coordinate floor drain locations with mechanical

PACKAGE E (residential loft < \$350,000, typ): Bedrooms, Closets, Half Baths: 1/2" GWB, painted

1/2" GWB, painted - note s2 Ceiling Floor hardwood Base 4" wood, painted

Kitchen, Living Room, Halls: 1/2" GWB, painted

1/2" GWB, painted - note s2 Ceiling Floor hardwood 8" wood, painted Base Countertop Laminate

Bathroom: Walls

1/2" MR GWB, painted 1/2" GWB, painted - note s2 Ceiling Floor ceramic tile Base ceramic tile Bath/basin

surround Laundry:

1/2" MR GWB, painted Walls Ceiling 1/2" GWB, painted - note s2 Floor altro, seamless Base altro, 6" flash cove

plastic

ceiling/floor s2

PACKAGE F (residential loft >\$350,000, typ): Bedrooms, Closets, Half Baths: same as package E

party walls s1

Kitchen, Living Room, Halls: same as package E except

Countertop concrete

Mezzanine:

Floor

Walls/Ceiling/ Base same as living room


ceramic tile

carpet Floor Bath: 1/2" MR GWB, painted Walls Ceiling 1/2" GWB, painted - note \$2


ceramic tile Base Bath/basin surround ceramic tile

Laundry: same as package E

ceiling/floor s2 party walls s1 NOTE:








PACKAGE G (stair):

F1/S1 painted Walls Ceiling 1/2" GWB, painted Floor forbo 'artoleum' Base 4" wood painted Treads rubber Nosings rubber

PACKAGE H (basement):

Walls F1/S1 painted 1/2" GWB, painted Ceiling Floor unfinished concrete screed 4" wood painted



date: 20 May, 2005

490 Congress Street Portland, Maine Kimball Block, LLC Portland, Maine

A-7.1