

SeaCoast Mechanical, LLC

Heating and Air Conditioning

P O Box 747

Westbrook ME. 04098

Ph# 207-939-8356

Proposal

Center Congress LLC, MRM Equity ME
482 Congress Street

Site location – 482 Congress, Suite 201

Date: 6/01/2017

Contact: Tim / Chuck

Description of work to be covered under this proposal. SeaCoast Mechanical shall provide labor and Material to recover the refrigerant for ten ton Trane unit, remove and dispose of. Install one Trane Ten ton replacement condenser only R-22. Reconnect into the existing suction and liquid lines, pressurize, leak check evacuate to 500 microns, charge with new R-22 refrigerant.

Excluded all related line voltage wiring.

Total cost labor and material for proposed work shall be \$9,250.00

Upon signing proposal 50 percent \$4,625.00 balance of \$4,625.00 due upon completion.