



PLUMBING CONNECTION SCHEDULE

- P-4 1-1/2" DIRECT WASTE HUB, STUB OUT WALL AT 8"-AFF, CONNECT AT ITEM 4, UNDERBAR, SINK, 3-COMPARTMENT.
- P-4b 1/2" 140°-HOT WATER, 60-GPH, STUB OUT WALL AT 12"-AFF AND CONNECT AT ITEM 4, UNDERBAR, SINK, 3-COMPARTMENT .
- P-4c 1/2" COLD WATER, STUB OUT WALL AT 12"-AFF AND CONNECT AT ITEM 4, UNDERBAR, SINK, 3-COMPARTMENT.
- P-5 FLOOR SINK, HALF-GRATE, 3/4" INDIRECT WASTE FROM ITEM 5, UNDERBAR, ICE BIN; ALSO SERVES ITEMS 6.
- P-6 1/2" 140°-HOT WATER, 60-GPH, STUB OUT WALL AT 12"-AFF AND CONNECT AT ITEM 6, UNDERBAR, BLENDER STATION .
- P-6b 1/2" COLD WATER, STUB OUT WALL AT 12"-AFF AND CONNECT AT ITEM 6, UNDERBAR, BLENDER STATION.
- P-6c 1/2" COLD WATER, STUB OUT WALL AT 12"-AFF AND CONNECT AT ITEM 6, UNDERBAR, BLENDER STATION.
- P-8 1/2" 140°-HOT WATER, 60-GPH, STUB OUT WALL AT 12"-AFF AND CONNECT AT ITEM 8, UNDERBAR, HAND SINK .
- P-8b 1/2" COLD WATER, STUB OUT WALL AT 12"-AFF AND CONNECT AT ITEM 8, UNDERBAR, HAND SINK.
- P-8c 1-1/2" DIRECT WASTE HUB, STUB OUT WALL AT 8"-AFF, CONNECT AT ITEM 8, UNDERBAR, HAND SINK.
- P-14 FLOOR SINK, HALF-GRATE, 3/4" INDIRECT WASTE FROM ITEM 14, ICE MACHINE.
- P-14b 3/8" COLD WATER, STUB OUT WALL AT 60"-AFF AND CONNECT AT ITEM 14, ICE MACHINE; THRU WATER FILTRATION SYSTEM.
- P-16 FLOOR SINK, HALF-GRATE, 2" INDIRECT WASTE FROM ITEM 16, SINK, 1-COMPARTMENT; ALSO SERVES ITEMS 19.
- P-16b 1/2" COLD WATER, STUB OUT WALL AT 18"-AFF AND CONNECT AT ITEM 16, SINK, 1-COMPARTMENT.
- P-16c 1/2" 140°-HOT WATER, 120-GPH, STUB OUT WALL AT 18"-AFF AND CONNECT AT ITEM 16, SINK, 1-COMPARTMENT .
- P-25 3/4" GAS SUPPLY, 110-MBTUH, STUB OUT WALL AT 36"-AFF AND CONNECT AT ITEM 25, FRYER.
- P-28 1/2" GAS SUPPLY, 40-MBTUH, STUB OUT WALL AT 36"-AFF AND CONNECT AT ITEM 28, GRIDDLE, COUNTERTOP, GAS.
- P-29 3/4" GAS SUPPLY, 80-MBTUH, STUB OUT WALL AT 36"-AFF AND CONNECT AT ITEM 29, CHARBROILER, COUNTER GAS.
- P-30 3/4" GAS SUPPLY, 206-MBTUH, STUB OUT WALL AT 36"-AFF AND CONNECT AT ITEM 30, RANGE, MEDIUM DUTY GAS.
- P-31 2" DIRECT WASTE HUB, STUB OUT WALL AT 8"-AFF, CONNECT AT ITEM 31, SINK, 3-COMPARTMENT.

- P-31b 1/2" COLD WATER, STUB OUT WALL AT 18"-AFF AND CONNECT AT ITEM 31, SINK, 3-COMPARTMENT.
- P-31c 1/2" 140°-HOT WATER, 120-GPH, STUB OUT WALL AT 18"-AFF AND CONNECT AT ITEM 31, SINK, 3-COMPARTMENT .
- P-32 1-1/2" DIRECT WASTE HUB, STUB OUT WALL AT 24"-AFF, CONNECT AT ITEM 32, HAND SINK.
- P-32b 1/2" 140°-HOT WATER, 120-GPH, STUB OUT WALL AT 18"-AFF AND CONNECT AT ITEM 32, HAND SINK .
- P-32c 1/2" COLD WATER, STUB OUT WALL AT 18"-AFF AND CONNECT AT ITEM 32, HAND SINK.
- P-36 2" DRAIN, STUB AT 5"-BELOW FINISH FLOOR, CONNECT AT ITEM 36, MOP SINK.
- P-36b 1/2" 140°-HOT WATER, 60-GPH, STUB OUT WALL AT 36"-AFF AND CONNECT AT ITEM 36, MOP SINK .
- P-36c 1/2" COLD WATER, STUB OUT WALL AT 36"-AFF AND CONNECT AT ITEM 36, MOP SINK.

LEGEND -- PLUMBING CONNECTIONS

- HW--HOT WATER, OR CW--COLD WATER
- S--STEAM SUPPLY, OR C--CONDENSATE RETURN
- GAS SUPPLY
- WASTE, DIRECT--CONNECTED UNLESS NOTED "OPEN HUB"
- ☐ FLOOR SINK WITH HALF GRATE UNLESS NOTED OTHERWISE
- ⊕ FLOOR DRAIN
- ⊕ FLOOR DRAIN W/ATTACHED FUNNEL
- FIELD CONNECTIONS

Foodservice Consultant:
TJM Consulting, Inc.
 273 Main Street, Suite 5
 Yarmouth, Maine 04096
 (207) 215-4736 tom@tjmconsulting.net

Owner:
Sol Food Group, LLC.
 P.O. Box 169
 Portland, Maine 04112

Project:
El Rayo's Restaurant
 26 Free Street
 Portland, Maine 04101

Drawing: **Foodservice Equipment
 Plumbing Rough-in Plan**
 Scale: 1/4"=1'-0"
 Date: December 14, 2015

Revisions:

SHEET:
FS-3