



**PLUMBING CONNECTION SCHEDULE**

- P-4 1-1/2" DIRECT WASTE HUB, STUB OUT WALL AT 8"-AFF. CONNECT AT ITEM 4, UNDERBAR, SINK, 3-COMPARTMENT.
- P-4b 1/2" 140°-HOT WATER, 60-GPH, STUB OUT WALL AT 12"-AFF AND CONNECT AT ITEM 4, UNDERBAR, SINK, 3-COMPARTMENT.
- P-4c 1/2" COLD WATER, STUB OUT WALL AT 12"-AFF AND CONNECT AT ITEM 4, UNDERBAR, SINK, 3-COMPARTMENT.
- P-5 FLOOR SINK, HALF-GRATE, 3/4" INDIRECT WASTE FROM ITEM 5, UNDERBAR, ICE BIN; ALSO SERVES ITEMS 6.
- P-6 1/2" 140°-HOT WATER, 60-GPH, STUB OUT WALL AT 12"-AFF AND CONNECT AT ITEM 6, UNDERBAR, BLENDER STATION.
- P-6b 1/2" COLD WATER, STUB OUT WALL AT 12"-AFF AND CONNECT AT ITEM 6, UNDERBAR, BLENDER STATION.
- P-6c 1/2" COLD WATER, STUB OUT WALL AT 12"-AFF AND CONNECT AT ITEM 6, UNDERBAR, BLENDER STATION.
- P-8 1/2" 140°-HOT WATER, 60-GPH, STUB OUT WALL AT 12"-AFF AND CONNECT AT ITEM 8, UNDERBAR, HAND SINK.
- P-8b 1/2" COLD WATER, STUB OUT WALL AT 12"-AFF AND CONNECT AT ITEM 8, UNDERBAR, HAND SINK.
- P-8c 1-1/2" DIRECT WASTE HUB, STUB OUT WALL AT 8"-AFF, CONNECT AT ITEM 8, UNDERBAR, HAND SINK.
- P-14 FLOOR SINK, HALF-GRATE, 3/4" INDIRECT WASTE FROM ITEM 14, ICE MACHINE.
- P-14b 3/8" COLD WATER, STUB OUT WALL AT 60"-AFF AND CONNECT AT ITEM 14, ICE MACHINE; THRU WATER FILTRATION SYSTEM.
- P-16 FLOOR SINK, HALF-GRATE, 2" INDIRECT WASTE FROM ITEM 16, SINK, 1-COMPARTMENT; ALSO SERVES ITEMS 19.
- P-16b 1/2" COLD WATER, STUB OUT WALL AT 18"-AFF AND CONNECT AT ITEM 16, SINK, 1-COMPARTMENT.
- P-16c 1/2" 140°-HOT WATER, 120-GPH, STUB OUT WALL AT 18"-AFF AND CONNECT AT ITEM 16, SINK, 1-COMPARTMENT.
- P-25 3/4" GAS SUPPLY, 110-MBTUH, STUB OUT WALL AT 36"-AFF AND CONNECT AT ITEM 25, FRYER.
- P-28 1/2" GAS SUPPLY, 40-MBTUH, STUB OUT WALL AT 36"-AFF AND CONNECT AT ITEM 28, GRIDDLE, COUNTERTOP, GAS.
- P-29 3/4" GAS SUPPLY, 80-MBTUH, STUB OUT WALL AT 36"-AFF AND CONNECT AT ITEM 29, CHARBROILER, COUNTER GAS.
- P-30 3/4" GAS SUPPLY, 206-MBTUH, STUB OUT WALL AT 36"-AFF AND CONNECT AT ITEM 30, RANGE, MEDIUM DUTY GAS.
- P-31 2" DIRECT WASTE HUB, STUB OUT WALL AT 8"-AFF, CONNECT AT ITEM 31, SINK, 3-COMPARTMENT.

- P-31b 1/2" COLD WATER, STUB OUT WALL AT 18"-AFF AND CONNECT AT ITEM 31, SINK, 3-COMPARTMENT.
- P-31c 1/2" 140°-HOT WATER, 120-GPH, STUB OUT WALL AT 18"-AFF AND CONNECT AT ITEM 31, SINK, 3-COMPARTMENT.
- P-32 1-1/2" DIRECT WASTE HUB, STUB OUT WALL AT 24"-AFF, CONNECT AT ITEM 32, HAND SINK.
- P-32b 1/2" 140°-HOT WATER, 120-GPH, STUB OUT WALL AT 18"-AFF AND CONNECT AT ITEM 32, HAND SINK.
- P-32c 1/2" COLD WATER, STUB OUT WALL AT 18"-AFF AND CONNECT AT ITEM 32, HAND SINK.
- P-36 2" DRAIN, STUB AT 5"-BELOW FINISH FLOOR, CONNECT AT ITEM 36, MOP SINK.
- P-36b 1/2" 140°-HOT WATER, 60-GPH, STUB OUT WALL AT 36"-AFF AND CONNECT AT ITEM 36, MOP SINK.
- P-36c 1/2" COLD WATER, STUB OUT WALL AT 36"-AFF AND CONNECT AT ITEM 36, MOP SINK.

**LEGEND - PLUMBING CONNECTIONS**

- HW-HOT WATER, OR CW-COLD WATER
- S-STEAM SUPPLY, OR C-CONDENSATE RETURN
- GAS SUPPLY
- WASTE, DIRECT-CONNECTED UNLESS NOTED "OPEN HUB"
- FLOOR SINK WITH HALF GRATE UNLESS NOTED OTHERWISE
- ⊕ FLOOR DRAIN
- ⊕ FLOOR DRAIN W/ATTACHED FUNNEL
- FIELD CONNECTIONS

Foodservice Consultant:  
**TJM Consulting, Inc.**  
 273 Main Street, Suite 5  
 Yarmouth, Maine 04096  
 (207) 215-4735 tjm@tjmconsulting.net

Owner:  
**Sol Food Group, LLC.**  
 P.O. Box 169  
 Portland, Maine 04112

Project:  
**El Rayo's Restaurant**  
 26 Free Street  
 Portland, Maine 04101

Drawing: **Foodservice Equipment  
 Plumbing Rough-in Plan**  
 Scale: 1/4"=1'-0"  
 Date: December 14, 2015

SHEET:  
**FS-3**