

- CONNECTIVITY POINT SCOPE OF WORK**
- All low voltage wiring, testing and termination.
 - Coordination during demo phase to re-use existing data home runs where possible.
 - Disconnect and re-work cable T.V. servicing board room. Cable box to be located in new credenza.
 - Temp remove and store boardroom touch screen panel for T.V. Re-install and re-program.
- JOHN WALKER ROOM**
- Provide new conference phone system.
 - Install mount and T.V. on wall at 54". T.V. relocated from the board room.
- RESOURCE ROOM**
- Install convenience data jacks (1 port) at 18" AFF - 2 location north wall (plan view)
 - Install convenience data jack (1 port) at 18" AFF - 1 location SW corner (can be used for printer if need be)
 - Install bloomberg/computer data (2 port) at 18" AFF - 1 location SE corner below work station
 - Install data jacks (1 port) for each of the 2 bloomberg monitors at 54" AFF side by side
 - Provide any Coax or other TV signal wiring and termination as needed.
 - Furnish and install the digital "Smart" projector above white board - North Wall
- RESOURCE OFFICE/CUBES**
- Install convenience data jack (1 port) at 18" AFF below desk. Next to power quad. Home run.
- BOARD ROOM**
- Install convenience data jacks (2 port) on face of column within credenza.
 - Temp remove touch screen panel. Reinstall and re-program.
 - Install new larger (70" SMART) T.V. with RS-232 function in this room. Power and data already exist.
- SERVER ROOM**
- All work in server room will be completed by Connectivity Point.

