**Project Title**

VERRILL DANA
INTERIOR
RENOVATIONS

ONE PORTLAND SQUARE,
PORTLAND, MAINE, 04101

**AEI** PROJECT NO.    16008

Verrill Dana LLP
Attorneys at Law

TRUE NORTH

PROJECT NORTH

CATHERINE A
FAUCHER
No. 7375

**Project Status**

ISSUED FOR
CONSTRUCTION

SEPTEMBER 21, 2016

**Drawing Title**

FLOOR 10
LIGHTING PLAN

Scale:    As indicated

Drawing Number

EL-10.4

| Mark | Date | Description |
|------|------|-------------|

**C9    KEYNOTES**

1. LIGHTING CONTROL SHALL BE MANUAL ON/MANUAL OFF VIA WALL SWITCHES.
2. LIGHTING CONTROL SHALL BE MANUAL ON/AUTO OFF WALL SENSOR SWITCH - DETAIL A1/EL-50.1
3. - NOT USED -
4. LIGHTING CONTROL SHALL BE AUTO ON/AUTO OFF WALL SENSOR SWITCH WIRED FOR 3-WAY OPERATION - SEE DETAIL D1/EL-50.1
5. LIGHTING CONTROL SHALL BE AUTO ON/AUTO OFF VIA CEILING OCCUPANCY SENSOR(S) - SEE DETAIL F1/EL-50.1
6. LIGHTING CONTROL SHALL BE MANUAL ON/AUTO OFF VIA CEILING SENSOR(S) - DETAIL A3/EL-50.1
7. LIGHTING CONTROL SHALL BE WALL MOUNTED OCCUPANCY SENSOR DIMMER SWITCH, MANUAL ON, AUTOMATIC OFF (NO DETAIL)
8. LIGHTING CONTROL SHALL BE 0-10V DIMMING WITH AUTO OFF VIA CEILING SENSOR(S) - DETAIL C3/EL-50.1
9. LIGHTING CONTROL SHALL BE AUTOMATIC-ON/AUTOMATIC-OFF VIA CEILING MOUNTED OCCUPANCY SENSORS WITH OFF OVERRIDE AND MANUAL DIMMING CONNECTED TO THE LOAD SIDE OF THE SENSOR RELAY - DETAIL D3/EL-50.1
10. LIGHTING CONTROL SHALL BE DUAL CIRCUIT SWITCHING WITH 2-BUTTON OCCUPANCY SENSOR - DETAIL F3/EL-50.1
11. LIGHTING CONTROL SHALL BE MANUAL ON/AUTO OFF WITH AUTOMATIC DAYLIGHT CONTROL - DETAIL A6/EL-50.1
12. LIGHTING CONTROL SHALL BE SWITCHING OF MULTIPLE GROUPS WITH AUTO OFF VIA CEILING SENSOR(S) - SEE DETAIL C6/EL-50.1

1 - RELOCATE EXISTING LUMINAIRES IN THIS ROOM TO NEW CEILING AS INDICATED.

| A1 | FLOOR 10 LIGHTING PLAN | | A9 | LIGHTING CONTROL NOTES |
|----|------------------------|--|----|------------------------|
| 1/8" = 1'-0" | | | | |