


REFLECTED CEILING PLAN GENERAL NOTES

- CONTRACTOR TO PROVIDE ANY MISSING ESCUTCHEONS AT SPRINKLER HEADS ALL LIGHT FIXTURES AND HVAC REGISTERS SHALL BE LOCATED ON CEILING GRID U.N.O. ALL CEILING FIXTURES INCLUDING ALL
- DOWNLIGHTS & SPRINKLER HEADS SHALL BE CENTERED ON PANEL OR TILE, TYP U.N.O. NOTIFY ARCHITECT OF ANY CONFLICTS WITH THE SUSPENDED GRID 3. SYSTEM, HVAC, OR SPRINKLER FIXTURES PRIOR TO INSTALLATION.
- ALL FIXTURE RELOCATION IS SUBJECT TO ARCHITECT'S APPROVAL. EMERGENCY LIGHTING SHALL BE PROVIDED PER CODE 4. REQUIREMENTS. ALL CEILING FIXTURES AND WIRING FOR LIGHT FIXTURES, EXIT 5.
- SIGNS, OR OTHER ELECTRICAL DEVICES SHALL BE U.L. APPROVED. THERMALLY PROTECTED, AND SHALL BE INSTALLED IN CONDUIT OR OTHER WIRING METHOD APPROVED BY THE BUILDING DEPARTMENT. ALL SWITCHES, THERMOSTATS, AND OTHER WALL-MOUNTED 6. CONTROL DEVICES SHALL BE MOUNTED AT 48" ABOVE UNFINISHED
- FLOOR TO TOP OF BOX U.O.N. SUBMITTALS AND SHOP DRAWINGS FOR ALL LIGHT FIXTURES ARE 7 REQUIRED FOR APPROVAL PRIOR TO PURCHASE OF
- MATERIALS/FIXTURES. THIS DRAWING IS FOR LAYOUT PURPOSES ONLY. ENGINEERING OF 8. SWITCHING AND CIRCUITRY SHALL BE PROVIDED BY THE ELECTRICAL CONTRACTOR IN ACCORDANCE WITH APPLICABLE
- BUILDING CODES AND REGULATIONS FOR BUILDING LIFE SAFETY, EMERGENCY, EGRESS AND NIGHT LIGHTS. SEE ELECTRICAL NOTES. HORNS AND STROBES SHALL BE PROVIDED THROUGHOUT AREA OF WORK AS REQUIRED TO MEET CODE REQUIREMENTS. LAYOUT MUST BE SUBMITTED TO ARCHITECT FOR APPROVAL PRIOR TO
- INSTALLATION. LIGHT FIXTURES AND SWITCHING SHALL CONFORM TO CODE 10. REQUIREMENTS. PROVIDE A CONSISTENT LAMP COLOR TEMPERATURE THROUGHOUT THE SPACE. MATCH EXISTING BUILDING STANDARD LAMP U.O.N.
- REWORK EXISTING LIGHT FIXTURE SWITCH LOCATIONS, HVAC 11. DIFFUSER LOCATIONS, FIRE SPRINKLER LAYOUT AND THERMOSTAT LOCATIONS AS REQUIRED FOR NEW LAYOUT. PATCH AND REPAIR ALL AREAS AFFECTED BY CONSTRUCTION. 12.
- ALL NEW GWB CEILINGS & SOFFITS SHALL BE SMOOTH FINISH, 13. MATCH LEVEL OF EXISTING. EXISTING SOFFITS TO REMAIN SHALL BE FINISHES TO SMOOTH LEVEL 4 FINISH AS WELL.
- EXIT SIGNS ARE NORMALLY ILLUMINATED AT ALL TIMES AND 14. PROVIDED WITH AN EMERGENCY ELECTRICAL SYSTEM FROM STORAGE BATTERIES, UNIT EQUIPMENT, OR AN ON-SITE GENERATOR SET TO INSURE CONTINUED ILLUMINATION FOR AT LEAST 90 MINUTES IN CASE OF PRIMARY POWER LOSS.
- PROVIDE CEILING ACCESS PANELS AS REQUIRED FOR CODE 15. COMPLIANCY AND MAINTENANCE OF ALL SYSTEMS ABOVE CEILING. CONTRACTOR TO ATTEMPT TO PROVIDE MULTIPLE POINTS OF ACCESS THROUGH ONE PANEL WHEN LAYING OUT UTILITIES ABOVE CEILING. PRIOR TO INSTALLATION, CONTRACTOR TO REVIEW IN FIELD WITH ARCHITECT AND OWNER THE LOCATIONS OF ALL PANELS. CEILING ACCESS PANELS TO BE PAINTED TO MATCH CEILING FINISH.
- 16. OPEN TO STRUCTURE CEILING SHALL BE CLEANED OF DEBRIS. CAP ALL UNUSED CONDUIT, WIRE, PIPE, & DUCT AND PREP TO RECEIVE NEW PAINT
- CONTRACTOR TO PROVIDE ANY MISSING ESCUTCHEONS AT 17. SPRINKLER HEADS.



A70.

CANAL

Architecture / Planning / Interior Design

207 553 2115

One Canal Plaza, Suite 888

NO NEW SCOPE IN THIS WING OTHER THAN THE ELIMINATION OF DOORS AT STAIR 1/EGRESS CORRIDOR, AND NEW CEILINGS AND HVAC AT THE INTERIOR - SEE RCP & MECH DWGS. NEW SOFFIT IN FINAL PHASE OF WORK

(6A)

(6B)

ACT.1 CEILING TYPE TAG & HEIGHT A.F.F. GWB CEILING ON METAL STUD FRAMING ACOUSTICAL TILE CEILING SPRINKLER HEAD • sd SMOKE/HEAT DETECTOR ۲ EXIT SIGN **RECESSED CAN FIXTURE - ROUND** Ø **RECESSED CAN FIXTURE - SQUARE** Ø 2' x 2' FLUSH MOUNT FIXTURE 2' x 4' FLUSH MOUNT FIXTURE ۲ ROUND PENDANT FIXTURE • • LINEAR PENDANT FIXTURE \square SUPPLY DIFFUSER **RETURN GRILL** NOTE: LIGHTING, MECHANICAL, & FIRE PROTECTION SYMBOLS ON ARCHITECTURAL DRAWINGS PROVIDED FOR LAYOUT AND COORDINATION PUIRPOSES ONLY. SEE ENGINEERING DRAWINGS, SCHEDULES, AND

NOTE: REUSE EXISTING GRID AT ALL PERIMETER OFFICES. EXISTING GWB CEILINGS AND SOFFITS TO REMAIN SHOWN HALFTONE. EXISTING BARREL VAULT CEILINGS IN CORRIDORS TO REMAIN.