



RFP LEGEND

	2'x2' EXISTING CEILING PANEL ACP-X		HMC SUPPLY DIFFUSER		2' x 2' EMERGENCY LIGHTING CIRCUIT		MS WET SPRINKLER PIPING
	NEW 2' x 2' ACOUSTICAL CEILING PANEL ACP-1		EXISTING HMC SUPPLY DIFFUSER		RECESSED COMPACT FLUORESCENT DOWNLIGHT WIRED TO NIGHT OR EMERGENCY LIGHTING CIRCUIT		MS EXISTING WET SPRINKLER PIPING
	2'x2' NEW ACOUSTICAL CEILING PANEL ACP-2		HMC EXHAUST OR RETURN AIR REGISTER		RECESSED FLUORESCENT DOWNLIGHT		MS CONNECT TO EXISTING
	NEW OPSIUM SOFFIT OPB-1		EXISTING HMC EXHAUST OR RETURN AIR REGISTER		2' x 2' RECESSED FLUORESCENT LIGHT FIXTURE		MS NEW UPRIGHT SPRINKLER HEAD (TYPE TO MATCH BUILDING STANDARDS U.O.N. ON DRAWINGS)
	EXISTING OPSIUM SOFFIT OPB-X		2' x 2' RECESSED WALKWASHING DOWNLIGHT		RECESSED WALKWASHING DOWNLIGHT		MS EXISTING SPRINKLER HEAD TO BE REMOVED AND FLAG PIPING ABOVE CEILING
	CEILING HEIGHT		6" RECESSED FLUORESCENT DOWNLIGHT		4" CHANNEL REFLECTOR WALL WASHER		MS EXISTING SPRINKLER HEAD TO REMAIN
			4" CHANNEL REFLECTOR WALL WASHER				MS EXISTING SPRINKLER HEAD TO BE RELOCATED

- RFP GENERAL NOTES**
- REFER TO ELECTRICAL DRAWINGS FOR LIGHTING SCHEDULE.
 - ALL CEILINGS TO BE CENTERED IN ROOM, U.O.N.
 - ALL NEW CEILINGS TO BE 9'-0" U.O.N.
 - THE FIRE PROTECTION CONTRACTOR SHALL REMOVE NEW SPRINKLER HEADS AND PIPING AS REQUIRED TO SUPPORT NEW ARCHITECTURAL LAYOUT. SPACING TO COMPLY WITH REQUIREMENTS OF NFPA 13. EXTEND NEW PIPING FROM EXISTING SPRINKLER BRANCH PIPING AS DEPICTED IN DETAIL 1 ON THIS SHEET.
 - THE FIRE PROTECTION CONTRACTOR SHALL BE RESPONSIBLE FOR ENGINEERING, DESIGN AND HYDRAULIC CALCULATIONS OF THE SPRINKLER SYSTEM TO COMPLY WITH THE REQUIREMENTS OF NFPA 13. DESIGN AND HYDRAULIC CALCULATIONS SHALL BE PROVIDED TO THE ARCHITECT AND SHALL BE REVIEWED AND APPROVED BY THE LOCAL FIRE DEPARTMENT. PERFORM THE APPROPRIATE TEST AS REQUIRED BY THE LOCAL FIRE DEPARTMENT.
 - SPRINKLER SYSTEM PLANS MUST BE REVIEWED AND APPROVED BY THE LOCAL FIRE DEPARTMENT PRIOR TO SPRINKLER SYSTEM MODIFICATIONS OR ALTERATION.
 - REMOVE AND REPLACE ALL CEILING TILES WHERE DAMAGED.
 - REMOVE AND REPLACE ALL CEILING TILES WHERE DAMAGED.
 - REMOVE AND REPLACE ALL CEILING TILES WHERE DAMAGED.
 - REMOVE AND REPLACE ALL CEILING TILES WHERE DAMAGED.