


- Notes:**
1. Building and this rental space are fully sprinklered, with fire alarm pull station adjacent to front entrance door and rear exit door.
 2. All interior walls are existing steel stud construction with 1/2" gypsum board finish.
 3. Floors are existing concrete slab except for an existing 4 1/2" high raised wood deck extending approximately 3' 6" in from front wall.
 4. Ceiling is existing 2' x 2' acoustic tile w/ 2' x 4' fluorescent light fixtures.
 5. Except for the front 'Sales' area, existing concrete floor to be leveled and painted with non-slip gloss industrial coating.
 6. Ceiling above 'Sales' area to be 1x3 Fir slats on 1x wood strapping, suspended from concrete deck above.

New wood/laminate floor this area on 1/2" underlayment plywood on new 2x wood sleepers @ 16" oc, adhered to to concrete slab.



R. Dean Bingham / Architect
 55 Roberts Street
 Portland, ME 04102
 207-774-7779

Dean'sweets
 475 Fore Street
 Portland, ME 04101

Scale: 1/4"
 6/25/14

Floor Plan

A2