



**1012 sqft = Total Floor Area**

Hall and Toilet 105 sqft = unoccupied  
 Seating 84 sqft / 7 = 12 occupants  
 Unconcentrated Assembly 250 sqft / 15 = 17 occupants  
 Business 146 sqft / 100 = 2 occupants  
 Kitchen 433 sqft / 200 = 3 occupants  
**Total Occupant Load = 34**

**Love Kuplicakes**  
**469 Fore Street**  
**Owner:**  
**Amy Alward**  
**207-767-3334**

**Ref: BP# 2016-00871**

**Note, seating:**  
 12 seats total x .05 ADA percentage = .6  
 therefore 1 seat required for ADA compliance