

CPT1	CARPET	MILLIKEN- COLOR FIELD PATINA
CPT2	CARPET	MILLIKEN- COLOR FIELD PATINA
CPT3	CARPET	MILLIKEN- COLOR FIELD PATINA
VCT1	VINYL COMP. TILE	MANNINGTON BRUSH WORKS
VB1	VINYL BASE	JOHNSONITE 4" STRAIGHT VINYL BASE COLOR
VB2	VINYL BASE	JOHNSONITE 4" COVE VINYL BASE COLOR
T1	PORCELAIN TILE	STONE SOURCE - EVO-Q - 3"X24" - HERRINGBONE INSTALLATION
GT1	GROUT	HYDROMENT OR EQUAL - 1/8" GROUT LINE
D1	MEMBRANE	SCHLUTER DITRA- UNCOUPLING MEMBRANE UNDER PORCELAIN TILE
TS1	TRANSITION	SCHLUTER "SCHEME" TILE TO CPT TRANSITIONS; STAINLESS
TS2	TRANSITION	VINYL TRANS. STRIP JOHNSONITE CARPET TO VGT TRANSITIONS
WT1	WALL TILE	TBD
WD1	WOOD WALL	TERRA MAI MODERN CLASSICS WALNUT ENGINEERED F/P- OIL 9/16"X5" WIDE 1'X7' RANDOM LENGTHS
LVT	LUX VINYL TILE	MOHAWK HOT HEAVY GROWN UP C0075
LVT	LUX VINYL TILE	MOHAWK HOT HEAVY GROWN UP C0075

PT1	PAINT	BENJAMIN MOORE- SEE NOTES FOR PAINT APPLICATION
PT2	PAINT	BENJAMIN MOORE- SEE NOTES FOR PAINT APPLICATION
PT3	PAINT	BENJAMIN MOORE- SEE NOTES FOR PAINT APPLICATION
PT4	PAINT	BENJAMIN MOORE- SEE NOTES FOR PAINT APPLICATION
PT5	PAINT	BENJAMIN MOORE- SEE NOTES FOR PAINT APPLICATION

SCHEME 1 - Reception 100.	
FLOOR	T1, GT1, TS1, D1, AREA RUG
BASE	WOOD TBD
WALLS	PT, WT1
CEILING	PT
DOORS	SEE DOOR SCHEDULE
Door Frame	SEE DOOR SCHEDULE

SCHEME 2	
FLOOR	CPT1
BASE	VB1
WALLS	PT
CEILING	ACT
DOORS	SEE DOOR SCHEDULE
Door Frame	SEE DOOR SCHEDULE

SCHEME 3 - STOR. 145, 144, SERV. 142	
FLOOR	VCT
BASE	VB2
WALLS	PT
CEILING	ACT
DOORS	SEE DOOR SCHEDULE
Door Frame	SEE DOOR SCHEDULE

SCHEME 4 - RESEARCH	
FLOOR	CPT1
BASE	VB1
WALLS	PT
CEILING	EXISTING TO REMAIN
DOORS	SEE DOOR SCHEDULE
Door Frame	SEE DOOR SCHEDULE

SCHEME 5	
FLOOR	CPT1
BASE	VB1
WALLS	PT
CEILING	SEE RCP
DOORS	SEE DOOR SCHEDULE
Door Frame	SEE DOOR SCHEDULE

SCHEME 6 CAFE	
FLOOR	LVT
BASE	VB2
WALLS	PT, WT1, GT1
CEILING	ACT
DOORS	SEE DOOR SCHEDULE
Door Frame	SEE DOOR SCHEDULE

SCHEME 7 BOARD ROOM 102	
FLOOR	EXISTING TO REMAIN
BASE	EXISTING TO REMAIN
WALLS	PT
CEILING	EXISTING TO REMAIN
DOORS	SEE DOOR SCHEDULE
Door Frame	SEE DOOR SCHEDULE

INTERIOR PAINTING NOTES  
Gypsum Board: Provide a primer and two finish coats over interior gypsum board surfaces:  
1. GWB Soffits and Ceilings: Flat Acrylic Finish, except as indicated otherwise.  
2. GWB Walls: Low-Luster (Eggshell), Acrylic Finish, except as indicated otherwise.  
3. Door Trim: Semi-gloss, Acrylic Finish, except as indicated otherwise.

SPECIALTY MILLWORK FIXTURES BY GC



FINISH PLAN  
SCALE: 1/4" = 1'-0"