

Symbol	Label	Quantity	Manufacturer	Catalog Number	Description	Lamp	Number Lamps	Lumens Per Lamp	Light Loss Factor	Wattage
	A	51	Gotham Architectural Lighting	EVO 35/07 4AR MWD LS XXV EZ10	EVO 4in recessed downlight, 750 lms, 3500K, 85CRI, specular finish; dimmable.	LED	1	826	0.9	10.3
	A1	2	Gotham Architectural Lighting	EVO LW 35/25 4AR LS XXV EZ10	EVO 4in recessed wall washer, 2500 lms, 3500K, 90CRI, specular finish; dimmable.	LED	1	1841	0.9	29.8
	A2	28	Gotham Architectural Lighting	EVO 35/20 4AR WD LS XXV EZ10	EVO 4in recessed downlight, 2000 lms, 3500K, 85CRI, specular finish; dimmable.	LED	1	1949	0.9	23.5
	B	7	iGuzzini	I.P495 UNV 01 D10 / BI5105	Laser Blade recessed wall washer, 3500K, 95CRI; dimmable.	LED	1	1006	0.9	35
	C	0	LumenWex	NOT USED		LED	1	4576.035	0.9	43.13
	C1	8	LumenWex	VIA2PDI-HLO-WIO-LED-80-400-750-35-5FT	VIA 2 direct/indirect 5' pendant, 400 / 750 lms, 3500K, 80CRI, widespread distribution (indirect); 2-circuit dimmable.	LED	1	4576.035	1.35	43.13
	C2	6	LumenWex	VIA2PDI-HLO-WIO-LED-80-400-750-35-8FT	VIA 2 direct/indirect 8' pendant, 400 / 750 lms, 3500K, 80CRI, widespread distribution (indirect); 2-circuit dimmable.	LED	1	4576.035	0.9	43.13
	D	93	ZUMTOBEL	MIRELEVO 22 RU 2800 835 L DU	Mirel recessed 2x2, 2800 lms, 80+CRI, square lens optic; dimmable.	LED	1	2770	0.9	22.3
	D1	0	ZUMTOBEL	MIRELEVO 24 RU 2800 835 L DU	Mirel recessed 2x4, 2800 lms, 80+CRI, square lens optic; dimmable.	LED	1	2810	0.9	21.6
	F	0	DECO LIGHTING	SFP-LED 22 20 35 UNV	SFP edge lit 2x2, 2014 lms, 3500K, 85CRI; dimmable.	LED	1	Absolute	0.9	20.7
	G	6	Brownlee Lighting	2340 24 C37LED XX 35K DIM	24" flush mount drum, 3837 lms, 3500K, 82CRI; dimmable.	LED	1	3258.909	0.9	36.9
	H	4	Brownlee Lighting	2681 19 XX C37LED FL2 XX 30K DIM	19" drum pendant, 3837 lms, 3000K, 82CRI; dimmable.	LED	1	2766.22	0.9	36.88
	I	1	Winona Lighting	WFP5810 12DIA LCP1A 35K MVOLT FABX XX	Enzo tapered pendant, 3185 lms, 3500K, 83+CRI; dimmable. Confirm OAH.	LED	1	3189.241	0.9	66
	J	1	Winona Lighting	WFP5818 30DIA SSTM A/60A19 XXV FABX XX	Giselle 30" drum pendant.	(8) 60W A19	1	3189.241	1.8	66
	J2	0	Winona Lighting	WFP5818 24DIA SSTM A/60A19 XXV FABX XX	Giselle 24" drum pendant.	(4) 60W A19	1	3189.241	0.9	66
	K	1	Tech Lighting	700SRVL X X LED830	Revel 50" linear pendant, 3500 lms, 3000K 80CRI; dimmable	LED	1	3915	0.9	40
	L	2	Juno Lighting	UPS30 30K 90CRI XX	Juno 30" soft task undercabinet, 844 lms, 3000K, 90CRI; dimmable.	LED	1	844	0.9	12.5
	M	3	Tech Lighting	700MPCIRWS-LED830	Circulet pendant, 500 lms, 3000K, 80CRI, satin nickel finish; dimmable.	LED	1	500	0.54	6.3

Note
 MODEL NUMBERS MAY NOT BE COMPLETE.
 DISREGARD QUANTITY FOR TYPE C2 - MANUFACTURER'S SYMBOL IS A 4' FIXTURE. TYPE C2 IS AN 8' LINEAR PENDANT, QUANTITY (3).

Description	Symbol	Avg	Max	Min	Max/Min	Avg/Min
100 RECEPTION	+	17 fc	29 fc	6 fc	4.8:1	2.8:1
100 RECEPTION DESK	+	31 fc	77 fc	4 fc	19.3:1	7.8:1
100 RECEPTION WHALE	+	21 fc	33 fc	13 fc	2.5:1	1.6:1
101 CONFERENCE	+	26 fc	40 fc	15 fc	2.7:1	1.7:1
103 HALL	+	20 fc	39 fc	4 fc	9.8:1	5.0:1
104 OFFICE	+	51 fc	65 fc	36 fc	1.8:1	1.4:1
105 OFFICE	+	41 fc	50 fc	32 fc	1.6:1	1.3:1
106 OFFICE	+	45 fc	55 fc	34 fc	1.6:1	1.3:1
107 OFFICE	+	43 fc	55 fc	32 fc	1.7:1	1.3:1
108 OFFICE	+	42 fc	53 fc	35 fc	1.5:1	1.2:1
109 OFFICE	+	51 fc	64 fc	37 fc	1.7:1	1.4:1
110 OFFICE	+	51 fc	65 fc	37 fc	1.8:1	1.4:1
111 OFFICE	+	42 fc	64 fc	14 fc	4.6:1	3.0:1
112 OFFICE	+	53 fc	68 fc	37 fc	1.8:1	1.4:1
113 HALL	+	13 fc	22 fc	5 fc	4.4:1	2.6:1
114 CONFERENCE	+	31 fc	41 fc	21 fc	2.0:1	1.5:1
115 RESEARCH	+	39 fc	51 fc	24 fc	2.1:1	1.6:1
116 OFFICE	+	53 fc	68 fc	37 fc	1.8:1	1.4:1
117 CONFERENCE	+	36 fc	84 fc	13 fc	6.5:1	2.8:1
118 OFFICE	+	51 fc	68 fc	35 fc	1.9:1	1.5:1
119 OFFICE	+	51 fc	67 fc	35 fc	1.9:1	1.5:1
120 OFFICE	+	42 fc	54 fc	35 fc	1.5:1	1.2:1
121 OFFICE	+	43 fc	55 fc	32 fc	1.7:1	1.3:1
122 OFFICE	+	45 fc	55 fc	34 fc	1.6:1	1.3:1
123 OFFICE	+	41 fc	51 fc	32 fc	1.6:1	1.3:1
124 OFFICE	+	51 fc	65 fc	37 fc	1.8:1	1.4:1
125 OFFICE	+	51 fc	66 fc	37 fc	1.8:1	1.4:1
126 OFFICE	+	51 fc	66 fc	36 fc	1.8:1	1.4:1
127 OFFICE	+	51 fc	68 fc	34 fc	2.0:1	1.5:1
128 HALL	+	21 fc	39 fc	15 fc	2.6:1	1.4:1
129 OFFICE	+	51 fc	67 fc	35 fc	1.9:1	1.5:1
130 OFFICE	+	51 fc	68 fc	34 fc	2.0:1	1.5:1
131 OFFICE	+	51 fc	66 fc	35 fc	1.9:1	1.5:1
132 OFFICE	+	33 fc	59 fc	7 fc	8.4:1	4.7:1
133 OFFICE	+	36 fc	64 fc	6 fc	10.7:1	6.0:1
134 OFFICE	+	35 fc	64 fc	10 fc	6.4:1	3.5:1
135 OFFICE	+	37 fc	64 fc	11 fc	5.8:1	3.4:1
136 OFFICE	+	37 fc	62 fc	14 fc	4.4:1	2.6:1
137 OFFICE	+	34 fc	58 fc	11 fc	5.3:1	3.1:1
138 OFFICE	+	35 fc	64 fc	9 fc	7.1:1	3.9:1
139 OFFICE	+	60 fc	79 fc	41 fc	1.9:1	1.5:1
140 OFFICE	+	43 fc	66 fc	12 fc	5.5:1	3.6:1
141 OPEN OFFICE	+	41 fc	84 fc	3 fc	28.0:1	13.7:1
143 CAFE	+	20 fc	37 fc	5 fc	7.4:1	4.0:1
143 CAFE CTR	+	44 fc	102 fc	20 fc	5.1:1	2.2:1
146 COPY	+	38 fc	62 fc	8 fc	7.8:1	4.8:1
146 COPY CTR	+	22 fc	29 fc	16 fc	1.8:1	1.4:1
146 COPY CTR	+	13 fc	19 fc	7 fc	2.7:1	1.9:1
147 OPEN OFFICE	+	39 fc	71 fc	5 fc	14.2:1	7.8:1
148 OFFICE	+	40 fc	65 fc	24 fc	2.7:1	1.7:1
149 OFFICE	+	40 fc	65 fc	25 fc	2.6:1	1.6:1
150 OFFICE	+	39 fc	66 fc	25 fc	2.6:1	1.6:1
151 OFFICE	+	37 fc	66 fc	20 fc	3.3:1	1.9:1
152 OFFICE	+	37 fc	64 fc	18 fc	3.6:1	2.1:1
153 OFFICE	+	39 fc	63 fc	24 fc	2.6:1	1.6:1
154 OFFICE	+	30 fc	38 fc	23 fc	1.7:1	1.3:1
155 COPY	+	33 fc	42 fc	27 fc	1.6:1	1.2:1
155 COPY CTR	+	36 fc	54 fc	13 fc	4.2:1	2.8:1
155 COPY CTR	+	36 fc	54 fc	14 fc	3.9:1	2.6:1
156 OFFICE	+	38 fc	64 fc	23 fc	2.8:1	1.7:1
157 ART WALL	+	17 fc	55 fc	4 fc	13.8:1	4.3:1
157 HALL	+	23 fc	44 fc	9 fc	4.9:1	2.6:1