

## ROXUL COMFORTBATT®

## Thermal Batt Insulation

### Product Description & Application

ROXUL COMFORTBATT® is a mineral wool batt insulation designed for thermal resistance in wood and steel framing.

	Performance	Test Standard										
Compliance	Mineral Fiber Blanket Insulation - Type I Compliant	ASTM C665										
Reaction to Fire	Flame spread index = 0 ; Smoke developed index = 0 Behavior of materials at 750°C - Non Combustible	ASTM E84 (UL 723) ASTM E136										
Density	> 2 lbs/ft³ (>32 kgs/m³)	ASTM C167										
Thermal Resistance	<table border="0"> <tr> <td>Wood Stud</td> <td>Steel Stud</td> </tr> <tr> <td>R 15 - 3.5" thick (89mm)</td> <td>R 10 - 2.5" thick (64mm)</td> </tr> <tr> <td>R 23 - 5.5" thick (140mm)</td> <td>R 15 - 3.5" thick (89mm)</td> </tr> <tr> <td>R 30 - 7.25" thick (184 mm)</td> <td>R 24 - 6" thick (152mm)</td> </tr> <tr> <td></td> <td>R 30 - 7.25" thick (184mm)</td> </tr> </table>	Wood Stud	Steel Stud	R 15 - 3.5" thick (89mm)	R 10 - 2.5" thick (64mm)	R 23 - 5.5" thick (140mm)	R 15 - 3.5" thick (89mm)	R 30 - 7.25" thick (184 mm)	R 24 - 6" thick (152mm)		R 30 - 7.25" thick (184mm)	ASTM C518
Wood Stud	Steel Stud											
R 15 - 3.5" thick (89mm)	R 10 - 2.5" thick (64mm)											
R 23 - 5.5" thick (140mm)	R 15 - 3.5" thick (89mm)											
R 30 - 7.25" thick (184 mm)	R 24 - 6" thick (152mm)											
	R 30 - 7.25" thick (184mm)											
Dimensions	Wood Stud 16" (406mm) on center: 15.25" x 47" (387mm x1194mm) Wood Stud 24" (610mm) on center: 23" x 47" (584mm x 1194mm) Steel Stud 16" (406mm) on center: 16.25" x 48" (413mm x 1219mm) Steel Stud 24" (610mm) on center: 24.25" x 48" (616mm x 1219mm)											



Issued 04-01-16  
 Supersedes 06-26-13

NOTE: \*Mast Format 1995 Edition \*\*Master Format 2004 Edition. As ROXUL Inc has no control over installation design and workmanship, accessory materials or application conditions, ROXUL Inc. does not warranty the performance or results of any installation containing ROXUL Inc's products. ROXUL Inc's overall liability and the remedies available are limited by the general terms and conditions of sale. This warranty is in lieu of all other warranties and conditions expressed or implied, including the warranties of merchantability and fitness for a particular purpose.