Tilson - proposed 9'x8' office **Wall Type & Door Sch**

Inspections Division
Date: 11/04/13

Walls will be 3 5/8 metal stud w/ 5/8" gypboard both sides, painted.

Door #1 to be knock down hollow metal frame, solid wood 1 3/4" door with lever passage set

Project:	Location:	Contractor/Vendor:	Project #	Date:
Tilson Office	245 Commercial	Great Falls		10/14/13