

## VRF HEAT RECOVERY BRANCH CIRCUIT CONTROLLER

System Tag	Tag Reference	M-Net Address	Model Number	Type (Single / Main / Sub)	Number of Ports
System 1	Floor 3	53	CMB-P1016NU-HA	Main	16
System 1	Floor 2	68	CMB-P108NU-GB	Sub	8

**Notes & Options:**

- 1 Include Diamondback Ball Valves BV-Series, 700PSIG working pressure, full port, 410A rated.
- 2 Connected Capacity to BC should not exceed 189,000 BTU/h for Single BCs and 126,000 BTU/h

Connected Capacity to BC	Voltage / Phase	MCA 208V/230V	Notes / Options
184,000.0	208/230V/1-phase	1.65 / 1.93	1, 2
53,000.0	208/230V/1-phase	0.64 / 0.58	1, 2

n for Sub BCs.