Inspections Division
Date: 06/16/17

MITSUBISHI CITY MULTI VRF OUTDOOR UNIT SCHEDULE

System Tag	Tag Reference	M-Net Address	Model Number	Modules	Nominal Cooling Capacity (BTU/h)
System 1		51, 52	PURY-HP192TSKMU-A-H	HP96, HP96	192,000.0

Notes & Options:

1 Nominal cooling capacities are based on indoor coil EAT of 80/67°F (DB/WB), outdoor of 95°F (
2 Nominal heating capacities are based on indoor coil EAT of 70°F (DB), outdoor of 43°F (WB)
3 Efficiency values for EER, IEER, COP are based on AHRI 1230 test method for mixture of ducte
4 For systems with multiple modules, refrigerant pipe dimensions indicate total system combined p
5 Added field charge listed is in addition to factory charge, this must be updated based upon final a

Inspections Division
Date: 06/16/17

Nominal Heating Capacity (BTU/h)	Design Cooling Outdoor Temp DB (°F)	Design Heating Outdoor Temp WB (°F)	Corrected Cooling Total Capacity (BTU/h)	Corrected Heating Capacity (BTU/h)	Voltage / Phase
215,000.0	87.0	-6.5	181,400.8	176,708.0	208/230V / 3-phase 3-wire

DB)

ed & non-ducted indoor units.
piping downstream of module
as-built piping layout.

Inspections Division

Date: 06/16/17

Electrical-Per Module			Notes / Options
208/230 or 460			
MCA 208V/230V	RFS	MFS	
60/54, 60/54	65, 65	104/94, 104/94	1, 2, 3, 4, 5