

ROOM FINISH SCHEDULE

AREA	ROOM		FLOOR		BASE		WAINSCOT			WALLS						CEILING			REMARKS			
	NO.	NAME	MAT	COLOR NO.	MAT	COLOR NO.	MAT	COLOR NO.	HT	NORTH	COLOR NO.	EAST	COLOR NO.	SOUTH	COLOR NO.	WEST	COLOR NO.	MAT		COLOR NO.	HT	
	201	LOBBY	CPT	C1	VB	VB1	-	-	-	PAINT	P1	PAINT	P1	PAINT	P1	PAINT	P1	GPDW	SAT1	8'-2"		
	202	STORAGE	VCT	VCT1	VB	VB2	-	-	-	PAINT	P1	PAINT	P1	PAINT	P1	PAINT	P1	SAT	SAT1	8'-2"		
	203	CONFERENCE	CPT	C1	VB	VB1	-	-	-	PAINT	P1	PAINT	P1	PAINT	P1	PAINT	P1	SAT	SAT1	8'-2"		
	204	OFFICE	CPT	C1	VB	VB1	-	-	-	PAINT	P1	PAINT	P1	PAINT	P1	PAINT	P1	SAT	SAT1	8'-2"		
	205	OFFICE	CPT	C1	VB	VB1	-	-	-	PAINT	P1	PAINT	P1	PAINT	P1	PAINT	P1	SAT	SAT1	8'-2"		
	206	OFFICE	CPT	C1	VB	VB1	-	-	-	PAINT	P1	PAINT	P1	PAINT	P1	PAINT	P1	SAT	SAT1	8'-2"		
	207	OFFICE	CPT	C1	VB	VB1	-	-	-	PAINT	P1	PAINT	P1	PAINT	P1	PAINT	P1	SAT	SAT1	8'-2"		
	208	WORKSTATIONS	CPT	C1	VB	VB1	-	-	-	PAINT	P1	PAINT	P1	PAINT	P1	PAINT	P1	SAT	SAT1	8'-2"		
	209	C.I.O.	CPT	C1	VB	VB1	-	-	-	PAINT	P1	PAINT	P1	PAINT	P1	PAINT	P1	SAT	SAT1	8'-2"		
	210	MANAGER	CPT	C1	VB	VB1	-	-	-	PAINT	P1	PAINT	P1	PAINT	P1	PAINT	P1	SAT	SAT1	8'-2"		
	211	MANAGER	CPT	C1	VB	VB1	-	-	-	PAINT	P1	PAINT	P1	PAINT	P1	PAINT	P1	SAT	SAT1	8'-2"		
	212	OFFICE	CPT	C1	VB	VB1	-	-	-	PAINT	P1	PAINT	P1	PAINT	P1	PAINT	P1	SAT	SAT1	8'-2"		
	213	MANAGER	CPT	C1	VB	VB1	-	-	-	PAINT	P1	PAINT	P1	PAINT	P1	PAINT	P1	SAT	SAT1	8'-2"		
	214	STAIR	EXIST	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	EXISTING TO REMAIN	
	215	WOMENS	EXIST	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	EXISTING TO REMAIN, NOTE 1 CLEAN EXISTING FIXTURES	
	216	MENS	EXIST	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	EXISTING TO REMAIN, NOTE 1 CLEAN EXISTING FIXTURES	
	217	HALL	CPT	C1	VB	VB1	-	-	-	PAINT	P1	PAINT	P1	PAINT	P1	PAINT	P1	SAT	SAT1	VARIES		
	218	ELEV VESTIBULE	EXIST	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	EXISTING TO REMAIN	
	219	STAIR	EXIST	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	EXISTING TO REMAIN	
	220	IT OPERATIONS MANAGER	CPT	C1	VB	VB1	-	-	-	PAINT	P1	PAINT	P1	PAINT	P1	PAINT	P1	SAT	SAT1	8'-2"		
	222	PRINT	CPT	C1	VB	VB1	-	-	-	PAINT	P1	PAINT	P1	PAINT	P1	PAINT	P1	SAT	SAT1	8'-2"		
	223	TEST	VCT	VCT 1	VB	VB1	-	-	-	PAINT	P1	PAINT	P1	PAINT	P1	PAINT	P1	SAT	SAT1	8'-2"		
	224	HALL	CPT	C1	VB	VB1	-	-	-	PAINT	P1	PAINT	P1	PAINT	P1	PAINT	P1	SAT	SAT1	8'-2"		
	225	WORKSTATIONS	CPT	C1	VB	VB1	-	-	-	PAINT	P1	PAINT	P1	PAINT	P1	PAINT	P1	SAT	SAT1	8'-2"		
	226	HALL	CPT	C1	VB	VB1	-	-	-	PAINT	P1	PAINT	P1	PAINT	P1	PAINT	P1	SAT	SAT1	8'-2"		
	227	CLO	-	-	-	-	-	-	-	PAINT	P1	PAINT	P1	PAINT	P1	PAINT	P1	GPDW		8'-0"	* ABV. RAISED FLOOR	
	228	OPERATIONS CENTER	RAISED	R1	VB	VB1	-	-	-	PAINT	P1	PAINT	P1	PAINT	P1	PAINT	P1	GPDW		VARIES		
	229	EQUIPMENT ROOM	RAISED	R1	VB	VB1	-	-	-	PAINT	P1	PAINT	P1	PAINT	P1	PAINT	P1	GPDW		8'-0"	* ABV. RAISED FLOOR	
	230	UPS ROOM	RAISED	R1	VB	VB1	-	-	-	PAINT	P1	PAINT	P1	PAINT	P1	PAINT	P1	GPDW		8'-0"	* ABV. RAISED FLOOR	
	231	CLO	EXIST	-	-	-	-	-	-	PAINT	P1	PAINT	P1	PAINT	P1	PAINT	P1					
	232	CLO	EXIST	-	-	-	-	-	-	PAINT	P1	PAINT	P1	PAINT	P1	PAINT	P1					
	601	TELEPHONE ROOM	EXIST	-	-	-	-	-	-	PAINT	P1	PAINT	P1	PAINT	P1	PAINT	P1	EXIST				
	602	OFFICE WORKSTATIONS	CPT	C1	VB	VB1	-	-	-	PAINT	P1	PAINT	P1	PAINT	P1	PAINT	P1	SAT	SAT1	*	* TO MATCH EXISTING	

MATERIAL LEGEND

CARPET (CARPET TILE)
 C1 - MILLIKEN PERSPECTIVES - P-6013 MULTI MURMUR, 126 - TUFTED MODULAR W/ UNDERSCORE CUSHION

VINYL COMPOSITE TILE
 VCT1 - CONGOLEUM ALTERNATIVES - AL-47, GOLDEN WHEAT

VINYL COVE BASE 6"
 VB1 - JOHNSONITE - 16, NAVY BLUE
 VB2 - JOHNSONITE - 129, SILK

PAINT
 P1 - BENJAMIN MOORE - 207, VELLUM
 P2 - SHERWIN WILLIAMS - SW0007, DECOROUS AMBER
 P3 - SHERWIN WILLIAMS - SW6106, KILIM BEIGE

SUSPENDED ACOUSTICAL TILE
 SAT1 - ARMSTRONG - CORTEGA 770, WHITE, WITH 15/16" PRELUDE SUSPENSION SYSTEM

RAISED FLOOR
 R1 - SEE SPECIFICATIONS

Architects + Engineers
HARRIMAN ASSOCIATES

66 Pearl Street, Suite 201
 Portland, Maine 04101

207.775.0053 tel
 207.775.0460 fax
 www.harriman.com

Building communities
 since 1870

© 2004

Project Title

MEMIC COMPUTER ROOM RELOCATION

PORTLAND, MAINE

HA Project No. **04150**

Key Plan

NOTES:

1. REPLACE DAMAGED OR STAINED EXISTING CEILING TILES WITH NEW AS REQUIRED PER NEW CONSTRUCTION.
2. ALL COLUMNS SHALL BE PAINTED P2.
3. DOOR FRAMES, BORROWED LIGHT FRAMES AND TRIM SHALL BE PAINTED P3.
4. ALL EXISTING WINDOW SILLS SHALL BE PAINTED P3.

	11-03-04	ISSUED FOR CONSTRUCTION
	10-18-04	90% REVIEW
	10-01-04	DD REVIEW
Mark	Date	Description
Issue Dates		

Drawing Status

Drawing Title

ROOM FINISH SCHEDULE

PA / PE: **PSC** Drawn By: **MED**

Drawing Number

A61.1