3RD FLOOR TOILET ROOM UPGRADES @ MEMIC

19 CROSS ST. / 261 COMMERCIAL ST.
PORTLAND, ME 04101

ABBREVIATIONS

APF	ABOVE FINISH FLOOR	HC	HANDICAP	S	SOUTH
ALUM or AL	ALUMINUM	HDWD	HARDWOOD	SAT	SUSPENDED ACOUSTICAL TILE CEILING
AWP	ACOUSTICAL WALL PANEL	HDR	HEADER		SHOWER CURTAIN
		HDWE	HARDWARE	SC	SOAP DISPENSER
BIT	BITUMINOUS	HM	HOLLOW METAL	SD	SCHEDULE
BM	BENCH MARK	HORIZ	HORIZONTAL	SCHED	SECTION
BOT	BOTTOM	HT	HEIGHT	SECT	SUSPENDED GYPSUM BOARD CEILING
BRG	BEARING			SGB	SHEET
BRK	BRICK	ID	INSIDE DIAMETER	SHT	SIMILAR
		IF	INSIDE FACE	SIM	SANITARY NAPKIN DISPOSAL
C	CARPET	IN	INCHES	SND	SPECIFICATIONS
CAB	CABINET	INSUL	INSULATION	SPEC	SQUARE
CB	CHALK BOARD	INT	INTERIOR	SQ	SYNTHETIC SPORTS SURFACE
CC	CENTER TO CENTER			SSS	STAINLESS STEEL
CH	CONCRETE FLOOR WITH HARDENER	JNT or JT	JOINT	STST	STEEL
				STL	FIBER
CJ	CONTROL JOINT	KEC	KITCHEN EQUIPMENT CONSULTANT	STRUCT	STRUCTURAL
CL	CENTER LINE	KP	KICK PLATE	SVI	STRAIGHT VINYL BASE
CLG	CEILING			SV	SHEET VINYL
CMU	CONCRETE MASONRY UNIT				
CONC	CONCRETE	L	LAVATORY	T	TEMPERED (GLASS)
CONT	CONTINUOUS	LAB	LABEL (FIRE)	TB	TACK BOARD
CONST	CONSTRUCTION	LNTL	LINTEL	TH	THERMAL (INSULATED)
CONTR	CONTRACTOR	LOC	LOCATION	THK	THICKNESS
CT	CERAMIC TILE	LS	LOCKSET	TO	TOP OF
				TOB	TOP OF BEAM
DBL	DOUBLE	M	MARBLE	TOM	TOP OF MASONRY
DC	DOOR CLOSER	MAS	MASONRY	TOW	TOP OF WALL
DIA	DIAMETER	MAX	MAXIMUM	TP	TOILET PAPER DISPENSER
DIM	DIMENSION	MB	MARKER BOARD	TYP	TYPICAL
DNA	DOES NOT APPLY	MECH	MECHANICAL		
DR	DOOR	MFGR	MANUFACTURER		
DTL	DETAIL	MIN	MINIMUM	VB	VAPOR BARRIER
DWG	DRAWING	MISC	MISCELLANEOUS	VCT	VINYL COMPOSITION TILE
		MO	MASONRY OPENING	VERT	VERTICAL
E	EAST	MR	MOP RINSING	VWC	VINYL WALL COVERING
EA	EACH	MRGB	MOISTURE RESISTANT GYPSUM BOARD		
EF	EACH FACE			W	WEST
EJ	EXPANSION JOINT	MTL	METAL	W/	WITH
EL	ELEVATION			WC	WATER CLOSET
ELEC	ELECTRICAL	N	NORTH	WD	WOOD
ELEV	ELEVATOR	NA	NOT APPLICABLE	WF	WATER FOUNTAIN
EMAG	ELECTROMAGNETIC	NIC	NOT IN CONTRACT	WG	WIRE GLASS
	HOLD OPEN	NO	NUMBER	WP	WOOD PANELING
EQ	EQUAL	NOM	NOMINAL		
EW	EACH WAY	NTS	NOT TO SCALE		
EWC	ELECTRIC WATER COOLER				
EXIST OF (E)	EXISTING	OA	OVERALL		
EXP	EXPANSION	OC	ON CENTER		
EXT	EXTERIOR	OD	OUTSIDE DIAMETER		
		OF	OUTSIDE FACE		
FCS	FLOOR COATING SYSTEM	OPNG	OPENING		
FD	FLOOR DRAIN	OPP	OPPOSITE		
FDN	FOUNDATION				
FE	FIRE EXTINGUISHER	P	PAINT		
FFE	FINISH FLOOR ELEVATION	PTD	PAINTED		
FIN	FINISH	PB	PANIC BAR		
FIN FL or FF	FINISH FLOOR	PL	PLATE		
FIN GR	FINISH GRADE	PLY WD	PLYWOOD		
FL	FLOOR	PNL	PANEL		
FR	FIRE RATING	PS	PASSAGE SET		
FRMG	FRAMING	PT	PRESSURE TREATED		
FT	FEET (FOOT)	PT & D	PAPER TOWEL & WASTE DISPENSER		
FV	FIELD VERIFY	PTN	PARTITION		
FWC	FABRIC WALL COVERING				
		RD	ROOF DRAIN		
G	GRANITE	RE	REFER		
GA	GAUGE	REF	REFRIGERATOR		
GALV	GALVANIZED	REINF	REINFORCED		
GB	GRAB BARS	REQ'D	REQUIRED		
GC	GENERAL CONTRACTOR	RM	ROOM		
GWB	GYPSUM WALL BOARD	RO	ROUGH OPENING		

GENERAL NOTES

1. ALL WORK SHALL CONFORM TO LOCAL AND STATE LAWS, ORDINANCES AND PREVAILING EDITIONS OF ADOPTED BUILDING CODES. IT IS THE CONTRACTOR'S RESPONSIBILITY TO SECURE ALL PERMITS FOR WORK.
2. THE CONTRACTOR SHALL VERIFY ALL CONDITIONS AND DIMENSIONS PRIOR TO COMMENCING THE WORK AND REPORT ANY DISCREPANCIES TO THE ARCHITECT. CONTRACTOR SHALL PROCEED WITH THE WORK ONLY AFTER SUCH DISCREPANCIES HAVE BEEN RESOLVED BY THE ARCHITECT. CONTRACTOR SHALL ALLOW A 48 HOUR TIME FRAME FOR RESOLVING DISCREPANCIES ONCE THE ARCHITECT HAS ACKNOWLEDGED THE CONDITION.
3. CONTRACTOR SHALL REVIEW AND VERIFY ALL EXISTING CONDITIONS PRIOR TO STARTING THE WORK IN ANY GIVEN AREA.
4. WORK WITH GIVEN DIMENSIONS AND LARGE SCALE DETAILS. DO NOT SCALE THE DRAWINGS AS THE REPRODUCTIVE PROCESS TENDS TO DISTORT THE ACCURACY OF THE GRAPHIC SCALE INDICATED.
5. ALL CONSTRUCTION ACTIVITIES SHALL BE PERFORMED IN A NEAT, SAFE, AND CLEAN MANNER. ALL CONSTRUCTION WASTE SHALL BE REMOVED FROM THE BUILDING. SITE BURNING IS NOT ALLOWED. LEAVE WORK AREA IN A CLEAN, SAFE
6. ALL CONSTRUCTION DEBRIS SHALL BE DISPOSED OF AT AN APPROVED OFF-SITE FACILITY IN COMPLIANCE WITH ALL REGULATIONS.
7. ALL WOOD IN CONTACT WITH MASONRY OR CONCRETE SHALL BE PRESSURE TREATED.
8. ALL CEILINGS SHALL BE LEVEL TO TO A TOLERENCE OF 1/8" IN A 20'-0" RADIUS WHEN CHECKED WITH A 10' STRAIGHT EDGE.
9. INSTALL SOLID BLOCKING AT WALL FRAMING BEHIND ALL SURFACE MOUNTED FIXTURES, TRIM AND HANDRAILS.
10. ALL GRAB BARS AND HANDRAILS SHALL BE ABLE TO SUPPORT A DEAD WEIGHT OF 250 LBS. AT ANY POINT.
11. THE LOCATION OF ANY DOOR JAMBS NOT DIMENSIONED SHALL BE 6" FROM ADJACENT PERPENDICULAR WALL.
12. ALL WALL PARTITIONS SHALL EXTEND FLOOR TO STRUCTURE ABOVE, UNLESS OTHERWISE NOTED.
13. ALL NEW SHEETROCK IN WET AREAS (PLUMBING FIXTURES) SHALL BE MOISTURE-RESISTANT TYPE, UNLESS OTHERWISE NOTED.
14. ALL NEW INTERIOR WALLS SHALL HAVE FULL- THICK ACOUSTICAL BATT INSULATION.
15. THESE ARCHITECTURAL DRAWINGS WERE PREPARED FOR THE OWNER & CONSTRUCTION MANAGER AS PART OF AN ABBREVIATED SERVICES AGREEMENT, AND AS SUCH, DO NOT DELINEATE ALL ASPECTS OF THE WORK.
16. THE CONSTRUCTION MANAGER SHALL BE RESPONSIBLE FOR THE COORDINATION OF ALL ASPECTS OF THE WORK, INCLUDING, BUT NOT LIMITED TO, MECHANICAL AND ELECTRICAL DESIGN-BUILD ENGINEERING, BUILDING TRADES & DISCIPLINES.
17. REFER TO THE ACCESSIBILITY DETAIL SHEET FOR AMERICANS WITH DISABILITIES ACT (ADA) AND MAINE HUMAN RIGHTS ACT (MHRA) CONSTRUCTION CRITERIA.

MATERIALS

- CONCRETE
- CONCRETE MASONRY UNIT
- BRICK
- GRAVEL
- SOIL
- STUD PARTITION (NEW)
- STEEL
- WOOD FRAMING
- WOOD BLOCKING
- PLYWOOD
- GYPSUM BOARD
- SUSPENDED ACOUSTICAL TILE
- BATT INSULATION
- RIGID INSULATION
- FINISH WOOD
- ONE HOUR RATED PARTITION
- TWO HOUR RATED PARTITION
- EXISTING PARTITION (SCREENED)
- NEW PARTITION

SYMBOLS

- 101 ROOM NUMBER
- DOOR NUMBER
- WINDOW NUMBER
- BUILDING SECTION
- WALL SECTION
- DETAIL SECTION
- CASEWORK ELEVATION
- INTERIOR ELEVATION
- VERTICAL ELEVATION
- PARTITION TYPE
- STRUCTURAL CENTERLINE

PROJECT TEAM

GENERAL CONTRACTOR

VILLAGE BUILDERS
21 NEW PORTLAND ROAD
GORHAM, MAINE 04038
207.839.6072

OWNER

CASCO VIEW HOLDINGS II, LLC
P.O. BOX 1137
PORTLAND, MAINE 04101
207.791.3461
CONTACT: JERRY DOBRANSKY

DRAWING INDEX

A-1 COVER SHEET
D-1 DEMOLITION PLAN
A-2 3RD FLOOR TOILET ROOM PLANS
A-3 DETAILS
A-4 ACCESSIBILITY NOTES & DETAILS

100% SUBMISSION
CONSTRUCTION PERMIT

GRANT HAYS ASSOCIATES
ARCHITECTURE & INTERIOR DESIGN
P.O. BOX 6179 FALMOUTH MAINE 04105
207.871.5900 www.granthays.com

SEAL

LICENSED ARCHITECT
MICHAEL F. HAYS
No. 1724
STATE OF MAINE

Michael F. Hays

REVISIONS

PROJECT NAME

3RD FLOOR TOILET UPGRADES @ MEMIC
19 CROSS ST. / 261 COMMERCIAL ST.
PORTLAND, MAINE 04101

SHEET

COVER SHEET

DATE
9 JUNE 2014

SCALE
NONE

DRAWN
MFH

JOB NO.
14 0619

SHEET
A-1

COPYRIGHT
REPRODUCTION OR RELEASE OF THIS DOCUMENT WITHOUT WRITTEN PERMISSION FROM GRANT HAYS ASSOCIATES IS PROHIBITED.