4th Floor Demolition Plan

1/8"= 1'-0"

3rd Floor Demolition Plan

1/8"= 1'-0"

Submittals

1. Provide owner with demolition schedule that minimize disturbances and interruptions to the owner's onsite operations. The schedule shall indicate interruptions of utility services, use and protection of elevator and stairs, locations of partitions for dust and noise control, and path of waste removal from building

Quality

2. Comply with applicable EPA notification regulation before starting selective demolition. Comply with ANSI A10.6 Safety Requirements for Demolition Operations, and NFPA 241: Standard for Safeguarding Construction, Alteration, and Demolition Operations

Project Conditions and Requirements

3. The owner will occupy areas of the building adjacent to the areas of demolition. Conduct the work in a manner that provides minimal disruption to the owners operations
4. The demolition plan is intended to be a schematic guide for removing existing assemblies, structures and materials as required for the new work to be installed. It is not intended to be exhaustive in detail. The contractor shall be familiar with the work of the project and remove all items as required by the work
5. Remove all construction assemblies, materials, finishes, mechanical and electrical items necessary for the completion of the work as depicted on the drawings, specifications, and supplementary instructions. Refer to mechanical and electrical drawings for additional information on demolition of those items.
6. The removal disposal and associated fees of all demolished items shall be the responsibility of the General Contractor.
7. All removed items, debris and salvage shall be the property of the General contractor unless noted otherwise in the drawings or by the Owner.
8. Demolition may uncover existing conditions, structures or assemblies that were not foreseen by the Architect or owner. The contractor shall bring to the attention of the Architect any existing conditions that are discovered that will affect the scope or design of the project
9. The Contractor shall restore any fire rated assemblies damaged by the demolition process to their required rating
10. The contractor shall identify any pre-existing damage to fire rated walls, floors, ceilings and columns. The Architect will coordinate with the General Contractor to develop a plan to restore the continuity of rated assemblies
11. The Contractor shall protect finishes, assemblies and structures not required to be demolished or that are outside the area of work.
12. The contractor shall control dust, noise and vibration, to protect the adjacent areas
13. The contractor shall provide shoring and temporary support of existing structural members that the work requires.
14. materials to be removed and reused, such as light fixtures and other electrical equipment, doors, and plumbing fixtures, shall be stored and protected from damage by ongoing construction activities
15. Maintain and ensure safe passage of building occupants around and through areas of demolition.
16. Partition walls shown to be demolished shall be demolished in their entirety, for their full height.

Hazardous Materials

17. If the Contractor suspects that hazardous materials such asbestos containing materials (ACM), lead based paint, polychlorinated biphenyl, (PCB) and petroleum products are present he shall not disturb the material and notify the owner's representative.
18. Fluorescent lights shall be handled and disposed of properly to prevent the release of mercury vapor

Conditions Specific to this Project

1. Remove all existing ceiling tile, suspension system, lighting, mechanical registers

CITY OF PORTLAND, MAINE — RESURGAM

Inspections Division

Date: 09/10/15

facilitation

Lisa Whited
Chief Transformation Officer
207. 329. 2189 lisa@workplacetf.com

Michael Barton
Value and Constructablity Analyst
207. 939. 5432 michael@workplacetf.com

Josef Chalat
Maine Licensed Architect
207. 318. 3234 AzimuthBlu@gmail.com

Mechanical and Electrical Engineering:
Bennet Engineering
contact: Cat Tranberg
ph (207) 865-9475
Cat@bennettengineering.net

Project:

MEMIC
Tenant Improvement to 3rd, 4th, and 5th floors
261 Commercial Street, Portland Maine
CBL 038 F019

Tenant: MEMIC
261 Commercial Street
Portland Maine, 04101

Tenant Contact
Catherine Lamson,
Senior Vice President
Chief Administrative Officer
(207) 791 3304

Building Owner:
Casco View Holdings II, LLC
PO Box 1137
Portland, ME 04104

General Contractor:
Zachau Construction
1185 U.S. Route One
Freeport, ME 04032
ph (207) 865-9925 (office)
contact: Jon
207.807.8980 (mobile)
Jon@zachauconstruction.com

Date	Purpose
08/13/2015	Review by JD not for construction

Sheet Title

3rd and 4th Floor Demolition Plans

Sheet Number

d1