Optional detail at furniture whips
1½"= 1'-0"

Wall Notes:
1. Provide acoustic sealant at bottom of wall, power outlets, switches
2. Offset outlets or other penetrations at least one stud bay so that no stud bay contains pentrations on both sides of wall
3. Provide moisture resistant cement backer board board at tile installations
4. continue framing to structure above continue gypsum wall board 4-6" above ceiling

WT-01 Wall Type (non-rated partition)
1½"= 1'-0"

3rd Floor Plan

3/16" = 1'-0"

1. contractor shall verify where solid blocking is required and provide blocking appropriate to items to be supported
2. All fire extinguishers shall be provided in ADA compliant cabinet mounts

d DIRTT wall system, glazed

d DIRTT wall system, opaque

Inspections Division

Date: 09/10/15

facilitation

Lisa Whited
Chief Transformation Officer
207. 329. 2189 lisa@workplacetf.com

Michael Barton
Value and Constructability Analyst
207. 939. 5432 michael@workplacetf.com

Josef Chalat
Maine Licensed Architect
207. 318. 3234 AzimuthBlu@gmail.com

Mechanical and Electrical Engineering:
Bennet Engineering
contact: Cat Tranberg
ph (207) 865-9475
Cat@bennetengineering.net

Project:

MEMIC
Tenant Improvement to 3rd, 4th, and 5th floors
261 Commercial Street, Portland Maine
CBL 038 F019

Tenant: MEMIC
261 Commercial Street
Portland Maine, 04101

Tenant Contact
Catherine Lamson,
Senior Vice President
Chief Administrative Officer
(207) 791 3304

Building Owner:
Casco View Holdings II, LLC
PO Box 1137
Portland, ME 04104

General Contractor:
Zachau Construction
1185 U.S. Route One
Freeport, ME 04032
ph (207) 865-9925 (office)
contact: Jon
207.807.8980 (mobile)
Jon@zachauconstruction.com

Date	Purpose
08/13/2015	Review by JD not for construction

Sheet Title

3rd Floor Plan

Sheet Number

a1