



20 Thomas Dr
 WESTBROOK, ME 04092-3824
 (207) 842 6440
 FAX: (207) 842 6439
 www.simplexgrinnell.com

SimplexGrinnell Material List (THIS IS NOT A PRICE QUOTATION)

TO:
 Casco View Holdings II, LLC
 261 Commercial St
 PORTLAND, ME 04101-4622

Project: MEMIC CV - Fir 1, 6, Penthouse
 Customer Reference: Casco View Memic 2-13
 SimplexGrinnell Reference: 969407001
 Date: 03/20/2013
 Page 1 of 2

QUANTITY	MODEL NUMBER	DESCRIPTION
Casco View Memic 2-13		
Casco View Memic 2-13		
FIRST FLOOR		
1	SSU00672	CAB DOC STORAGE 12X13X2D RED
2	4009-9401	4009 ADDRESSABLE CONTROLLER
4	2081-9288	BATTERY 12.7AH
27	4906-9203	MC TRUEALERT V/O WALL MT WHITE
8	4906-9229	MC TRUEALERT A/V WALL MT WHITE
3	4906-9204	MC TRUEALERT V/O CEILING MT WHT
37	4098-9714	PHOTO SENSOR
3	4098-9733	HEAT SENSOR
40	4098-9792	SENSOR BASE
8	4099-9003	MANUAL STATION - DOUBLE ACTION
4	2975-9178	BACKBOX MANUAL STATION
3	4090-9116	ADDRESS MODULE-ISOLATOR
4	4090-9001	SUPERVISED IAM
1	4906-9131	WP MC AV NON-ADDR WALL MT RED
1	4905-9828	WP AV/VO 1.5IN BACK BOX RED
1	4905-9816	ADDRESS. ADAPTER FOR SLC
1	4905-9817	"SURFACE MOUNT, 4"" TRIMPLATE
SIXTH FLOOR		
9	4906-9129	HORN/STROBE MC WHITE
PENTHOUSE		
1	4906-9227	MC TRUEALERT A/V WALL MT RED
1	4905-9941	SKIRT, HORN/STROBE RED

WIRING AND INSTALLATION
WIRING AND INSTALLATION

Comments

This quote includes the following:

1. Replacing old non-addressable Signals and Initiating Devices on the 1st and 6th Floor, with new addressable devices, as shown on the plans dated 2/27/13.



Project: MEMIC CV - Fir 1, 6, Penthouse
Customer Reference: Casco View Memic 2-13
SimplexGrinnell Reference: 969407001
Date: 03/20/2013
Page 2 of 2

SimplexGrinnell Material List (THIS IS NOT A PRICE QUOTATION)

Comments (continued)

2. Adding an Addressable Pull Station and Horn/Strobe to the Elevator Penthouse, on the Roof.
3. Adding Addressable Power Extenders to the Freight Elevator Lobbies on the 1st and 6th Floors.
4. Installing a Weatherproof Strobe adjacent to the existing Knox Box.
5. Running new wiring to all new devices.
6. Removal of the existing conventional devices and associated wiring, once the Addressable Devices are in Service.
7. Programming and Testing. (Note: Signal Testing will be done between 4 and 5PM.)
8. A Fire Alarm Permit from the Portland Fire Department.

This quote includes the disconnecting the following unused devices and coiling the wires up in the existing back boxes. If not in conduit the existing wiring will be pulled up above the ceiling and terminated in junction boxes.

1. 3rd Floor Fitness Center.
2. 3rd Floor Hall near Restrooms.
3. 4th Floor Hall near Restrooms.
4. 4th Floor South Wall (Simplex Device).
5. 5th Floor Hall near Restrooms.
6. 6th Floor Ceiling near Electric Room.
7. 6th Floor Hall near Telco Room.

NOTE: This proposal is subject to the approval of the Portland Fire Department. Any additional devices required would be at an additional cost.