Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 03/05/15

GENERAL NOTES: (SEE A-1.1 FOR ADDED NOTES)

DEMOLITION:
1. REMOVE ALL NON-STRUCTURAL WALLS AS SHOWN.

2. REMOVE ALL ELEVATOR EQUIPMENT.

3. BASEMENT TO BE SPRINKLED AND HAVE 1 HOUR RATED CEILING.

4. DISCONNECT GAS TO UPPER LEVELS. GAS SERVICE TO BE PROVIDED AS PER OWNER'S NEEDS.

5. SEE A-6.1 DOOR SCHEDULE.

CONTRACTOR TO VERIFY ALL EXISTING CONDITIONS. SEE NOTE 6 A-1.1.

James Sterling AIA
Architect
142 High Street
Portland, Maine

SHWARTZ BUILDING RENOVATIONS

BASEMENT LEVEL
scale: 1/4"=1'-0"

REGISTERED ARCHITECT JAMES STERLING NO. 1076 STATE OF MAINE

A-1.0

9/13/12

REVISIONS:
24 SEPTEMBER 2012
19 OCTOBER 2012
#3 24 APRIL 2013