GENERAL NOTES

DEMOLITION:
1. REMOVE ALL NON-STRUCTURAL WALLS AS SHOWN AND REMOVE EXISTING DOOR OPENINGS.

2. REMOVE ALL ELEVATOR EQUIPMENT.

3. FLOOR AND CEILNG FINISHES IN NEW APARTMENTS TO BE DETERMINED BY OWNER.

4. ALL EXISTING PANELING ON BOTH SIDES OF STAIR 200 ENCLOSURE TO BE REMOVED EXPOSING EXISTING PLASTER, APPLY F1 FINISH OVER PLASTER.

5. ALL EXISTING OPENINGS TO STAIR 200 TO BE INFILLED, F1.

6. DIMENSIONS ARE FOR NEW PARTITIONS AND OPENINGS ONLY. OVERALL APARTMENT DIMENSIONS ARE FOR FIELD VERIFICATION. NOTIFY THE ARCHITECT OF ANY DISCREPANCIES BEFORE STARTING WORK.

7. DISCONNECT AND REMOVE ALL GAS PIPING.

CONTRACTOR TO VERIFY ALL EXISTING CONDITIONS AND VERIFY PROPOSED DIMENSIONS. SEE NOTE 6.

Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 03/05/15

James Sterling AIA
Architect
142 High Street
Portland, Maine

SHWARTZ BUILDING RENOVATIONS

SECOND LEVEL

scale: 1/4" = 1'-0"

REGISTERED ARCHITECT JAMES AVERY STERLING NO. 1076 STATE OF MAINE

REVISIONS:
24 SEPTEMBER 2012
19 OCTOBER 2012

9/13/12

A-1.2