

## **Children's Museum *Down to the Sea* landscaping scope**

### **Asphalt removal**

- Remove existing asphalt on courtyard area and dispose (about 2,500sq')
- Fence will be removed by CMTM staff

### **Paver borders**

- Install 12" paver borders between sand, bluestone, and playground chip areas

### **Sand, bluestone, playground chips**

- Install 3" deep playground sand (see g)
- Install ADA accessible crushed bluestone walk way around sand
- Install Playground chips around perimeter (about 1600sq')

### **Decorative Stones**

- Install 25 sq' of irregular bluestone Stepping stones for paths and landings
- according to plan
- Install boulders buried 1/3 according to plan

### **Stone veneer whale pond**

- Install concrete block pool water proofed sealer in pool.
- Walls are approx. 18" high x 12" wide with veneer Boston blend round stone on both sides with full nose ledgerstone paver cap.
- Carve and shape 3 whale rocks so the pump water spouts out of the top of the whale holes. Carve rocks so that the pump heads are hidden from view.
- Cover pump with approx 8" round river stone. Visible depth of water in pool is not to exceed 1 in.

### **Finished landscaping**

- Spec and install shrubs and perennials in marked planting areas