

DOOR SCHEDULE									
DOOR #	FROM	TO	SIZE	DOOR MATERIAL	DOOR TYPE	DOOR RATING	FRAME	HARDWARE SET	NOTES
001	SPA	STORAGE	3'-0" X 7'-0"	SOLID CORE	I	-	HOLLOW METAL	04	
002	SPA	LAUNDRY	3'-0" X 7'-0"	SOLID CORE	I	-	HOLLOW METAL	02	
100	SHAMPOO AREA	SPA TREATMENT #1	3'-0" X 7'-0"	SOLID CORE	I	-	HOLLOW METAL	03	
101	SHAMPOO AREA	SPA TREATMENT #2	3'-0" X 7'-0"	SOLID CORE	I	-	HOLLOW METAL	03	
102	SHAMPOO AREA	SPA TREATMENT #3	3'-0" X 7'-0"	SOLID CORE	I	-	HOLLOW METAL	03	
103	FUTURE TENANT	ADA BATH	3'-0" X 7'-0"	SOLID CORE	I	-	HOLLOW METAL	03	
104	HAIR SALON	VESTIBULE	3'-0" X 7'-0"	STOREFRONT	II	-	ALUMINUM	01	
105	VESTIBULE	FUTURE TENANT	3'-0" X 7'-0"	STOREFRONT	II	-	ALUMINUM	01	
106	VESTIBULE	WAITING AREA	3'-0" X 7'-0"	STOREFRONT	II	-	ALUMINUM	01	
107	HAIR SALON	WAITING AREA	9'-0" X 7'-0"	SLIDING GLASS	III	-	ALUMINUM	05	
200	CORRIDOR	ADA BATHROOM	3'-0" X 7'-0"	SOLID CORE	I	-	HOLLOW METAL	03	
201	CORRIDOR	MAKE-UP STUDIO	3'-0" X 7'-0"	SOLID CORE	I	-	HOLLOW METAL	06	
202	CORRIDOR	FITNESS STUDIO	6'-0" X 8'-0"	SOLID CORE	IV	-	WOOD	06	
203	UNISEX BATH	CHANGING AREA	3'-0" X 7'-0"	SOLID CORE	I	-	HOLLOW METAL	03	
204	UNISEX BATH	CHANGING AREA	3'-0" X 7'-0"	SOLID CORE	I	-	HOLLOW METAL	03	

GENERAL DOOR SCHEDULE NOTES:

- ALL DOOR HARDWARE AND ACCESSORIES TO BE ADA COMPLIANT.
- COORDINATE DOOR HARDWARE FINISHES AND DESIGNS WITH OWNER.

HARDWARE SETS:

- 01 EXIT DOOR: (3) CLEAR OFFSET HINGES, CLOSER, STRIKE, LATCH ASSEMBLY, LOCKSET, ADA THRESHOLD, DOOR PULL, PANIC BAR EXIT
- 02 PASSAGE DOOR: (3) HINGES, CLOSER, STRIKE, LATCH ASSEMBLY, LEVER HANDLE
- 03 PRIVACY DOOR: (3) HINGES, CLOSER, STRIKE, LATCH ASSEMBLY, PRIVACY LOCKSET, LEVER HANDLE
- 04 STORAGE DOOR (3) HINGES, CLOSER, STRIKE, LATCH ASSEMBLY, STORAGE LOCKSET, LEVER HANDLE
- 05 TELESCOPING GLASS DOOR: TELESCOPING DOOR HARDWARE, LOCKSET
- 06 ENTRY DOOR (3) HINGES, CLOSER, STRIKE, LATCH ASSEMBLY, ENTRY LOCKSET, LEVER HANDLE/DOOR PULL

