COPYRIGHT: Reuse or reproduction of the contents of this document is not permitted without written permission of Bild Architecture LLC

DOOR SCHEDULE									
DOOR #	FROM	TO	SIZE	DOOR MATERIAL	DOOR TYPE	DOOR RATING	FRAME	HARDWARE SET	NOTES
001	SPA	STORAGE	3'-0" X 7'-0"	SOLID CORE	I	-	HOLLOW METAL	04	
002	SPA	LAUNDRY	3'-0" X 7'-0"	SOLID CORE	I	-	HOLLOW METAL	02	
100	SHAMPOO AREA	SPA TREATMENT #1	3'-0" X 7'-0"	SOLID CORE	I	-	HOLLOW METAL	03	
101	SHAMPOO AREA	SPA TREATMENT #2	3'-0" X 7'-0"	SOLID CORE	I	-	HOLLOW METAL	03	
102	SHAMPOO AREA	SPA TREATMENT #3	3'-0" X 7'-0"	SOLID CORE	I	-	HOLLOW METAL	03	
103	FUTURE TENANT	ADA BATH	3'-0" X 7'-0"	SOLID CORE	I	-	HOLLOW METAL	03	
104	HAIR SALON	VESTIBULE	3'-0" X 7'-0"	STOREFRONT	II	-	ALUMINUM	01	
105	VESTIBULE	FUTURE TENANT	3'-0" X 7'-0"	STOREFRONT	II	-	ALUMINUM	01	
106	VESTIBULE	WAITING AREA	3'-0" X 7'-0"	STOREFRONT	II	-	ALUMINUM	01	
107	HAIR SALON	WAITING AREA	9'-0" X 7'-0"	SLIDING GLASS	III	-	ALUMINUM	05	
2 108	HAIR SALON	STAIR	3'-0" X 7'-0"	SOLID CORE	I	1HR	HOLLOW METAL	07	
200	CORRIDOR	ADA BATHROOM	3'-0" X 7'-0"	SOLID CORE	I	-	HOLLOW METAL	03	
2 201	CORRIDOR	MAKE-UP STUDIO	3'-0" X 7'-0"	SOLID CORE	I	-	HOLLOW METAL	06	
202	CORRIDOR	FITNESS STUDIO	6'-0" X 8'-0"	SOLID CORE	IV	-	WOOD	06	
203	UNISEX BATH	CHANGING AREA	3'-0" X 7'-0"	SOLID CORE	I	-	HOLLOW METAL	03	
204	UNISEX BATH	CHANGING AREA	3'-0" X 7'-0"	SOLID CORE	I	-	HOLLOW METAL	03	
205	CORRIDOR	SPIRAL STAIRCASE	3'-0" X 7'-0"	SOLID CORE	V	-	HOLLOW METAL	07	

GENERAL DOOR SCHEDULE NOTES:

- ALL DOOR HARDWARE AND ACCESSORIES TO BE ADA COMPLIANT.
- COORDINATE DOOR HARDWARE FINISHES AND DESIGNS WITH OWNER.

HARDWARE SETS:

01	EXIT DOOR:	(3) CLEAR OFFSET HINGES, CLOSER, STRIKE, LATCH ASSEMBLY, LOCKSET, ADA THRESHOLD, DOOR PULL, PANIC BAR EXIT
02	PASSAGE DOOR:	(3) HINGES, CLOSER, STRIKE, LATCH ASSEMBLY, LEVER HANDLE
03	PRIVACY DOOR:	(3) HINGES, CLOSER, STRIKE, LATCH ASSEMBLY, PRIVACY LOCKSET, LEVER HANDLE
04	STORAGE DOOR	(3) HINGES, CLOSER, STRIKE, LATCH ASSEMBLY, STORAGE LOCKSET, LEVER HANDLE
05	TELESCOPING GLASS DOOR	TELESCOPING DOOR HARDWARE, LOCKSET
06	ENTRY DOOR	(3) HINGES, CLOSER, STRIKE, LATCH ASSEMBLY, ENTRY LOCKSET, LEVER HANDLE/DOOR PULL
07	STAIRCASE DOOR:	(3) HINGES, CLOSER, STRIKE, LATCH ASSEMBLY, LEVER HANDLE. ELECTRONIC HOLD OPENS

3 1ST FLR ADA BATH
0 2'-0" SCALE: 1/2" = 1'-0"

2 1ST FLR EXISTING BATH
0 2'-0" SCALE: 1/2" = 1'-0"

3 UNISEX TOILETS
0 2'-0" SCALE: 1/2" = 1'-0"

4 2ND FLR ADA BATHROOM
0 2'-0" SCALE: 1/2" = 1'-0"

A

B

C

D

5 ADA BATH ELEVATIONS
0 2'-0" SCALE: 1/2" = 1'-0"

Bild Architecture
PO Box 8235
Portland, ME
04104
207.408.0168
evan@bildarchitecture.com

bild ARCHITECTURE

LICENSED ARCHITECT 11-21.2016 EVAN A. CARROLL No. 3687 STATE OF MAINE

Reviewed for Code Compliance Inspections Division Approved as Noted Date: 02/06/17

PROJECT NO. 16015
PROJECT NAME HEAD GAMES
PORTLAND, ME

REVISIONS
1 | 12.7.2016
2 | 1.31.2017
3 | -
4 | -
5 | -

DRAWN BY AEW
PERMITTING DRAWINGS
SHEET TITLE SCHEDULES & INT ELEVS

ISSUE DATE 11.21.16
SHEET SCALE 1/4" = 1'-0"

A

2.0