PORTLAND MUSEUM of ART

ROBERT INDIANA "SEVEN" PEDESTAL

GENERAL NOTES:

1. FIELD VERIFY ALL DIMENSIONS AND LAYOUT PRIOR TO PROCEEDING WITH WORK. NOTIFY ARCHITECT IN WRITING OF ANY DISCREPANCIES OR INCONSISTENCIES. FAILURE TO REPORT ANY DISCREPANCIES WITHIN THESE CONSTRUCTION DOCUMENTS TO THE ARCHITECT WILL NOT BE GROUNDS FOR ADDITIONAL COST OR CHANGE ORDERS.
2. CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING ALL MATERIALS (UNLESS NOTED OTHERWISE), AND WORKMANSHIP IN ACCORDANCE WITH FEDERAL, STATE, CITY AND LOCAL BUILDING CODES AND THEIR REQUIREMENTS.
3. CONTRACTOR AND ALL TRADES SHALL NOTE REQUIREMENTS OF "GENERAL NOTES" ON ALL SHEETS.
4. EACH TRADE TO PROVIDE SMOKE OR FIRE SEALANT AT PENETRATIONS AS REQUIRED FOR WALL TYPE. ALL SEALANT, FIRE STOPPING, AND SMOKE STOPPING ASSEMBLIES SHALL BE U.L. RATED.
5. DIMENSIONS ARE FACE OF CONCRETE, FACE OF MASONRY, AND CENTERLINE OF STUD PARTITIONS, UNLESS INDICATED OTHERWISE. DIMENSIONS NOTED AS CLR (CLEAR) ARE TO FACE OF FINISH SUBSTRATE.
6. REFER TO ALL CONSTRUCTION DOCUMENTS FOR REQUIREMENTS WHICH MAY AFFECT THE WORK IN ANOTHER DISCIPLINE AND COORDINATE WORK.
7. REFER TO DETAILS & ENLARGED PLANS FOR ADDITIONAL DIMENSIONAL INFORMATION.
8. CONTRACTOR SHALL PROVIDE BLOCKING AND COORDINATE FINAL MOUNTING LOCATIONS AND BLOCKING REQUIREMENTS FOR ALL ITEMS, INCLUDING THOSE IDENTIFIED AS "BY OWNER," AND ALL ITEMS IDENTIFIED AS "OWNER SUPPLIED, CONTRACTOR INSTALLED."
9. DO NOT SCALE DRAWINGS.
10. "PROVIDE" MEANS "FURNISH AND INSTALL".
11. ELEVATIONS INDICATED ON THE GENERAL, STRUCTURAL, ELECTRICAL, ARE BASED ON EXISTING SITE CONDITIONS.
12. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE CUTTING & PATCHING OF FLOORS, WALLS, & CEILINGS DUE TO THE REMOVAL OR ADDITION OF MECHANICAL, PLUMBING, ELECTRICAL, & FIRE PROTECTION WORK. SEE GENERAL NOTE NUMBER (13.) FOR FINISH REQUIREMENTS.
13. COORDINATE THE EXTENT OF ALL REMOVALS W/ NEW FINISHES & FINISHES TO REMAIN. PATCH & REPAIR ALL DAMAGE TO EXISTING FINISHES TO REMAIN TO MATCH THE ADJACENT FINISH. EXTEND THE PATCH & REPAIR CONTINUOUSLY TO THE NEAREST CORNER UNLESS NOTED OTHERWISE. PREPARE FINISH SUBSTRATES FOR APPLICATION OF FINISHES IN ACCORDANCE W/ THE FINISH MANUFACTURER'S WRITTEN RECOMMENDATIONS.
16. UNLESS NOTED OTHERWISE CONDUIT & PIPING OF ALL ASSOCIATED TRADES SHALL BE RUN CONCEALED WITHIN CEILING CAVITIES OR WALL FRAMING.

GENERAL SYMBOL LEGEND:

A00 / AE000	BUILDING SECTION
A00 / AE000	WALL SECTION
A00 / AE000	DETAIL
A00 / AE000	EXTERIOR ELEVATION
A / D / A00 / AE000 / B / C	INTERIOR ELEVATION
	LEVEL LINE
8	CIRCLE NOTE
8 X	WINDOW TAG X= GLAZING TYPE
8 X	PARTITION TAG X= PARTIAL WALL HEIGHT, UNO
0000	DOOR TAG
MAIN LOBBY / A402	ROOM NAME ROOM NUMBER
A	COLUMN BUBBLE AND CENTER LINE
S	BACKER ROD & SEALANT CONTINUOUS UNLESS NOTED OTHERWISE

GRID NO.	TITLE
SCALE	REFERENCE SHEET

ABBREVIATIONS:

ACT	ACOUSTIC CEILING TILE
AFF	ABOVE FINISHED FLOOR
AP	ACCESS PANEL
BO	BOTTOM OF
BOF	BOTTOM OF FOOTING
BOS	BOTTOM OF STEEL
CJ	CONTROL JOINT, CONSTRUCTION JOINT
CLG	CEILING
CO	CENTER OF
COORD	COORDINATE
(E)	EXISTING
EA	EACH
EPDM	ETHYLENE PROPYLENE DIENE MONOMER
EXIST	EXISTING
FE	FIRE EXTINGUISHER
FF	FINISHED FLOOR; FAR FACE
FT	FIRE TREATED
GC	GENERAL CONTRACTOR
GWB	GYPSUM WALL BOARD
HC	HANDICAPPED; HOLLOW CORE
HM	HOLLOW METAL
HT	HEIGHT
HVAC	HEATING, VENTILATING AND AIR CONDITIONING
L	ANGLE
LLH	LONG LEG HORIZONTAL
LLV	LONG LEG VERTICAL
MDO	MEDIUM DENSITY OVERLAY
MO	MASONRY OPENING
MTL	METAL
NIC	NOT IN CONTRACT
NTS	NOT TO SCALE
OC	ON CENTER
OH	OVERHEAD
PAF	POWDER-ACTUATED FASTENER
PL	PLATE
PLAM	PLASTIC LAMINATE
PLF	POUNDS PER LINEAR FOOT
PSF	POUNDS PER SQUARE FOOT
PSI	POUNDS PER SQUARE INCH
PT	PRESERVATIVE TREATED
PVC	POLYVINYL CHLORIDE
PW	PLYWOOD
R	RISER; RADIUS
RB	RESILIENT BASE
RD	ROOF DRAIN
RO	ROUGH OPENING
SC	SOLID CORE
SCHD	SCHEDULE
SF	SQUARE FOOT; SUPPLY FAN
SK	SHEAR KEY
SS	STAINLESS STEEL
STL	STEEL
T	TREAD
TCE	TOP CHORD EXTENSION
TO	TOP OF
TOC	TOP OF CONCRETE
TOF	TOP OF FOOTING
TOM	TOP OF MASONRY
TOP	TOP OF PIER
TOS	TOP OF STEEL; TOP OF SLAB
TOW	TOP OF WALL
TP	TOILET PAPER (DISPENSER)
UNO	UNLESS NOTED OTHERWISE
VCT	VINYL COMPOSITION TILE
VTR	VENT THROUGH THE ROOF
W/	WITH
WC	WATER CLOSET
WF	WIDE FLANGE
W/O	WITHOUT
WD	WOOD
WP	WORKING POINT
WWF	WELDED WIRE FABRIC

DRAWING LIST:

GENERAL

GI001 COVER SHEET

SITE/CIVIL

CP101 SITE PLANS

STRUCTURAL

S-101 PEDESTAL PLANS AND DETAILS
S-201 VENEER ELEVATIONS AND LAYOUT

ELECTRICAL

E-101 ELECTRICAL PLANS

CITY OF PORTLAND MAINE RESURGAM

1112Wolfrey 999Gale,#C230a, 999 LaFlorista,Hdq,Motors 124/139

Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 10/17/14

ARCHITECTURE
ENGINEERING
PLANNING
INTERIORS
ENERGY

SMRT

PROJECT NORTH:

PORTLAND MUSEUM OF ART
ROBERT INDIANA "SEVEN" PEDESTAL
PORTLAND, MAINE

ISSUED FOR CONSTRUCTION
10-08-14

CURRENT ISSUE STATUS:

REV	DESCRIPTION	DATE
0	ISSUED FOR CONSTRUCTION	10-08-14

GRAPHIC SCALE: 0" 1"

SCALE:	NA
PROJECT MANAGER:	ADB
JC/DRAWN BY:	ADB / ADB
A/E OF RECORD:	ADB
PROJECT NO:	14142
SMRT FILE:	GI001-14242
DATE:	10-08-14

SHEET TITLE:
COVER SHEET

SHEET No.
GI001

© COPYRIGHT 2014 SMRT INC.