



**DEMOLITION GENERAL NOTES**

1. CONTRACTOR SHALL REMOVE ALL NON-METALLIC "ROMEX" CABLE AND ASSOCIATED JUNCTION BOXES FROM INTERIOR OF BUILDING. FOR BRANCH CIRCUITS STILL BEING UTILIZED AND NOT SPECIFIED AS BEING DEMOLISHED, PROVIDE ARMORED CABLE AND RECONNECT TO EXISTING/NEW PANELBOARDS.
2. CONTRACTOR SHALL COORDINATE DEMOLITION WITH INSTALLATION OF NEW ELECTRICAL EQUIPMENT.

**POWER ONE-LINE DEMOLITION KEY NOTES**

- ① CONDUIT AND CONDUCTORS TO REMAIN.
- ② REMOVE EXISTING CONDUIT AND CONDUCTORS BACK TO SOURCE.
- ③ REMOVE EXISTING PANEL, CONDUIT AND CONDUCTORS BACK TO SOURCE.
- ④ REMOVE EXISTING DISCONNECT, CONDUIT AND CONDUCTORS BACK TO SOURCE.
- ⑤ REMOVE EXISTING TRANSFORMER, CONDUIT AND CONDUCTORS BACK TO SOURCE.
- ⑥ REMOVE EXISTING JUNCTION BOX/WIREWAY, CONDUIT AND CONDUCTORS BACK TO SOURCE.
- ⑦ REMOVE EXISTING CIRCUIT BREAKER, CONDUIT AND CONDUCTORS BACK TO SOURCE.
- ⑧ EXISTING ELECTRICAL PANEL/EQUIPMENT REMAINS.
- ⑨ REMOVE EXISTING GENERATOR CONDUIT AND CONDUCTORS BACK TO SOURCE.
- ⑩ REMOVE EXISTING 120/208V PANELBOARD. EXISTING BRANCH CIRCUITS TO BE RECONNECTED. SEE NEW WORK RISER.
- ⑪ INTERRUPT CONDUIT, PULL BACK CONDUCTORS/REROUTE/RECONNECT. SEE DEMOLITION FLOOR PLAN ED6.3.
- ⑫ REMOVE EXISTING PANELBOARD AND SAVE FOR REUSE IN NEW WORK. REMOVE EXISTING CONDUIT AND CONDUCTORS BACK TO SOURCE.
- ⑬ REMOVE EXISTING CONDUCTORS. CONDUIT AND TUBS REMAINS.
- ⑭ REMOVE EXISTING BREAKERS AND BUSS GEAR FROM EXISTING PANELBOARD. ENCLOSURE OR "TUB" REMAINS.
- ⑮ COORDINATE WITH LOCAL UTILITY COMPANY FOR REMOVAL OF TRANSFORMER CONDUCTORS AND UTILITY OWNED EQUIPMENT.
- ⑯ EXISTING PANEL TO BE RELOCATED FOR TEMPORARY CONSTRUCTION POWER.
- ⑰ EQUIPMENT REMAINS FOR USE AS TEMPORARY CONSTRUCTION POWER.

11/25/09 ISSUED FOR BID

Mark Date Description

Issue Dates

Drawing Status

Drawing Title  
**ELECTRICAL DEMOLITION ONE-LINE DIAGRAM**

PA / PE: WRH Drawn By: RJB

Drawing Number

**ED40.0**