Approved for Historic Preservation
Certificate of Appropriateness
Date: 05/26/16

MODERN ENERGY SOLUTIONS

RLD Inc.

HEAT PUMP SALES & SERVICE

Dave's World Inc.
16 Summer Street
Dover-Foxcroft ME 04426
Phone: 207-564-2784 or 207-924-6964
Fax: 207-564-7204
E-mail: info@davesworld.com
www.davesworld.com

Invoice #

mer Information			
Date:	2/29/2016	$25,431.46	50% Deposit Required
Name	Catholic Charities		Amount Paid (deposit)
Address	87 High St		Please Indicate Method of Payment
City/State/Zip	Portland, ME		Credit Card
Phone			Financing
Alt. Phone#			Cash
e-mail			Check#
		A/R Notes	
		** MUST CHECK METHOD OF PAYMENT **	

Outside Salesperson **Mark Roy 207-717-0097**

Quantity	Description	Total
	HEAT PUMP QUOTE	
2	Mitsubishi/Fujitsu High Efficiency Heat Pump(s)	$49,412.91
	Proposal for the installation of TWO Mitsubishi MXZ-8C48NAHZ . ONE 3 zone branch box to be installed with the first 8C48 unit which will be connected to ONE MSZ-FH18NA to be installed in the Lobster Room ONE MSZ-FH18NA to be installed in the Whale Room and ONE MSZ-FH12NA to be installed in the Dolphin Room. ONE 5 zone branch box will be connected to the other 8C48 unit which will be connected to FIVE MSZ-FH12NA heads. ONE head to be installed in each of the following rooms, Play Room, Business Office, Directors Office, Toddler Room and Lounge. A total of EIGHT installed between both outdoor units. No indoor heads quoted for bathrooms (not an ideal application). Both outdoor units to be installed on 18" ground mount stands and pads on side of building with weather caps. Branch boxes to be centrally located in basement of school. Electrical service will need upgrade and outdoor GFI's will be needed. Dave Bennett has already visited job site so he should have an idea of what will be involved electrically. Property may be rebate eligible, however, no rebates are listed on this quote. Site visit will be required by both the lead electrician and lead heat pump installer prior to installation to work through final layout. Install may need to be done after normal business hours due to client restrictions. Any additional costs for construction, repair, historical society requirments or finish carpentry are not quoted and may be subject to additional charge. ***All materials, labor, and electrical work is included in the 'Total Amount Due' box. Dave's World is a Qualified Partner for Efficiency Maine's Multi-Family and Commercial rebate programs.***	
	Outdoor GFI Material & Labor:	**$200.00**
	Sub-Panel Materials & Labor:	**$1,250.00**
		$0.00
	24 Month Buy Back/Satisfaction Guarantee For Mitusbishi and Fujitsu Heat Pump(s)	**$50,862.91**
	Thank You For The Opportunity To Earn Your Business efficiency MAINE Rebate Program	**$0.00**

ALL MATERIAL IS GUARANTEED TO AS SPECIFIED. ALL WORK TO BE COMPLETED IN A PROFESSIONAL MANNER ACCORDING TO STANDARD PRACTICES. ANY ALTERATION OR DEVIATION FROM ABOVE SPECIFICATIONS WILL BE IN ADDITION TO THIS QUOTE, IF INVOLVING EXTRA COSTS. ALL AGREEMENTS CONTINGENT UPON DELAYS BEYOND OUR CONTROL. PURCHASER AGREES TO PAY ALL COST OF COLLECTION, INCLUDING ATTORNEY'S FEES.

Net Cost After Rebate	**$50,862.91**
Total Due at Completion (after deposit)	**$50,862.91**
Approximate Monthly Payment	

Please sign one copy and check your preferred method of payment in the Top Right of this Form. This estimate is good for 15 days from above Date.

AUTHORIZED SIGNATURE (Salesperson)

ACCEPTANCE SIGNATURE (Customer)

DATE

PRACTICING AWESOMENESS...