

COLUMN SCHEDULE	
MARK	DESIGNATION
C1	HSS 6x6x1/4"
C2	HSS 6x6x5/16"
C3	HSS 6x6x3/8"
C4	HSS 6x6x1/2"
C5	HSS 6x6x5/8"
C6	HSS 7x7x1/2"
C7	HSS 7x7x5/8"
C8	HSS 8x8x1/2"
C9	W18x60
C10	HSS 4x4x1/4"
C11	HSS 8x8x5/8"
C12	HSS 8x6x5/8"
C13	HSS 10x6x1/2"
C14	HSS12x6x1/2"

NOTE:
1. SPLICE ALL COLUMNS 4'-0" ABOVE 3RD FLOOR TOP OF STEEL.
2. 18FGx FLOOR JOIST GIRDERS SHOWN W/ LOADS ON SEPARATE SHEET S4.04 & S4.05.
3. TJ = TIE JOIST

PLAN NORTH

1 SECOND FLOOR FRAMING PLAN
3/32" = 1'-0"

© Copyright 2016 Opechee Construction Corporation

Monday, March 28, 2016 2:45:17 PM

BECKER STRUCTURAL ENGINEERS
75 York Street, Portland, Maine 04101
207.879.1838 ■ beckerstructural.com

OPECHEE CONSTRUCTION CORPORATION
11 CORPORATE DRIVE ■ BELMONT ■ NH 03220
PHONE (603) 527-9090 ■ WWW.OPECHEE.COM

STATE OF MAINE
TODD M. NEAL
NO. 9406
LICENSED
PROFESSIONAL ENGINEER

Mixed Use Development

York & High Street
Portland, Maine

REVISION:
02/19/16 PER BSE FRAMING MARKUPS
03/17/16 BSE CONSTRUCTION MARKUPS

ISSUED:
01/13/16 FOR STRUCTURAL REVIEW
02/17/16 FOR STRUCTURAL REVIEW
FOR BUILDING PERMIT 02/26/16
03/28/16 FOR CONSTRUCTION

project architect: KAK
drawn by: JJD

SECOND FLR. FRAMING PLAN

sheet number:
S3.01